



MEMOIRS OF THE  
ARCHÆOLOGICAL SURVEY OF INDIA

---

No. 43

AN ARCHÆOLOGICAL TOUR IN  
GEDROSIA

SIR AUREL STEIN, K.C.I.E., PH.D., D. LITT., D. SC.,  
*Archæological Survey of India (ret.), Fellow of the British Academy*

WITH AN APPENDIX BY  
LT.-COLONEL R. B. SEWELL, I.M.S., F.Z.S., F.L.S.,  
*Director, Zoological Survey of India*

AND

B S GUHA, A.M., PH.D.,  
*Anthropologist, Zoological Survey of India*



CALCUTTA GOVERNMENT OF INDIA  
CENTRAL PUBLICATION BRANCH

1931

Government of India Publications are obtainable from the Government of India Central Publication Branch, 3, Government Place, West Calcutta, and from the following Agents. —

## EUROPE

OFFICE OF THE HIGH COMMISSIONER FOR INDIA

INDIA HOUSE ALDWICH LONDON W C 2

And at all Booksellers

INDIA AND CEYLON Provincial Book Depôts

Thacker Spink & Co. Calcutta and Simla  
W. Newman & Co. Ltd. Calcutta  
S. K. Lahiri & Co. Calcutta  
The Indian School Supply Depôt, 308 B  
Calcutta  
Batterworth & Co. (India) Ltd. Calcutta  
M. C. Saxeena & Sons 15 College Square Cal  
Standard Literature Company Limited Cal  
Association Press, Calcutta  
Chakraverty Chatterjee & Co. Ltd. 13 College Square,  
Calcutta  
The Book Company Calcutta  
James Murray & Co. 12 Government Place Calcutta  
(Meteorological Publications only)  
Rav Choudhury & Co. 685 Anutosh Mukherjee R  
Calcutta

The Standard Bookstall Karachi Quetta, Delhi Murree  
and Rawalpindi

Road Rawalpindi,

The Standard Book Depôt Lahore Narnatal Mussoora,  
Dulhousie, Ambul Cantonment and Delhi,  
The North India Christian Tract and Book Society 18,  
Clare Road Allahabad

Daryaganj,

Manager Dewal Kashore Press, Lucknow  
The Upper India Publishing House Ltd. Literature  
Palace Amuddaula Park Lucknow  
R. Subh M. Gulab Singh & Sons Mufid Am Press Lahore  
and Allahabad

mitha

The Insurance Publicity Co. Ltd. Lahore  
The Punjab Religious Book Society Lahore  
The Commercial Book Co. Lahore  
The University Book Agency Kachan Road Lahore  
Manager of the Imperial Book Depot, 63 Gladney Chawk  
Street Delhi

J. N. J. and Bros. Delhi  
Fano Book Agency New Delhi & Simla  
Oxford Book and Stationery Company Delhi, Lahore  
Simla Meerut and Calcutta  
Supdt. American Baptist Mission Press Rangoon  
Burma Book Club Ltd. Rangoon  
S. C. Lal Kar Proprietor Students & Co. Cooch Behar  
The Manager The Indian Book Shop Benares City  
Nand Lal and Bros. Chowk Benares City  
The Sewillputter Co-operative Trading Union Ltd  
Saidpur (S. I. R.)

Pragnath Press & Sons, Patna City  
The Students Emporium Patna  
K. L. Mathur & Bros. Gurgaon Patna City  
Kamala Book Stores Bangalore, Patna  
G. Banerjee and Bros. Ranchi  
M. C. Kotha Raipura Road Baroda  
The Hyderabad Book Depot Chaderghat Hyderabad  
(Deccan)  
S. Krishnaswami & Co. Teppakulam P. O. Trichinopoly  
Fort  
Kamatala Publishing House, Bangalore City  
B. Ramaiah, Fort Bangalore City  
S. perintendent Bangalore Press Lake View Mysore Road  
Bangalore City

Bombay  
The Manager Oriental Book Supplying Agency 15  
Shankar Poonam City  
Rama K. Shinde Bros. Opposite V. S. Ramdas Poonam City  
S. I. Bookstall 21 Budhwar Poonam  
Manikdas & Sons Booksellers and Publishers Bhaga  
Tallo Surat  
The Standard Book and Stationery Co. 3233 Arbab Road  
Lahore  
R. B. Unnikrishnan & Co. The Bharat Book Depôt Dharwar  
The Students Union Book Depôt, Dharwar  
S. R. Shinde Kamatala Postala Bhandara Melamuddi  
Dharwar

Agents in Palestine — Shamataky, J. R. Salem  
\* Agent for publications on credit only

(AC)

M. C.

# LIST OF CONTENTS.

---

	PAGE.
INTRODUCTORY	1
CHAPTER I—A Sketch of geographical features	
SECTION 1 Notes on Kharan	3
ii Notes on Makran	7
iii Notes on Jhalawan and the Brahuis	12
CHAPTER II—Remains in Kharan	
SECTION 1 From Quetta to Nauruz Kalat	15
ii Sites in North Eastern Kharan	21
iii The mounds of Besema and Zayak	29
CHAPTER III—Old sites in Rakhshan and Parom	
SECTION 1 Remains at the head of Rakhshan	34
ii In the Panjgur Oasis	41
iii The basin of Parom	46
CHAPTER IV—In the Kej Valley and Dasht	
SECTION 1 First stay at Turbat	52
ii Along the Dasht Valley	56
iii The remains of Suktagendor	60
CHAPTER V—Remains on Makran Coast	
SECTION 1 Old remains near Gwadar	71
ii The Dambis of Jiwanri	77
iii From Gwadar Bay to Mand and Turbat	82
CHAPTER VI—Sites in the Kej Valley	
SECTION 1 The burial cairns of Zangian	86
ii The mound of Shahi tump	88
iii Burial deposits on Shahi tump	93
iv Funerary pottery at Shahi tump	98
CHAPTER VII—Ruined sites of Kolwa	
SECTION 1 Mounds by the North and South Routes	104
ii From Madak Kalat to Gushanak	111
iii The mound of Kulh	118
CHAPTER VIII—Ancient remains between Kolwa and Jhau	
SECTION 1 Ruined mounds of Bazdad and Awaran	12
ii The sites of Nundara and Jhau	132
iii The ruins of Shah damb Nundara	138
CHAPTER IX—Ruined sites of Mashkai	
SECTION 1 Gabar bands and mounds on lower Mashkai River	144
ii The mounds of Gajar and Shadunzar	150
iii Remains of the Mchi site	154
iv Remains examined in Upper Mashkai Gushak and Dal	163
CHAPTER X—Along the central valley of Jhalawan and Sarawan	
SECTION 1 Remains at Khozdar and Wadh	170
ii Baghawan mounds and the Gabar bands of Lakoman	178
iii From Kalat to Mastung	183
APPENDIX—Report on a Collection of Bones	190



## ADDENDA ET CORRIGENDA.

Plate XVII *For* Sh T vi 13 *b read* Sh T vi 13 i

Plan 4 *For* Sukhtagen dor *read* Sukhtagen dor

Plan 6 *For* Burial Cairnts *read* Burial Cairns

Plan 7 *For* Plan on line A B *read* Section on line A B

*Add* —Line of crosses marks extent of pottery-strewn area

# LIST OF ILLUSTRATIONS

— + —

- Fig 1—Mini of Kalat from south east  
 2—Burial enclosure near Azad gaz  
 3—Jal gorge below Karchun  
 4—Toji mound seen from above spring  
 5—Zarat- B'bi near Nag  
 6—Mini kalat Turbat from south east  
 7—Excavated rooms a b on Kargushk Mound  
 8—Kohna kalat mound Panjgur seen from east  
 9—Main fort of Mir Turbat seen from south west corner  
 10—South wall of Mini Turbat  
 11—North west corner of enclosed area Suktagen dor seen from above east wall  
 12—North west corner of enclosed area Suktagen dor with cutting  
 13—South west corner of enclosed area Suktagen dor  
 14—Interior of enclosed area Suktagen dor looking to south west  
 15—Nullah with wall Su in Suktagen dor seen from west  
 16—East wall Suktagen dor with north east corner  
 17—Gate at south west corner of enclosed area Suktagen dor seen from outside  
 18—Cinerary pots at foot of east wall Suktagen dor  
 19—Ruined Gumbaz south of Gwadar town seen from east  
 20—Ma Masura's tomb Bajoi Baghwana  
 21—Burial cairns at Gatt below Jabal Mahdi Gwadar  
 22—Burial cairn at Take dap  
 23—Barrage on Batel hill above Gwadar  
 24—Burial cairns at Zing an Turbat looking west  
 25—Shahi tump mound seen from south west during excavation  
 26—Funerary vessels around bodies a b section vii Shah tump before clearing  
 27—Sections viii x on Shah tump in course of excavation  
 28—Nests of funerary bowls etc in section vi Shah tump  
 29—Sections v vii Shah tump in course of excavation  
 30—Funerary vessels in section vii Shah tump in course of clearing  
 31—Buried bodies A B in section vii Shah tump after clearing  
 32—Buried bodies A B in section vii Shah tump seen closer  
 33—Madak kalat mound and ruined fort seen from S W  
 34—Feroz Khan Jamb seen from south-east  
 35—Buttress wall below Sing kalat Malar  
 36—Ruined dwelling within inner enclosure on Zik mound  
 37—Kull mound seen from NNW  
 38—Structure I Kull mound seen from north after excavation

Fig 39 —Wall cleared within enclosure on mound Rōdkan

- „ 40 —Room I vii. Kulh mound after clearing, from south west
- „ 41 —Fragments of decorated pots also grinding stones excavated in dwelling I Kulh.
- „ 42 —Large jar from V 1, grinding stones and pieces of decorated pottery from dwelling I vii Kulh mound
- „ 43 —Remains of dwellings near centre of top of Tikri-damb, Nundara
- „ 44 —Siah damb Nundara seen from south west
- „ 45,—Portion of Tikri-damb Nundara seen from south west
- „ 46 —Wall of ruined structure on NE side of Adesta-damb Jhan
- „ 47 —East face of Siah damb Nundara with flood bed below
- „ 48 —Walls of ruined dwellings above north east face of Siah damb Nundara
- „ 49 —Pier and clay terrace north of it NW end of Siah damb Nundara
- „ 50 —Walls of ruined dwellings on east face of Siah damb Nundara
- „ 51 —Ruined structures II IV Siah damb, Nundara from south east
- „ 52 —Interior of structure II Siah damb Nundara before excavation
- „ 53 —Ruins of structures above ESD ravine Siah-damb Nundara seen from south
- „ 54 —Structure I Siah damb, Nundara after excavation
- „ 55 —Central pillar within room II 1, Siah damb Nundara after excavation
- „ 56 —Structure I with dwelling III behind it Siah damb Nundara after excavation.
- „ 57 —South west portion of Mchi damb with terrace II in foreground before clearing
- „ 58 —Mound of Shahd nza with burial cairn in foreground
- „ 59 —Fort Damb at Gayer near from south
- „ 60 —Cinerary pot from burial ground Yak kandagi shank, Gwaryak
- „ 61 —Gabar band above Mugah
- „ 62.—Spet bulandi mound Mustang seen from south east
- „ 63 —Wall face of 'Gabar-band' near Lakorian
- „ 64 —Eastern end of 'Gabar band' near Lalorian

# LIST OF PLATES.

(N B The scales of ep od clw marked are app or max e)

- Plates
- I—Specimens of pottery from Kharan sites Scale 1/3
  - II—Specimens of pottery from sites in Ralhsban Makran Scale 1/3
  - III—Specimens of pottery from sites in Parom Makran Scale 2/5
  - IV—Specimens of pottery from sites in Kej and Dasht Valleys Makran Scale 1/3
  - V—Specimens of pottery from Kargushki Suktagedor and Jiwanni Makran Scale 1/3
  - VI—Specimens of objects in stone copper clay etc from Suktagedor Dasht Scale 3/5
  - VII—Specimens of objects in clay stone and meta from Suktagedor and Jiwanni Dasht Scale 1/3
  - VIII—Specimens of pottery vessels from burial cairns Jiwanni Scale 1/4
  - IX—Specimens of pottery vessels from burial cairns Jiwanni Dasht Scale 1/3
  - X—Specimens of pottery etc from Nazarabad and other sites in Nihung and Kej valley Makran Scale 2/5
  - XI—Specimens of pottery etc from Zangan and Shahitump Kej valley Makran Scale 1/4
  - XII—Specimens of pottery etc from Shahitump mound Kej Valley Makran Scale 1/3
  - XIII—Specimens of pottery and objects in stone and copper from Shahitump mound Kej Valley Makran Scale 2/5
  - XIV—Objects in stone clay and copper from Shahitump mound Kej valley Makran Scale 3/7
  - XV—Funeral pottery from Shahitump mound Kej valley Makran Scale 1/5
  - XVI—Funeral pottery from Shahitump mound Kej valley Makran Scale 1/3
  - XVII—Funeral pottery from Shahitump mound Kej valley Makran Scale 1/5
  - XVIII—Funeral pottery from Shahitump mound Kej valley Makran Scale 2/5
  - XIX—Funeral pottery from Shahitump mound Kej valley Makran Scale 1/3
  - XX—Specimens of pottery from sites in Kolwa Makran Scale 1/3
  - XXI—Specimens of pottery from Kulli and other sites in Kolwa, Makran Scale 1/3
  - XXII—Specimens of pottery and objects in glass and copper from Kulli and Gushanah Kolwa Makran Scale 3/5
  - XXIII—Specimens of pottery also objects in stone and clay from Kulli site Kolwa Makran Scale 2/5
  - XXIV—Specimens of pottery from sites of Kolwa Awaran and Mundara Makran Scale 1
  - XXV—Specimens of pottery from sites of Kolwa Jhau and Mundara Scale 1
  - XXVI—Specimens of pottery from Jhau and Mundara Jhalavaz Scale 1/5

Plates XXVII—Specimens of pottery and objects in clay from sites of Nundara and Mashkan Jhalawan Scale 1/3

XXVIII—Specimens of pottery from Meh-damb in Mashkan Jhalawan Scale 1/5

XXIX—Specimens of pottery from Meh-damb in Mashkan Jhalawan Scale 1/3

XXX—Specimens of pottery from Meh-damb in Mashkan Jhalawan Scale 2/7

XXXI—Terracotta figurines and other small objects in clay bone etc from Meh-damb Mashkan Jhalawan Scale 4/5

XXXII—Objects in copper from Meh-damb Mashkan and specimens of pottery from Mastung sites Sarawan Scale 2/5

XXXIII—Specimens of pottery from Nal and other sites of Jhalawan Scale 1/3

PLANS 1 (a) Sketch plan of Loji Site

(b) Walled enclosure with Muhammadan tombs Azad-guz Kharan

2 (a) Sketch plan of Pir Shah Hassan Mound Kharan

(b) Sketch plan of sites at Nag Rakhshan

3 (a) Sketch plan of Kargushki-damb Rakhshan

(b) Plan and section of excavated portion of ruined structure at Kargushki-damb

4 (a) Sketch plan of Sukhtagen-dor Dasht

(b) Plan of ruined dwelling at A Sukhtagen-dor

5 Sketch plan of ancient burial mounds on Lak Plateau near Jwanra

6 Sketch plan of burial mounds at Zangian Turbat

7 (a) Sketch plan of Shahi-tump Turbat

(b) Section at excavated area on line A-B

(c) Section of trench Shahi-tump

8 (a) Sketch plan of ruined mound, Gate-dap

(b) Sketch plan of Sogak Mound

(c) Sketch plan of Zuk Kalat

(d) Sketch plan of Sugi Kalat Malir

9 (a) Sketch plan of Kulh Site Kolah

(b) Sketch of elevation showing masonry on wall face of dwelling I

(c) Sketch plan and sections of ruined dwelling I

(d) Sketch plan of ruined dwelling V

10 (a) Sketch plan of Shih-damb Jhau

(b) Sketch plan of Spit-bulandi Mastung

11 (a) Sketch plan of Shah-damb Nundara

(b) Plan and section of dwellings I-II

12 Sketch plan of Meh-damb Jehel

13 (a) Sketch plan of Gabar-band Lakoman

(b) Rough sketch of Gabar-bands near Ughar Mashkan

Skeleton Map of Kalat State showing ancient sites surveyed by Sir Aurel Stein K.C.I.E. in Sarawan, Jhalawan and Makran

# AN ARCHÆOLOGICAL TOUR IN GEDROSIA

BY

SIR AUREL STEIN, K C I E, P H D., D L I T T D S c

---

## INTRODUCTORY

THE explorations described in this report formed the continuation and necessary complement of the tour which in the early portion of 1927 had taken me along the North West Frontier from the Kurram river down through Waziristan and the northern districts of Baluchistan. In the introductory remarks of the *Memor* dealing with the results of this tour I have had already occasion to refer to the reasons which had prompted me in 1925 to propose to Sir John Marshall an archæological reconnaissance of the Indo-Iranian border lands comprised within the limits of British Baluchistan. Foremost among these reasons was the special interest bound to be attracted to this wide and in an antiquarian sense as yet little known region through the important discoveries attending the excavations carried out under Sir John Marshall's direction at the sites of Mohenjo daro and Harappa. The area of the prehistoric civilization thus revealed on the lower Indus had extended also into the hill tracts adjoining westwards as was conclusively proved by the abundant finds of interest which had rewarded Mr Hargreaves thorough exploration in 1924 of a burial ground of chalcolithic times at Nal in the territory of the Kalat State.

Search of prehistoric remains west of Indus.—It had been recognized almost from the first that there were unmistakable links between what is now conveniently designated as the early Indus civilization and the remains brought to light from certain prehistoric sites of Iran and Mesopotamia. Apparent similarities noticed between the characters as yet undeciphered on seals from Mohenjo daro and Harappa and those of the earliest Sumerian script would necessarily help to direct attention to the possibility of a line of closer relations having lain through the territories which stretch from the terminal course of the Indus to the head of the Persian Gulf. Of these territories the easternmost, extending from the Indus for upwards of 300 miles towards the Persian border, and once forming part of ancient Gedrosia, are now included in the Kalāt State under the control of the Baluchistan administration. Hence a

systematic search on this ground for remains of prehistoric settlements continuing the chain westwards distinctly recommended itself as both useful and practicable.

Interest of ancient Gedrosia—It was into that far stretched portion of Gedrosia which comprises the territories of Kharian Makran and Thalawan between the Arabian Sea in the south and the deserts adjoining Afghanistan in the north that I had wished to extend the investigation started at the beginning of 1927 far away in the north near the confines of ancient Gandhara. The effective support of Sir John Marshall secured the approval of the Government of India also for this portion of my programme first broached in 1925 together with an adequate grant for its execution.

Apart from the special archaeological interest already indicated there were considerations of a geographical and historical order which made the opportunity thus generously afforded particularly welcome to me. On the one side there appeared good reason to hope that close examination of ancient remains traced in a region now so arid and for the most part truly desertic would help to throw fresh light on the much discussed problem of desiccation with which I had such ample occasion to concern myself in the course of my Central Asian explorations. On the other side this ground of ancient Gedrosia however small its importance economically and politically has been ever since the times of the Achaemenidian empire had once been the scene of a notable historical episode. Alexander's famous march through its torrid wastes on his return from India. Notwithstanding much learned speculation concerning the exact route followed by the great conqueror, some topographical details may continue to baffle the critical student even when examined on the ground. But the comparatively ample and trustworthy accounts in our classical sources of the observations made on that hazardous exploit could not fail to be of distinct geographical interest if compared with the present conditions of that region or with those which archaeological evidence might reveal as prevailing in far earlier times.

Sketch of essential, geographical facts—The considerations just referred to together with the important bearing which the physical features in the areas examined must have upon the interpretation of the ancient remains there traced have made it advisable to prefix a brief sketch of essential geographical facts concerning those areas to the record of my antiquarian observations. Such a sketch has appeared all the more advisable in view of the scantiness of the information which is to be found in a readily accessible form about that remote and in its present conditions far from attractive region. The conclusions to be drawn from a comparison of these conditions with what the evidence of the earliest traceable remains indicates may best be comprehensively reviewed in another place.

Help of local authorities—Succinct as the data furnished in this preliminary sketch must needs be they will suffice to convey some idea of the great extent of the ground which had to be covered by my explorations and of the difficulties to be faced on account of climatic drawbacks absence of local resources limitations of time and labour etc. It would have been quite

impossible to meet these difficulties but for the most willing and effective help of the authorities of the Kalat State which was secured to me from the outset through the arrangements kindly made by Colonel T H KEYES CMG CIE, Political Agent Kalat. In preparing the plan of my surveys I derived the utmost advantage from the shrewd advice of this distinguished political officer who through his prolonged association with the State has acquired exceptional knowledge of all its different parts. The instructions issued on my behalf by Nawab SIR MIR SHAMS SHAH, KCIE ISO, Wazir Azam of Kalat assured to me throughout whatever assistance in the matter of guidance, transport and labour could be rendered by the local administration in Makran and Jhalawan. In Kharan I enjoyed similar advantages through the help of its chief, Nawab HABIBULLAH KHAN.

Great extent of region surveyed—But notwithstanding all this assistance a reconnaissance survey of ancient sites scattered over so vast an area from the diamageless Mashkel basin to the coast of the Arabian Sea and from the Persian border to the southernmost tributaries of the Indus, would have called for several cold weather tours had not the construction during the last few years of tracks practicable for motor transport during the greatest part of the year permitted a saving of time and effort undreamt of before on such trying ground. These tracks owe their existence mainly to Colonel Keyes' energy. They made it possible for me to move rapidly along the great lateral valleys of Makran those of Lej and Rakhshan, to wherever ancient sites could be traced in them. Similar facilities for rapid access could thus be gained to the remains of prehistoric settlements in the long stretched valleys which descend through the hills of Jhalawan towards the sea. The advantages thus secured were duly set off by the contrast of the long weary marches which had to be done with camels through desert hills or barren plains in order to reach ground of archaeological interest away from those main valleys.

Character and limits of reconnaissance survey—The circumstances just briefly indicated will explain how it became possible for me by dint of much hard travel to extend my archaeological survey over an area which taking the whole of the three territories together measures some 270 miles from north to south and over 300 miles from east to west. The fact of this survey having to be accomplished in the course of four and a half months will help to account also for the scope and character of the object aimed at. It was my endeavour within the limits imposed by the available measure of time and accessibility to examine all ancient remains I could trace on the surface and to determine their general character and relative epoch. Wherever trial excavations seemed advisable for this purpose and local conditions would allow of them they had to be confined to the measure needed for securing data sufficient to settle essential points. The complete exploration of remains which at some of the sites traced might well claim months, if not seasons could not come within the purview of my survey. In all such cases I must rest content to have indicated to future excavators the places to which their labours may be directed with advantage, and to leave it to them to supplement or modify the conclusions



to which I was led by the observations and the materials obtained in the course of my partial exploration

**Limitations of report**—With regard to the report here presented of the results of my survey I must repeat what I have already stated as to the limitations of my previous report on the explorations in Waziristan and Northern Baluchistan. It has been my endeavour to give a full account of all I was able to observe and note at each surveyed site and by description and illustrations adequately to represent the general character of the archaeological materials secured there. But neither the range of my competence nor the time available to me for the preparation of this report will permit of my attempting here a systematic analysis of these abundant materials.

**Prehistoric remains lack of chronological control**—They are almost exclusively remains of prehistoric civilization and consequently lack chronological control by datable finds. Well marked variations of style exhibited by the plentiful decorated ceramic wares, mainly painted clearly betoken different periods of deposit. Indications derived from modifications of design, colour, etc. in these wares as well as protracted observations on the ground as to implements, structural materials, burial customs and the like have led me to form some quasi-empirical conclusions as to the sequence of these periods. But definite stratigraphic evidence as regards all these remains is still scanty. Hence it appears to me that their systematic classification must await on the one hand expert examination of the ceramic materials in respect of their technique and fabric apart from decorative design and on the other close comparison of the same with corresponding relics from other archaeological fields.

**Comparison of ceramic remains**—My acquaintance with the latter is restricted to the pottery remains recovered by me from wind-eroded sites in the desert delta of Sistan<sup>1</sup> and from the debris mounds explored by me on the Waziristan border and in Northern Baluchistan during my tour of 1927<sup>2</sup>. In the case of both these areas the painted pottery generally assignable to Chalcolithic times shows very close affinity with the ceramic wares from different sites examined in Malir and Jhalawan. But without evidence of stratification it is not possible there definitely to trace successive stages of development. The plentiful and well preserved funerary pottery from Nal which I know for the present only from Mr Hargreaves' very instructive preliminary report on his excavations of 1924<sup>3</sup> and from the specimens of earlier finds deposited in the Quetta Museum represents, as far as I can judge, a single characteristic type since found by me also at several of the sites to be described below.

I have had so far no opportunity to familiarize myself with the probably abundant materials of painted ceramic ware which the excavations at Mohenjodaro and Harappa have yielded. But there is good reason to hope that when

<sup>1</sup> See *Sistan: Inner and Outer*, pp. 349-50. Andrews, 'Neolithic pottery in Sistan', *Burlington Magazine*, December 1920.

<sup>2</sup> See *Sistan: An Archaeological Tour in Waziristan and Northern Baluchistan*, *Memoirs of the Archaeological Survey of India*, No. 37.

<sup>3</sup> See *Annual Report of the Archaeological Survey of India*, 1925-26, pp. 64-6.

fully published they will also afford much useful guidance for the close study of the materials brought back from my recent explorations for certain of the terracotta figurines recovered at Mohenjo daro<sup>4</sup> show a very striking resemblance to corresponding relics which my excavations at certain of the Makran and Jhalawan sites have brought to light in remarkable abundance

It is certain that close comparison of the mass of important relics of chalcolithic civilization recovered by the Pumpelly expedition in Transcaspiæ, by Dr Andersson's explorations in Central and Western China and by excavations at Susa and other Persian and Mesopotamian sites<sup>5</sup> could reveal to experts many interesting points of contact in the materials ceramic and other brought back from both my latest tours. But I cannot expect to command leisure and needful facilities for such study before hoped for exploratory labours call me to other fields. I feel hence obliged to express the earnest hope that prompt publication of the present report<sup>6</sup> will suffice to attract the attention of competent students in the West to these materials particularly the ceramic ones and that suitable means may be found to render close examination of the originals easier for them eventually through a temporary exhibition of selected specimens at some convenient place in London.

## CHAPTER I.—A SKETCH OF GEOGRAPHICAL FEATURES

### SECTION 1.—NOTES ON KHĀRĀN

The portion of the Kalat State over which my tour extended comprises the three territories of Khāran Makran and Jhalawan. Though they share many essential characteristics in physical aspects and in climatic economic and ethnic conditions yet well defined geographical features account for their separation in history and tradition. The fact that with a total extent of about 62 000 square miles they contain only a population of less than 180 000 souls according to the latest census (1920 21) suffices to indicate their uniform want of natural resources. It also helps to explain the very scanty notice they receive in works dealing with India and its borderlands towards Iran and also the obscurity that in Lord Curzon's just words has rarely lifted from these regions<sup>7</sup>

Sources of geographical information.—But a mass of useful and reliable information about those territories collected largely under the orders of that lamented great statesman and scholar is now to be found in the

<sup>4</sup> See *ibid.* e.g. Plates XXX XLIII.

<sup>5</sup> For a convenient synopsis of the publications dealing with painted ceramic remains found at neolithic and chalcolithic sites from China to Western Asia cf. Arne Furumö's *Painted Stone Age Pottery from the Province of Honan China in Palæontologica Sinica Series D Vol I fascicle 2* Peking, 1920. Cf. also H. Schmidt, *Prähistorische und Orients Zeitschrift für Ethnologie*, 1924 fasc. 5 6.

<sup>6</sup> Submitted in August 1923 to the Director General of Archaeology who kindly arranged at his office for the subsequent photographic reproduction of the specimens shown in Plates I XXXV.

<sup>7</sup> Cf. Curzon *Persia* ii. p. 204.

Baluchistan Gazetteer volumes which deal with them.<sup>1a</sup> It is to this very valuable publication prepared mainly by Mr R HUGHES BULLER I.C.S. and completed by Major C F MINCHIN D.S.O. I.A. that reference must be made for any data topographical economic ethnographic or other that may deserve consideration in connexion with the antiquarian results of my journey. The remarks offered in this section are intended merely to present the essential geographical features of those territories in a bird's eye view as it were and in the barest outlines. I may conveniently refer in a note below to those cartographical publications of the Survey of India which will be of use in following the general observations here offered and the topographical details connected with my explorations.<sup>2</sup>

**Barrenness of Kharan.**—The territory of Kharan with which we may begin our survey is almost entirely confined to the great drainageless basin which extends from the eastern limits of the Persian provinces of Sistan and Sarhad to the north western hill ranges of Jhalawan. In the north the rugged range of Raskoh separates it from the equally arid tracts of Chagai. To the south the Sialhan range forms the boundary towards Makran. By far the greatest portion of the country is an utterly barren waste the central area being filled by a great desert of moving sands. The few rivers which descend into the basin from the enclosing ranges do not carry water for more than a part of the year and only in the case of heavy floods do they reach their terminal depressions or Hamus. Owing to the great aridity of the climate cultivation is entirely dependent on what irrigation is obtainable from the floods brought down by the rivers and hill torrents. This supply even in good seasons is too scanty to permit of more than an insignificant portion of the land (estimated at about 25 per cent. of the total area) to be made productive.<sup>3</sup> Most even of the agricultural population depend for their maintenance also on pastoral occupations and in consequence are semi-nomadic while the rest live mainly by their flocks and the breeding and hire of camels.

**Scantiness of population.**—Such conditions sufficiently explain why with a total area of some 14,200 square miles Kharan can maintain a population

<sup>1a</sup> See Baluchistan District Gazetteer Series Vol VII Makran Text and Appendices by R Hughes Buller I.C.S. Bombay 1906 Vol VIIA *Kharan Text and Appendices* by Major C F Minchin D.S.O. I.A. Bombay 1907 Vol VII B *Jhalawan* Bombay 1907

Very useful supplements to these volumes are furnished in the report of F R Dennis Bray on the Baluchistan Census of 1911 and in the Baluchistan District Gazetteer Series B volume *Settlements Village Statistics* by E B Denny Town and Districts of Baluchistan 1909.

<sup>2</sup> See

recommenced survey of the coast and islands of the Arabian Sea and Adjacent Countries Series for Kharan Makran and Jhalawan together with portions of Persian Makran Afghania and Baluchistan and the Indus valley on the scale of 1 : 1,000,000.

In details of the ground along the route followed on my tour the Degree Sheet Nos. 31G J K M N O (R K I 3 A B C F C I) on the scale of 1 : 62,500 (2 1/2 inches to 4 miles) published for official use and may be consulted. The sheets for the most part reproduce the first proper survey made of these portions of British India in the middle of the last century. It is satisfactory to know that a fresh survey is continuing and I especially desire also with regard to the correct record of local names and a case of cultivation.

<sup>3</sup> Cf. Kharan Gazetteer p. 91 sq.

of only about two souls per square mile<sup>4</sup> and why emigration largely temporary to the Helmand valley and Sind is prevalent. The precarious nature of cultivation accounts also for the almost entire absence of permanent villages in Kharan the only one of any size being Kharan kalat the seat of its chief. Were it not for the plentiful produce of the date trees which provide the staple crop in certain localities of the south west and permit of export in exchange for grain the population of Kharan would be still more limited. That it was in former times considerably larger has been rightly inferred from the great number of massive stone dams known as Gabarbands and supporting what were once terraced fields they are to be found in now utterly desolate valleys of the hill tracts adjoining the great basin<sup>5</sup>. I shall have occasion fully to discuss this evidence when describing the corresponding remains examined in Jhalawan where they are equally frequent<sup>6</sup>.

Character of population.—The open configuration of the Kharan basin at its north western extremity offers easier access from Sistan than from any other adjacent territory. This adequately explains why the very scanty indications concerning the early and mediæval history of Kharan point to some closer connexion with that important and once rich province of Iran the ancient Drangiana. It also accounts for the comparatively homogenous character of its population. With the exception of the mostly nomadic Brahui tribes in the hills adjacent to Jhalawan it speaks western Baluchi and is manifestly of Iranian stock. Owing to the nature of the country mostly desert and lacking even a single oasis of any importance Kharan could never have served as a passage land for trade migrations or important military operations. But on the other hand this isolation and the hard conditions of life appear to have preserved more vigour and enterprise in the race than is to be found among the Baluch of Makran. This together with the inhospitable character of their own country probably helps to account for the far reaching activities as raiders and fighters which their chiefs of the Nausherwani clan were able to carry on right down to the third quarter of the last century at the expense of their neighbours to the north east and south<sup>7</sup>.

## SECTION II—NOTES ON MAKRAṆ

Configuration of Makran territory coastal belt.—Makran to which we may now turn in the south is a much larger and diversified territory. The fact that its area estimated at about 26 600 square miles maintains a

<sup>4</sup> The Census of 1920-2 showed a population of 97 38 of Baluch District Gazetteer Series B vol. *Sistan* p. 2.

<sup>5</sup> See *Kharan Gazetteer* p. 108 and pp. 80-89 where very instructive observations of Mr. Brodenburg are quoted from his *Sketch of the Baluchistan Desert. Memoirs of the Geological Survey of India* xxxi pp. 213 sq.

<sup>6</sup> See below pp. 140-141 168-169 181-182 sqq.

<sup>7</sup> Cf. *Makran Gazetteer* pp. 31-32 sqq. for an interesting account of the way in which the Baluch chiefs were able to maintain quasi-independence for nearly two centuries until 1884 when Izad Khan justly deserved the last and greatest of Baluchistan's firebreathers reluctantly acknowledged British suzerainty.

population of only about 27 souls per square mile<sup>1</sup> sufficiently indicates that here too most of the ground is desert. But the configuration of the country greatly differs. The greatest part of the area is occupied by barren mountain ranges stretching from the north east to the west in parallel arcs and gradually decreasing in height. The southernmost of them conveniently designated as the Makran Coast Range overlooks the desolate shores of the Arabian Sea. There scattered small settlements of fishing folk supported here and there by little patches of precarious cultivation make their living in ways not essentially very different from those of the primitive Ilthyophagor whom Alexander's troops met on their passage through these arid wastes. The valleys formed by the numerous torrent beds which break up this range afford nowhere a chance for even semi-permanent occupation except that in Kulanch to the north of the roadstead of Pasni where small villages carry on agriculture wholly dependent on the capricious rainfall of the coast. As the formation of the range consists mainly of more or less soft clays, intersected by harder calcareous layers excessive erosion has produced here many fantastic hill forms or else an interminable succession of low serrated ridges sticking out from equally bare detritus.

Kej river valley.—To the north this coastal range is flanked by the long stretched valley of the Kej River. Continued westwards by that of the tributary Nihing River and to the north east by the open drainageless basins of Kohwa it forms the economic backbone as it were of Makran. This is sufficiently illustrated by the fact that this valley tract extends for upwards of 200 miles and contains close on one third of the whole population of the country. It also accounts for the current application of the name Kej Makran to the whole territory as attested since mediæval times by Marco Polo and others.<sup>2</sup> Significantly enough more than one half of the people in the tract are to be found in the Nukbat of Turbat.<sup>3</sup> There in an almost continuous string of oases lining the banks of the Kej River with their fields and date groves irrigation is made possible both by Karezes or subterranean canals and by cuts (*kaurjo*) taking off from large pools in the river bed. These return water even after the rain floods from the mountains always heavy but very uncertain have passed by and left the greatest portion of the river's

<sup>1</sup> The Census of 1920-21 showed a population of 1,867, the figure having remained practically stationary since the first census in 1910-11.

<sup>2</sup> Cf. Yule, *Marco Polo*, II, pp. 410-411. The word 'Kej' is derived from the Sanskrit 'Kaj' meaning 'to cut'.

<sup>3</sup> Cf. Yule, *Marco Polo*, II, pp. 410-411. The word 'Kej' is derived from the Sanskrit 'Kaj' meaning 'to cut'.

And you must know that this kingdom of Kasmiran is the last in India as you go towards the west and the north-east.

The word 'Kej' is derived from the Sanskrit 'Kaj' meaning 'to cut'.

Marco Polo

Turk and

course dry. Somewhat similar conditions prevail also in Tump and Mand near the Nihing River.

The Kolwa tract—The open and for the most part drainageless tract of Kolwa forms for some 80 miles a natural continuation of the Kej valley proper from which it is separated by an almost imperceptible watershed. It contains by far the greatest dry crop area of Makran and its export of barley to other parts in years of good rainfall is considerable. Yet how rare such rainfall is and how precarious this cultivation in Kolwa is shown by the very scanty population of the tract being practically all nomadic. All the more interesting is the evidence which the explorations to be described below have revealed as to Kolwa having in prehistoric times been the seat of a large and thoroughly settled population. The contrast between the massively built stone structures traceable at more than one ancient site of Kolwa and the wretched huts of palm matting which house practically the whole of even the settled population in the Kej valley as elsewhere in Makran is striking and illustrates the great change which has come over this whole region.

The Dasht valley—The tract known as Dasht through which the united waters of the Kej and Nihing Rivers find their way to the sea at the bay of Gwatar forms an important south western adjunct of Kōj. Wide alluvial stretches of fertile soil are to be found on both sides of the river below the defile where it breaks through the Gokprosh hill chain and here cultivation necessarily precarious is carried on with the help of the rainfall caught by embankments. But in addition crops are raised on lands adjoining the river bed in years when heavy floods cause them to be inundated. A good deal of trade, largely due to the fishing industry of the coast finds its way down the Dasht to the small ports of Jiwan and Gwadar. The latter together with a surrounding coastal area of some 300 square miles politically forms part of the State of Muskat. It is a characteristic sign of the close intercourse which probably since early times has linked Makran with easternmost Arabia and has left its mark also on its population.

The Central Makran range—To the north of the Kej valley and its continuations there extends the Central Makran Range starting from the south eastern extremity of Makran and stretching with its several branches in an arc from north east to west. Though the belt covered by the range attains westwards a width of over 40 miles and supplies almost all the drainage gathered by the Kej River and its tributaries yet the only area capable of more or less permanent occupation is confined to the small valley of Buleda north of Turbat and to spring irrigated patches in the Zamran hills above the Nihing River. Of the two drainageless depressions of Paron and Balgattar containing salt marshes usually quite dry in their centre only the former has a small fringe of cultivable ground. Elsewhere the scanty pasturage to be found after rainfall along the torrent beds is the only resource attracting nomadic visits.

The Rakhshan valley—The northernmost division of Makran is formed by the large Rakhshan valley. It is enclosed on the south by a long stretched

branch of the Central Makran Range and on the north by the Siahian Range which divides it from the *basin* of Kharan. The Rakhshan River from the head of its drainage on ground included in the Kharan chiefship down to its junction with the Mashkel River at Grawil has a course of over 150 miles. Yet it is only in the short stretch of oases found along its middle course and collectively known as Panjgur that irrigation is available from Karizes and pools in the river bed filled by floodwater and springs. The permanent villages of Panjgur account for over 84 per cent of the whole population of the valley. This including the people of its north eastern extremity administered by Kharan and small semi-nomadic settlements is reckoned at about 15 800 souls. Such cultivation as can be practised elsewhere is dependent on the capricious rainfall and restricted by the stony nature of most of the ground in the valley. The greater elevation some 3 000 feet above sea level at Panjgur makes the summer heat less trying in Rakhshan than it is in low lying Kej and the coastal tract.

Makran as a land of passage.—This rapid sketch of the physical features of Makran and its present economic conditions makes it clear that it *could* never during historical times have been a politically important portion of the Indo-Iranian borderlands. Yet a look at the map shows that in spite of its lack of natural resources Makran is likely to have favoured ethnic relations between southern Persia on the one side and the lower Indus region on the other. This can be safely concluded from the facilities which the direction and open character of the two main valleys of Kej and Rakhshan afford for traffic and gradual migratory movements from either region. Both of them give access by easy routes up the Mashkel and Sarbaz rivers respectively to Rampur and other well cultivated tracts in the Kerman Province of Persia. They themselves can be gained from the side of India by several routes through the Jhalawan hills and the littoral territory of Jas Bela.

History of Makran.—It cannot come within the scope of these notes to review the varying fortunes which Makran's history underwent during successive periods. But a reference to the pages of the *Makran Gazetteer* in which Mr. Hughes Bullen has collected such historical and traditional data as were conveniently accessible at the time<sup>1</sup> will show that the history of Makran as known to us from the scanty sources available duly reflects the effect of the geographical factor just indicated. Dependence either on the power holding the neighbouring Persian provinces of Kirman and Sistān or else on the rulers of Sind and the hills immediately adjoining the Indus valley westwards has always characterized the political status of Makran from the earliest times to which reliable data allow us to go back right down to the present.

<sup>1</sup> See *Makran Gazetteer* — — — — —

**Difficulties of troop movements**—It is of special interest to note how strongly the desert character of most of Makran is brought out by successive historical records. In Arrian's detailed account of the sufferings which attended Alexander's march through Gedrosia and of the heavy losses his army there suffered we have an impressive picture of the forbidding nature of the ground to be met over great portions of the country.<sup>1</sup> The statement quoted by Arrian from Nearchos about the very severe losses which according to local tradition had attended the attempts of Semiramis and Cyrus to cross Gedrosia with an army<sup>2</sup> clearly proves whatever the facts underlying the popular tradition may have been that the country was considered then already just as it is now utterly unsuited for the movement of large bodies of troops.

**Alexander's passage**—The utter inadequacy of local supplies the want of sufficient grazing and in many places even of water must all through historical times have rendered the passage of Makran by a considerable force a very hazardous undertaking. Alexander's success in overcoming such formidable obstacles even though at the cost of heavy sacrifices was in truth but the exception that proves the rule while at the same time a proof of his incomparable genius as a leader. Hence it is easy to understand the dread of barren Makran expressed in the reports of those Arab commanders who under the early Caliphs orders endeavoured to use Makran as a base for the invasion of India.<sup>3</sup>

**Mixture of ethnic elements**—The combined result of geographical and historical factors is easily recognized in the strange mixture of ethnical elements which form the present population of Makran. Reference to the *Gazetteer* will show the many tribal divisions represented in a total population comparatively so small.<sup>4</sup> Here it will suffice to point out that though the great bulk of the Makrans call themselves Baluch and speak the Iranian language called Western Baluchi yet the race to which that ethnic name properly applies appears to have reached Makran on its eastward move from Persia only in mediæval times. It is certain that it largely intermingled then and since both with the earlier stock of the country and with later immigrants. Among them can be distinguished Bihuns of Dravidian speech from the Kalat side, Jadjals from Sindh and Las Bela, Persians from the Helmand valley, Arabs from the Persian Gulf and even a not inconsiderable African element introduced in the shape of slaves. The influence which Indian civilization, whether of Aryan or pre-Aryan type is likely to have asserted in Makran from a very early period, is symbolized as it were by the fact that the Gichki families who dominated Makran in the troublous times before and during Kalat rule and still retain a privileged position are avowedly of Indian Rajput descent.

<sup>1</sup> Cf. Arrian *Anabasis* VI xxii xxvii.

<sup>2</sup> See *ibid.* VI xxvii 2-3.

<sup>3</sup> Cf. *Makran Gazetteer* pp. 43 sq. and the passage quoted by Mr. Hughes Buller on its title page from 'The lament of Sennacherib' as reproduced in Sir Percy Sykes *Ten Thousand Miles in Persia*.

<sup>4</sup> Cf. *Makran Gazetteer* pp. 62-112.



None of the racial elements which successively invaded Makrān and were content to remain there could preserve for long such virile qualities as had helped them to their conquest. In this we may well recognize the effect which the trying climatic conditions of Makrān combined with other physical drawbacks are bound to have had at all times upon its settled inhabitants

### SECTION III.—NOTES ON JHALAWAN AND THE BRĀHŪIS

**Physical features of Jhalawān**—The territory known as Jhalawān, in accordance with a comparatively modern political division of the Kalat State may roughly be described as comprising the mountainous region stretching from north to south which divides the lower Indus valley from Khārān and Makrān.<sup>1</sup> In the north it is bordered by the hill tracts of Sarīwān extending from Kalāt, the capital of the State, towards Nashki, Pishin and Quetta. In the south there adjoins the State of Las Bēla confined mainly to the flat stretch of country between the extreme offshoots of the Jhalawān ranges and the Arabian Sea. The whole of Jhalawān territory comprising an area of some 21,100 square miles is occupied, as the map shows, by a succession of mountain ranges striking approximately from north to south. These attain their greatest heights, up to 9,830 feet, in the north near Kalāt and gradually grow lower towards the south. With the exception of the highest portions which in favourable seasons retain snow for brief periods, or of seasons with unusually good rainfall the slopes of the mountains are barren throughout. In the valleys dividing these ranges there gather rivers which all carry their drainage either into the sea, like the Hingol, Porāh and Hah, or else to the Indus. But it is only at the time of rain floods that these rivers contain water along their whole course and then, too, only for very brief periods.

**Aridity of climate**—As a result of the aridity which characterizes the climatic conditions of Jhalawān, though perhaps not quite in so marked a degree as those of Kharān and Makrān,<sup>2</sup> by far the greatest portion of the population reckoned at the Census of 1920-21 at 79,700 souls, depends in the main on pastoral resources and hence leads a nomadic life. Though springs and Karēzes, owing perhaps to the greater height of the ranges and a

<sup>1</sup> The name *Jhalawan* is explained as derived from the Baluch word *Jahl*, meaning below or to the south: the corresponding designation of *Sarawan* from Baluchi *war* (head: the above) *haz*, applied to the portion of the Kalat State which adjoins to the north. The name *Las Bēla* is derived from the Baluchi *las* (the above) *haz*, applied to the portion of the divisions of it was thus come.

The record  
Colonial Agent

slightly less scanty rainfall are more widely distributed than in Makran yet only less than one fourth of the total cultivated area receives irrigation<sup>3</sup> The rest is entirely dependent on the chance of adequate water being secured from the rare floods which in favourable years descend in the torrents and river beds or being caught by poorly constructed earth embankments from the slopes above the fields

**Scantiness of cultivation**—In consequence of the uncertainties besetting agriculture on all unirrigated land a very considerable portion of the land owning or tenant population is accustomed to move annually for the winter months to the plains of Sind or the Kachhi tract below Sauran in search of employment They thus avoid also the cutting cold of the winds which sweep down from the higher valleys at that season But in the spring when the great heat of the Indus valley begins to make itself felt they all return with their fumes and with such savings as there are invested in foodstuffs But for this seasonal migration a succession of unfavourable years such as is fairly frequent would be marred by famine conditions besides causing whole areas of cultivation to relapse into the appearance of a bare clay desert<sup>4</sup> The precarious character of agriculture in most parts of Jhalawan deserves to be specially noted in view of the evidence which the sites described below have furnished as to the existence there of a considerable settled population in pre historic times

**Historical references to Khozdar**—The geographical features of Jhalawan and the limitation of its economic resources account for the scantiness of historical data concerning the territory The earliest notices to be definitely located there relate to Khozdar which is repeatedly mentioned in connexion with Arab enterprises in the seventh century against Sind<sup>5</sup> That small tract enjoys the advantage of adequate irrigation from its river and of being situated at a point where main routes coming from Makran and Sind from Kandahar and the sea coast meet Hence it was likely to attract attention as a convenient base for operations against the lower Indus whether started from the west or from the north west the latter on the whole the more likely direction Later too in medieval times Khozdar is named among the territories affected by the conquests of successive rulers who extended their power into India from the north west

**Brahui population**—It is a matter for regret though scarcely for surprise that none of these scanty historical records contain any indication as to the ethnic character of the people encountered For very considerable interest attaches to the fact that a vast majority of the present population in Jhalawan is composed of Brahais who speak a Dravidian language and thus are wholly

<sup>3</sup> Cf. *Jhalawan Gazetteer* p. 140

<sup>4</sup> See below pp. 100 sqq. for observations bearing on this condition about Gwastak, Val and W. di

<sup>5</sup> Cf. *Jhalawan Gazetteer* pp. 31 sq. for notices of Khozdar in early Muhammadan records



Rise of Brahui confederacy—Among people so backward in all ways and so absorbed in the struggle with an unkind nature no traditional record of historical value can be expected. The earliest fact remembered by the Brahuīs and commemorated in a popular ballad is their securing freedom from Jat or Jadgal domination<sup>2</sup>. This points to former temporary dependence on rulers from Sind where the Jadgal tribe is still widely spread and once played a prominent part. But neither migration nor conquest on the part of the Brahuīs is implied. That their tribal organization is not based on agnatic kinship as among Pathans and Baluch is an important racial distinction. It appears to have gradually consolidated when the Moghul sovereigns weakened. Finally in the second half of the 17th century it gave rise to a military confederacy of the Brahui tribes more or less on feudal lines which found formal expression in the loosely knit Kalat State under the Ahmadzai family.

The territory of Sarawan shares the character of Jhalawan very closely in all essential points both as regards physical features and the constitution and ways of its present population. In view of this and the fact that my work within Sarawan was confined to a rapid survey of mounds in a small number of localities no separate sketch of the territory need be attempted in this place.

## CHAPTER II REMAINS IN KHĀRĀN

### SECTION 1.—FROM QUETTA TO NAUROZ KALAT

Preparations at Quetta—On November 28th 1927 I started for my tour from Quetta. There during a week's busy stay much kind help on the part of Colonel E. H. S. James CIE CBE Revenue and Judicial Commissioner Baluchistan and of Colonel T. H. Keyes CMG CIE Political Agent Kalat had done everything possible to facilitate my practical preparations. These included the provision on hire of two Dodge motor lorries specially suited for use on the rough tracks in Makran and Jhalawan and the supply of aluminium tanks and canvas Chagals for the transport of water. The latter equipment was obtained on loan from the Quetta Arsenal through the kind offices of Colonel H. McCredy R.A. Chief Ordnance Officer and proved most useful at the numerous sites where water could be obtained only from some distance or was too brackish for use.

Assistants for tour—Quetta was in other ways also a very convenient place for mobilization. There my small party was joined by Nair Abdul Ghafur surveyor and draftsman whose services had been kindly lent to me from his distinguished Corps K.G.O. First (Bengal) Sappers and Miners. His intelligent zeal and very efficient work was to prove once again as on my previous exploratory tours of 1926 and 1927 of very great help to me in respect

<sup>2</sup> See *Jhalawan Gazette* p. 3 1945 sqq.

of both survey and excavation at ancient sites. As the services of Mr A T Brendish could not be spared again by the Survey of India Department assistance for the developing of the photographs taken by me was provided at very short notice by the authorities of the K G O First Sappers and Miners. They very kindly arranged to depute with me Akhtar Munir a young sapper of the Corps after assuring his preliminary training. On my tour I also had the benefit of the practical help of Pandit Ram Chand Bahi of Srinagar Kashmir my temporary Clerk for the last ten years. As before on my tour in Northern Baluchistan he did his best to make himself useful by helping to supervise excavation work and to pack antiquities.

**Halt at Mastung.**—A variety of considerations induced me to start my archaeological surveys from Khairin and the most expedient line of approach to that territory is yet somewhat difficult of access by the metalled road to Kalat and thence as far as Surab by the motor truck leading to Panjgur in Makran. Leaving Quetta on November 23th I reached the oasis of Mastung the best cultivated portion of Sarawan and the headquarters of the Kalat Political Agency. There I should have been obliged in any case to make a short halt in order to dispose of the very last tasks connected with the printing of *Innermost Asia* before leaving regular postal communications behind. While thus busily engaged in exacting desk labours such as revising in proof the voluminous Index prepared by another hand for that work I greeted almost with relief the information communicated from Khairin to the Assistant Political Agent that the camel transport thence dispatched for my use could not be expected to meet me at Surab before December 8th at the earliest. I was thus enabled to remain at Mastung until December 8th and to use the peaceful isolation there afforded for clearing my hands by almost incessant work of obligations to which it would have been impossible to attend later without hampering my movements and labours in the field. During my stay at Mastung I snatched time also for a rapid inspection of several ancient mounds situated towards the north-western extremity of the ground reached by the Karez irrigation of the oasis. My observations on these mounds will more conveniently be recorded below together with those I was able to make there and elsewhere within Sarawan on my return journey<sup>1</sup>.

**Passage through Kalat.**—On December 6th I drove to Kalat a distance of 56 miles mostly across wide stony valleys which under a grey wintry sky looked doubly dreary and barren. A brief halt on the way at the levy post of Mungachar allowed me to collect information about certain ancient mounds which I was subsequently able to examine in that area of cultivation on my return journey in April. At Kalat I was able to gather some indications as to mounds supposed to mark the position of settlements older than the present hamlets. These curiously recalling Eastern Persia are scattered over the head of the valley and together with the half-deserted Bazar and the Khan of Kalat's castle above it constitute the capital of State.

<sup>1</sup> See below pp 157-99

From Kalat to Rodinj—Leaving the examination of these mounds until my return I started on the following day for Surab by the motor track which bifurcates there and gives access south eastwards to Khozdar and Karachi and south westwards to the Rakhshan valley and Panjgur. It first leads past the western face of the low rocky ridge which at its extremity bears the high clay and rubble built ramparts crowned by the Khan's gloomy looking strong hold (Fig 1). Then a few miles beyond it crosses narrow winding gorges towards the open plateau known as Dasht-i-Goran. The watershed passed here at an elevation of about 7000 feet is supposed to make the boundary towards Jhalawan. On the eastern side of the plateau the road passes the small village of Rodinj with fields partly irrigated from two small Karezes and partly dependent on rainfall.

Mound at mouth of Thok valley—Two mounds designated as through out the Kalat State by the term of *damb* were reported here. They could not be surveyed by me until my return on April 10th but may conveniently be mentioned here. One of them rises on gently sloping ground about 1½ miles ESE of the village and to the north of the mouth of the Thok valley. From this the only Karez still actually available for irrigation receives its scanty supply of water. The mound which probably has been built up by debris deposits over an outcrop of rock measures at its base about 220 yards from north to south and 140 yards across. Its height is about 28 feet above the natural slope to the east. Its surface is covered with small stones and plentiful potsherds mostly plain but greatly varying in fabric and colouring. Only few fragments could be found showing any patterns and these too only of the simplest designs. Their body like that of the plain ware is of red grey dark buff or greenish colour. As neither glazed nor any relief decorated pieces could be found I feel inclined to assign occupation of the site to a period which followed the prehistoric use of painted pottery but preceded historical times. Streaks varying in intensity of tint are frequently to be observed on the surface of the plain pieces and are likely to be intentional.

Kuki damb—About three quarters of a mile to the north rises the hillock known as *Kuki damb* near the mouth of another and smaller valley. It forms the last detached offshoot of a low but precipitous hill spur trending from the east and as the outcrop of chalky rock on the slopes shows is of natural origin. Its flat top measuring about 70 yards from north to south and some 18 yards across must as confused heaps of rough stones show, have once been occupied by rough dwellings. From there the plentiful pottery debris has been washed down which covers the slopes of the hillock and the ground close to its foot. These potsherds are of just the same type as those found at the previously described mound and thus indicate approximately contemporary occupation. At both sites small fragments of chert and similar hard stone could be picked up in plenty, but none were clearly recognizable as artifacts.

Failure of water from Karezes—No water is now to be found in the vicinity of either site. But at the western foot of the Kuki damb and some

120 feet below its top there had been sunk about eight years before my visit and at great expense wells for a Karez. It yielded water for four years allowing a large orchard to be planted north of Rodinj village but has since completely dried up. The same fate has recently overtaken a small Karez of old date which used to carry water to the groves of Ahibad a little hamlet at the mouth of the Thok valley and about a mile and a half south of Kula damb. Complaints about the subterraneous water supply having failed in the same way during recent times were to be heard also elsewhere in this tract.

Mound at Benn chah—About seven and a half miles to the south west of Rodinj the road passes the lonely halfway halting place between Kalat and Surab called Benn chah. About a furlong to the south of it there rises a mound measuring about 200 by 150 yards at its foot to a maximum height of about 30 feet above the stony scrub covered plain of the valley. Plentiful potsherds of plain ware varying in colour from pink to buff grey and light greenish tints are found on the slopes and less frequently also fragments of similar fabric decorated with coarsely executed narrow bands or other simple patterns mostly in dark brown. Fragments of iron ore were picked up at the foot of the mound and on its slopes also small pieces of flint or chert apparently unworked. Comparison of the pieces bearing painted decoration with the decorated ware from chalcolithic sites clearly indicates later occupation of the site probably contemporary with that of the mounds near Rodinj. Precarious cultivation wholly dependent on rainfall is carried on in favourable years by half a dozen households in the neighbouring area known as Mall. A Karez passing the roadside shelter was declared to have been dry for a long time.

Arrival at Surab—A drive of some 23 miles along the bare plain of the valley brought us by nightfall to the post of Surab in the centre of the cluster of small villages collectively known by that name. There I found the camels just arrived from Kharan and was thus able to arrange without delay for our onward move next morning. My wish to visit at least a portion of this territory in the north east was prompted specially by the remembrance of certain old remains which had been noted there by Lieutenant (later Sir Henry) Pottinger in 1809 on his passage towards Sistan. On a rapid tour made from Nushki to Kalat in 1904 I had failed to locate them. Regard for the distances to be covered through the mountains where no motor tracks are available necessitated the earliest possible start. So my camp was sent ahead on the morning of December 8th while I inspected the two old mounds of the existence of which in the Surab area information had reached me.

Mound near Neghar—The half dozen of small villages which cluster around the fortified post of Surab in the valley of the main feeder of the Gidar Dhor river owe their comparatively prosperous look to the presence of several springs and Karezes. These derive their supply of water from the rugged range which stretches along the eastern side of the valley and at some points rises to heights of over 9000 feet. Owing to the bitter cold of the winds Surab is dreaded in the winter. Hence almost all the people of the tract had already started on

their hibernal migration down to Sind. Thus we found the village of Neghar about three miles to the south east of the post quite deserted. Close behind it at the foot of a steep rocky outcrop of the range there extends a low mound of artificial origin rising about 20 feet above the level of the immediately adjoining fields. Its slopes are thickly covered with rubble from roughly built decayed dwellings. Remains of their walls could be traced on the flat top of the mound measuring about 70 by 80 yards. That the site was occupied, at least periodically, down to historical times can be safely concluded from small pieces of glazed ware decorated with designs in various colours and manifestly mediæval. The other ornamented potsherds picked up comprise fragments of superior red ware bearing on the inside or outside well-executed patterns in black (N D 1, Pl I). These on the analogy of similar pottery from other Baluchistan sites may I believe be attributed to late prehistoric times. The same applies also to a few fragments of similar ware showing simple incised or relief decoration (N D 2, Pl I).

Mound of Surkh-damb.—Riding from here across ground partially cultivated I next visited the much larger mound known as *Surkh damb* situated close to the village of Surkh and about half a mile to the south west of the Surab post. It extends for about 250 yards from north east to south west with a maximum width of about 140 yards. It rises up to 15 feet above the level of the irrigated fields close by. Among the abundant plain pottery of good reddish ware there were picked up here also pieces ornamented with simple black bands or else with narrow ridged ribbing a method of decoration of which examples can be found also among the ceramic remains of sites of the N W Frontier dating from Buddhist times. No glazed pieces could be found here. Here I may conveniently note that as far as my enquiries extended no pottery of any sort is now locally produced in Jhalawan or Kharan. Imports from Sind are also rare and confined to households of some standing. The vast majority of the population is accustomed to use only skins or wooden vessels of the coarsest description.

Journey to Nauroz kalāt.—The four fairly long marches which carried us across the mountains to Nauroz kalat offered no opportunities for antiquarian observations. But they allowed me to gain some acquaintance with the physical conditions prevailing in the Garr range which divides Kharan from Jhalawan. These conditions must at all times have affected the life of such scanty nomadic population as this region could ever support. They may be considered more or less typical of the higher of the ranges which occupy the greatest portion of Jhalawan. For this reason and also because the major portion of the journey lay along a line not described in the official handbook dealing with Routes in Southern Baluchistan a succinct account of these marches may find a record here.

March to N W of Surāb.—Our march from Surab on December 9th lay all the way to the north west and led first across an extensive stretch of *Lhusli dāba* cultivation, wholly dependent on rainfall. On ascending the stony glacis towards the broken hills which divide the Surab valley from that marked on



the map as Chulbaghū I noticed much decayed remains of two or three dams which looked as if meant to direct flood water from the slopes towards that cultivated ground. In the wide valley trough crossed further on vegetation was to be found only near a succession of stony torrent beds holding water in a few pools. Half a dozen deserted mud and stone hovels scattered over the plain indicated occasional cultivation of small patches by wandering flock owners in favourable years. Beyond this valley there stretches a chain of much eroded rocky ridges rising to over 7,000 feet. In a narrow ravine known to our Kharan guides as *Zarago* drinkable water was found by digging in a shallow dry channel and there we halted for the night.

Across the *Shah kumb* valley.—The next day's march took us first for a couple of miles across the easy watershed of this hill chain, called *Koh-i-Pudak* where wild pistachio trees grow in plenty. It forms a divide of some importance. On descending we first passed a spring in a ravine that feeds the *Chutok* river a main tributary of the *Korakan* and then less than a mile farther we reached the southern extremity of the open *Shah kumb* valley the drainage of which descends into the *Bado* river. Both *Korakan* and *Bado* flow into the *Kharan* basin. But their flood waters do not meet until close to the ground where they lose themselves in the desert sands. Moving to the north west for about four miles we crossed the head of the *Shah kumb* valley which affords fair grazing for camels and flocks and is hence regularly visited by nomadic *Brahui* encampments. Here I first noticed in places those curious small enclosures roughly marked with rows of stones which are laid out by *Brahui* nomads in commemoration of their dead and are known as *chēdāl*. They are supposed to symbolize dwelling places for the dead and are used for funeral gatherings. As they are always to be found away from the actual places of burial they may well indicate a survival from pre-Muhammadan rites.

Descent into *Jal* valley.—On leaving the *Shah kumb* valley the track led through a maze of bare blackish hillocks and narrow ravines most of these draining towards the *Chutok*. The valley in which the latter has cut its way through the mountains would afford the most direct route to *Kharan*. But it was declared to be so narrow as to be wholly unpassable for camels. Then the track emerged in a smaller valley stretching like that of *Shah kumb* from south to north and known as *Burbur*. Here too scrub and hardy grasses offer good camel grazing and small pools of water remained in a shallow bed draining into *Shah kumb* and the *Bado*. We had followed the *Burbur* valley for about three miles when the usual caravan track from *Kalat* to *Kharan* was struck. It led first north westwards into narrow rock lined ravines where once more the *Chutok* drainage was struck and then up to the *Jal* Pass some 6,000 feet above sea level. From there it descended into the narrow gorge of the *Jal* river winding between rock walls so high and so steep as to make a passage quite impossible in the event of rain. A small sandy terrace with some trees afforded a safe camping place at a point known as *Kundi*.

March in Jal gorge—A little distance below this the river gorge turns into an extremely narrow tortuous rift. Masses of fallen rock were said to render this impassable for animals and even men. So the track here strikes off into a small side Nullah to the north and ascends very steeply over rock and loose stones to the narrow sharp crested dip of a side spur. The pass is called Jalkand and is difficult even for lightly laden animals. The respect entertained for it on this account by wayfarers is duly marked by the offerings of poles, Ibex horns and the like which deck the supposed resting place of a 'Pir' buried on the rocky crest. A distant view opened westwards across a succession of deeply eroded spurs and towards the fantastically assumed Raskoh range which rose high above them in the distance. It strikingly recalled to my mind an even more arid mountain region, the outer spurs of the Kun lun above Khotan. After four miles troublesome descent across numerous smaller spurs and ravines the track regained the bed of the Jal River. Its narrow tortuous course lay farther on between wildly cut rock walls (Fig 3) but was followed without difficulty down to the point known as Gwatunk. There the little stream intermittently flowing in the stony bed finally disappears and there camp was pitched.

Arrival in Nauroz kalat—On the morning of December 11th a march of two miles and a half sufficed to bring us down to where the stony river bed now quite dry debouches on a vast bare peneplain. At its mouth some fields amidst clumps of large tamarisks are cultivated by a couple of Baluch families in years when an adequate flood descends the Jal bed and inundates them. Here we left the track leading down to Kharan fort and village and struck due west across the bare detritus covered peneplain. The line we were following crossed more than one ravine from the hills to the north east but only in one of them, not far from the Jal river mouth, was some water to be found. The spring supplying it was said to dry up after the winter. Before we reached Nauroz-kalat the only permanently inhabited place in the whole north eastern portion of Kharan territory we struck the wide tamarisk covered flood bed of the Ghazkaur and then passed through a desolate belt of low and utterly barren hills. So it was a welcome change when from the last rocky ridge we dropped down to the scanty palm groves and fields of Nauroz-kalat by the left bank of the Bado river. Since leaving Surab we had covered close on eighty miles without meeting any humans apart from a solitary shepherd in the Shahkumb valley.

---

## SECTION II—SITES IN NORTH EASTERN KHĀRAN

Search for remains noticed by Pottinger—I had chosen Nauroz kalat as my first objective in Kharan for two reasons. From there it would be possible for me to re-visit the site of Toji further up the Bado river. I had first rapidly examined it on my short tour of December 1904 but had not been able on that occasion to arrive at any certain conclusion as to the antiquity of

its surface remains. At Nauroz kalat too I might hope to obtain information as to the position of certain ruined structures which Pottinger had seen in 1810 on his third march from Nushki down to Kharan and which had aroused his special interest. The topographical indications recorded by him from what he could observe on his plucky journey performed under conditions of distinct risk and difficulty were not sufficient to permit of the locality being fixed without search on the ground. In 1904 want of time had made it impossible for me to extend this search to Nauroz kalat. But in my report on that short tour I had expressed the surmise that the ruins might have to be looked for farther down the Bado river than Pottinger's road estimate seemed to indicate.


Information secured at Nauroz kalat.—Nauroz kalat is a very small oasis settled only since the time of Azad Khan chief of Kharan in the second half of the last century who constructed a Karez and built a fort there as the residence of his son and successor Nauroz Khan. With the ready help of Nab Sultan Khan in charge of this subdivision of Kharan who had accompanied us from Surab the local information I needed was secured here without difficulty overnight. It clearly pointed to remains corresponding to those mentioned by Pottinger to be found on the route which leads down the river to the chief's seat at Kharan. As the latter was to be visited by me in any case I decided first to proceed on December 12th to the Toji site taking with me whatever able bodied men could be collected for digging eight in all.

The Toji site.—The site was reached after proceeding for about four miles up the bare gravel plateau through which the Bado river winds in a fairly wide bed filled with scrub and tamarisks. It contained at the time a shallow but brisk flow of water some 8 yards wide near the site but this flow is liable to dry up in the summer months. Where the course of the Bado is joined from the north east by a wide dry flood bed known as the *Toji laur* there puts out from the gravel *Dasht* to the east of the Bado a small detached terrace called *Toji damb*. It rises to about 50 feet above the nearest portion of the river bed (see A in the sketch plan Pl. 1) and is rendered conspicuous by the dark debris of stones and pottery which covers its top and slopes. A narrow dip of the ground separates it from the level *Dasht* and a small shallow *Nallai* intervenes between it and a similar tongue of the plateau to the south east also covered with debris and marked B in the sketch plan.

Advantages of site for defence.—Round the northern foot of the terrace A there bends a well marked small channel obviously scoured by the floods which occasionally descend in the large bed and farther up have produced the steeply cut banks of the *Dasht*. It holds a little streamlet of drinkable water fed by a spring which issues just below the above mentioned dip. Fig. 4 shows it in the foreground. The top of the terrace which measures about

<sup>1</sup> See Pottinger *Travels in Beloochistan* 1810 p. 123.


<sup>2</sup> Cf. Stein *Report on Archaeological Survey of the P. W. P. and Baluchistan* 1906 pp. 50 sqq.




R UR 2 NCTO UR R DO



TO G D O O



[ O KTO BOUT VT



U O U U U



120 yards from east to west and over 70 yards across where the widest falls off with very steep slopes towards this natural fosse as seen in the photograph. The relative height of the top above the streamlet is nowhere less than 30 feet. The great advantage for defence offered by these steep slopes as well as by the easy access to water accounts for the ancient occupation of the terrace as attested by remains of walls and the painted potsherds to be described presently.

**Remains of walls**—The steepness of the slopes on the northern face of the terrace made it easy to distinguish the natural strata of gravel and clayey alluvium reaching to a height of about 15 feet from the debris deposits higher up which are due to the decay of rubble built dwellings. At one point on the north eastern slope of the terrace marked in Fig 4 by the figure of a man standing a little clearing sufficed to lay bare a wall solidly built with fairly regular courses of large water worn stones set in mud plaster. It could be traced for a distance of some 20 feet though broken in places by erosion. From its position it might be supposed to have belonged to the foundation of a structure or of a circumvallation erected after an enlargement of the occupied area on the top of the terrace had become necessary.

**Traces of circumvallation**—Further to the west a line of large stones exposed in a row along the edge of the north face of the terrace top indicated the position of another massive wall. On excavation this wall was cleared for a length of 18 feet to a depth of 4 feet and proved fully 9 feet thick. Erosion cuts had broken it on the east and west but surface indications allowed its position to be traced for about double that length. Judging from this and its thickness this wall may well be supposed to have belonged to a circumvallation. On a lower level outside it there were struck the foundations of another massive wall running at a distance of about 2 feet but not quite parallel to it. The masonry of these walls was of the same type as noted above. The abundance of rough stones large and small which lie thickly over the top of the terrace could have been brought there only by the hand of man and clearly belongs to decayed dwellings. In some places modern digging done evidently for treasure had exposed the top of walls belonging to small structures as already noted in 1904.

**Painted pottery**—Amidst this debris on the top and also over the slopes there lie plentiful potsherds generally of superior red fabric. The same is the case on the terrace to the south west marked B where pottery debris alone offers a surface indication of former occupation. Most of this ware is plain but a quantity of fragments with painted designs could also be collected with ease. The great majority of these show geometrical patterns executed in black mostly over a red or else dark buff ground as seen in the specimens T K 1 G (Pl I). The patterns such as hachured leaf shapes solid triangles meeting at points hooks arranged in rows above plain bands have all their counterparts in the painted pottery from some of the prehistoric mounds of Zhob and Loralai. Bits of painted pieces showing coarse zigzags dots or scrolls in purple or brown over pinkish ground such as are characteristic of

the later of those mounds only very few could be found (see T K 79, Pl I). Apart from the scalloped rim on one of the latter pieces no relief decoration is shown by any of the pieces collected. But on the other hand a peculiar kind of mat marking familiar to me from some of the early pre historic sites of Northern Baluchistan appears on a number of fragments of rather coarse fabric. Pieces of unworked flints and other hard stones were picked up in numbers. But only two pieces one a very roughly worked scraper the other a coarse 'point' or borer show signs of human use. The former was found low down between the two adjoining walls above mentioned.

**Ruined embankments**—At the foot of the little Nullah which separates the two terraces A and B there runs a massive embankment or *band* built with large blocks of stone and over 8 feet thick. Its direction distinctly supports the assumption that it was connected with a similar *band* of equally massive construction and traceable over some 100 yards which extends from the opposite bank of the Toji kaur to the foot of the gravel plateau overlooking it as shown in the sketch plan (Pl I). The object of the embankment was manifestly to hold up and store flood water descending in the wide bed of the Toji kaur for irrigation of the riverine flat which stretches away to the west of it for over one third of a mile. Some 200 yards further up there survives for a distance of about 120 yards another old embankment faced similarly with a wall of large boulders. It is about 8 feet thick and still stands to a height of 4 to 5 feet above the ground in front of it. Its flank rests at the foot of the plateau to the north east. Alluvium brought down by rain floods in the ravine which here descends from the plateau to the Bado has filled up the ground above the *band* to the level of its extant height.

A hundred yards or so to the north there is found a second *band* of the same type and construction but less well preserved. It once no doubt also extended eastwards to the foot of the plateau, but it has been carried away on that side by flood water. It is now traceable only for about 50 yards to where it forms a corner and bends upwards. Here, too, alluvial deposit has raised the ground behind to a level flush with the present height of the stone dam. Traces of old furrows showed that this ground had at some time not very distant been used for cultivation. But this is no longer carried on, and the hard soil of the dammed up ground serves only for underground pits in which to store grain whenever crops can be raised by occasional tillage of the fields close to the present channel of the Bado.

**Construction of 'Gabar bands'**—These embankments of the Toji site like all similar stone built irrigation works to be found in great numbers over Kharân and Jhalawan are locally known as *Gabar bands*. This designation which ascribes them to the 'Gabars' or Zoroastrians is merely an indication of the great antiquity with which Brahm and Baluch popular belief invests these remains. That the construction of such solid stone dams is entirely beyond the capacity of the present inhabitants of this region is certain. Nor

does it seem possible to believe that their laborious construction could ever have been undertaken unless to meet the agricultural needs of a population far denser and far more settled than the present one. I shall have occasion further on to discuss the interesting antiquarian questions raised by these striking vestiges of the past in connexion with the imposing Gabar-bands examined by me in Kolwa and Jhalawan. Here it may suffice to point out that the evidence there discussed seems distinctly to favour the assumption of a close relation in origin as well as in approximate date between the embankments of Toji just described and the remains of the prehistoric settlement in the close vicinity of which they are found.

Intermittent cultivation in bed of Bado.—No signs of later permanent occupation are to be found anywhere in this neighbourhood. But the ground to the west of the Gabar bands is now tilled in years of good rainfall by a few semi-nomadic Baluch households. At other times too the easy access to water and the presence of good grazing in the beds of the Bado and Toji kaur are likely to have attracted such visitors. It is hence not difficult to account for the small groups of burial places found at several points of the plateau which divides the Toji kaur from the Bado. They are obviously Muhammadan as the low heaps of stones marking graves are almost invariably correctly orientated from north to south in the orthodox fashion. The digging done at one of the stone heaps where the direction differed revealed no deposit of any kind but showed undisturbed soil of hard clay and gravel below three feet of loose earth.

Pottinger's reference to site.—My renewed and closer inspection of this area left me in no doubt that the remains of the Toji site correspond to the several large mounds of stone and earth scattered over the desert which Pottinger describes as having been seen by him on his journey from Nushki into Kharan along the course of the Bado for the route regularly followed by travellers from Nushki to the chief cultivated area in the north eastern portion of Kharan actually passes by Toji. But there still remained the search for the very extraordinary tombs of a quadrangular shape each surrounded by a low wall of curious open freestone work which he mentions at a distance of about 400 yards from the western bank of the river<sup>2</sup>. They had puzzled Pottinger greatly as he could trace nothing whatever Muhammadan or Hindu in their style and had judicious doubts also about their having served as Zoroastrian places of worship.

Remains near Azad gaz Ziarat.—The location of these remains proved easy. Local information at Nauroz-kalat I new of ruins on the right bank of the Bado only at one place and that on the way down to Kharan the chief seat. Starting for this on the morning of December 13th we passed after a mile the fort of Nauroz-kalat a small but fairly substantial structure built by Azad Khan and less than half a mile farther the point where cultivation near the left bank ends. Then the track crossed the river and led past a stretch

<sup>2</sup> See *Travels in Beloochistan* p. 126



of abandoned cultivation to a narrow stony plateau which separates the course of the Bado from that of a torrent bed known as Garuk laur. On approaching the junction of the two near the Ziarat of Bibi Azad gaz we arrived after a total march of six miles at the ruins which Pottinger had seen.

Enclosures of Muhammadan graves.—They proved to comprise three low walled enclosures each containing a number of what are undoubtedly Muhammadan graves. All are built on the same plan with walls of fairly regular courses of flat sandstone slabs evidently brought from some easily worked stratum in the near hills and roughly dressed at the ends. All have a small prayer niche facing approximately west north west and a very low entrance opposite, as seen in Fig 2. The first of these burial enclosures met on coming from Nauroz kalat stands close by the roadside and is the one which has suffered most decay. Within a small square of walls standing to about three feet height a heap of earth mixed with burnt bricks marks a completely collapsed small Gumbaz or Muhammadan domed tomb. Within old men's memory the little square structure was said to have still stood in a condition recognizable as the resting place of a Pir. The well made hard bricks measured 11 by 7 inches with a thickness of 2 inches. Bricks of the same kind were found on some of the low little mounds which mark the graves found in the other enclosures.

Period of enclosures.—Two of these within a few yards of each other, are situated to the north west of the track and about 160 yards from the first. They contain each half a-dozen of grave mounds and measure about 33 feet square outside. The fourth a little to the south of them (Fig 2) measures 36 feet square outside and its plan as shown in Pl 1 is typical of the rest. The entrance passage only 2 feet wide and 2½ feet high shows small openings on its projecting sides and is roofed with flat slabs. Here as in the other enclosures the only decoration of the walls all built without clay or mortar consists of small slatey stones inserted at irregular intervals zigzag fashion in place of a stone slab as seen in Fig 2 by the side of the entrance. No local tradition survives as to the origin of the burial enclosures but their Muhammadan character is well recognized. I was unable to trace any definite indication as to their period. But considering their advanced state of decay and comparatively superior construction I am inclined to believe that they may belong to mediæval times when Kharān appears to have been ruled by Mahiks connected with Sistan<sup>4</sup> and may be supposed to have enjoyed a somewhat higher state of civilization than is found there now.

Ziarat of holy lady.—There can be no doubt that the location of these burial places is due to the sanctity enjoyed by the Ziarat supposed to mark the resting place of Bibi Azad gaz a holy lady. It occupies a small hillock at the meeting point of the Bado and Garuk laur about a quarter of a mile farther on. I could learn nothing about this holy person but duly noted that

<sup>4</sup> See *Kharan Gazetteer* p 30

just below her shrine there issues a fine spring fed by the subterranean drainage of the Garul valley. Local worship at such a spot is likely to be older than the introduction of Islam. The water from the spring accounts for the cultivation carried on here by three families in this otherwise dreary waste.

March to Kharan kalat.—Four miles further down the track crosses the Bado to the left bank and on the bare gravel plateau known as *Hadia*<sup>5</sup> passes several badly decayed burial enclosures like those of Azad gaz. Others of the same type but far more roughly constructed with mere rubble were found close by and looked like later imitations. Some five miles beyond at a point called Bumband the termination of the river's surface flow was reached. Here is the head of the chief canals which carry water from rain floods over the arid alluvial plain on either side of the main bed and render intermittent cultivation there possible. Following first the westernmost of these canals and then crossing an utterly barren stony plain we reached *Kharan kalat*, the 'capital' of the territory from which it takes its name.

The capital of Kharan.—This is not the place to describe the impressions produced by the little town of mud hovels and mat-huts which clusters around the chief's residence and the stronghold built by his renowned ancestor Azad Khan. Most of them were deserted at the time and towards the spring the chief and his people too are apt to move off to camps on higher ground, generally on the slopes of the Raskoh range. This rises northward with fantastically serrated peaks to a height close on 10 000 feet and provides a striking background to the far from attractive scenery of the Kharan capital. I was hospitably received by Nawab Habibullah Khan the present head of the Naushirvan family which has ruled Kharan for upwards of two centuries. I found a good illustration of the cultural influence here exercised by Iran in the domed structure serving as Darbar hall and guest house combined which was allotted to me as quarters. It had been built in recent years by Persian masons and in its plan closely reproduced the architectural features well remembered by me from manorial structures old and new in Sistan. The odd European furniture with which it was partly filled had of course been obtained through an Indian medium. Together with the building it seemed to symbolize the meeting of two civilizations both foreign to the soil and one greatly hybridized.

Mound of Pir Hassan Shah.—During my day's stay at Kharan kalat I visited on December 14th the large mound known from the Zaurat it bears on its top as the damb of *Pir Hassan Shah*. It is situated about two miles to the SSE. Rising above the flat plain cultivated in patches when adequate flood water can be obtained from the Bado it forms a conspicuous object though of no great height. It was the only ancient site in this part of the valley of which I could obtain information and is mentioned in the Gazetteer.<sup>6</sup>

<sup>5</sup> Fls. ap No 34 H seems to duplicate the local name under the form of *Ad gaz* while on the way to the *Ad gaz* altogether.

<sup>6</sup> Cf *Kharan Gazetteer* p 148.

The mound occupies ground between two branches of an ordinarily dry flood bed known as Kallun the western one of these in good years allows small stretches of ground at the foot of the mound to be cultivated. The mound measures about 600 yards from north to south and about half that across where widest. The highest portion near the middle rises to about 25 feet above the level of the fields and is covered with plentiful fragments of burnt bricks. These appeared to belong to a ruined Muhammadan structure probably a domed tomb or *gumbaz* their size is  $11 \times 6 \times 1\frac{1}{2}$  inches. On a slightly lower portion of the mound to the north is found a rough stone enclosure containing the supposed grave of the saint.

**Pottery remains of mound**—No old structural remains could be traced on the surface. But potsherds cover it in abundance and are exposed also where erosion has cut into the mound. Of painted fragments but few could be found they show simple geometrical designs in black over a red or buff ground (see PH 13 11 Pl I) resembling those on painted ware from chalcolithic sites of North Baluchistan. All the more plentiful were pieces decorated in relief with flat ribbing (see PH 4-6 Pl I). This type of decoration was found by me in Sistan to be closely associated with sites occupied from the first centuries of our era down to early Muhammadan times it is also well known in Egypt from the Roman and Byzantine periods.<sup>7</sup> Of the piece PH 4 it is interesting to note that besides the ribbing it shows also decoration by burnished bands. To historical times may probably be ascribed also the few pieces which like PH 7 10 show simple incised ornament and so also the fragment with a handle PH 9. On the other hand the numerous fragments of which the outer surface is mat marked (for a specimen see PH 8, Pl I) are likely to be far more ancient they are all hand made while the rest of the pottery is wheel made. It deserves to be noted that we could not find a single piece of glazed ware. Judging from these ceramic indications it appears probable that the mound originally formed by prehistoric deposits continued to be occupied during historical times but ceased to be so in the Muhammadan period when the use of glazed ware was common, as shown by the frequency of it at sites of that period in Makran.

**Departure from Kharan kalat**—The presence of this large mound in the close vicinity of Kharan kalat proves that the ground near the head of the deltaic area formed by the Bado Korakan and Garuk flood beds has served since early times for the chief agricultural settlement of Kharan just as it does now. I could learn of no other darb of this kind in the north eastern portion of the territory nor does the Gazetteer indicate the existence of any. The numerous vaulted tombs or *Gumbaz* of Muhammadan times which the Gazetteer mentions in widely distant parts of Kharan<sup>8</sup> did not offer sufficient archaeological interest to justify the expenditure of time which visits to them would have implied. So I felt free on December 15th to leave

<sup>7</sup> Cf. Stein *Innermost Asia* p. 100 n. 910 928 1 Pl. CXV  
<sup>8</sup> See *Kharan Gazetteer* pp. 45 sq.

the Kharan capital for the journey which as planned at the outset was to carry me south east through the mountains to the Besema tract of the territory. There I could regain the motor track which leads to the head of the Rakhshan valley and thus down to Panjgur in the northernmost part of Makran.

Domed tomb with relievo slabs—The caravan route to be followed for this journey led on its first long march up to the mouth of the Garuk valley. On the way near the huts of the Shiroza hamlet, only 2½ miles from Khāran fort I passed one of those domed tombs. It is known as *Ashilo gumbaz*. Its fair preservation and the shape of its high dome suggested a late date. The upper frieze on the outside of the square burial chamber is ornamented with burnt clay slabs showing in low relief very coarsely modelled figures of camels, horses and other animals, such as are described in the Gazetteer as typical of these sepulchral structures in Makran. Our start had been much delayed through the belated arrival of fresh camel transport and with the prospect of a long march before us no time was left for closer examination of the structure.

Remains at mouth of Garuk valley—For about ten miles the track led across scrub covered waste broken by patches of neglected cultivation or furrowed by inundation channels which at times provide them with water. Then for another fifteen miles the march lay up a gently sloping glacis of bare gravel to where the Garuk river bed debouches from the deeply eroded barren hill range. Here water left behind by the last rain flood was found in a muddy pool of the bed. Of the mound which the Gazetteer mentions at this point as having yielded 'some pottery believed to be of great antiquity to cultivators when excavating for purposes of cultivation' I could obtain no information, nor does the ground offer here a chance for tillage. But when we had ascended next morning for about 2½ miles along the deep cut river bed I was shown by Murad Khan the Naib of the Besema and Rakhshan tract who accompanied our party and proved thoroughly familiar with the ground much decayed remains of stone walls on the top of an isolated narrow ridge rising to over 150 feet above the bed. They extend for about 170 yards from north east to south west the once occupied space on the top having a maximum width of about 60 yards. The rough stone walls evidently belonged to a small fort or place of refuge as indicated also by the stone heaps which marked the position of towers. Potsherds lay in plenty over the rocky ridge but were mostly coarse undecorated ware. The few painted pieces picked up showed only poorly executed dark stripes or hachures over a buff or pinkish fabric. No ribbed or glazed ware distinctive of historical times could be found, but the look of the pottery militated against the assumption of any great antiquity for this small site. The natural strength of the position and the presence of a well in the river bed immediately below adequately account for its occupation which was probably intermittent.

---

\* See *Kharan Gazetteer*, p. 143.

## SECTION II—THE MOUNDS OF BESEMA AND ZAYAK

Two marches on December 16th and 17th carried us southward along the main drainage of the Garuk river to the spring of Drug and the vicinity of the open valley trough known as Besema. The line followed by this well known track led in the dry river bed or else up and down small side valleys when narrow defiles of the former had to be avoided. Everywhere the slopes of the hills passed were uniformly barren. Pools and wells could be found along the main bed at intervals but there were nowhere signs of prolonged occupation whether old or recent. Only twice we had met nomadic Brahū house holds moving up to such grazing as can be found in the higher side valleys eastward.

Physical features of Besema.—Starting from the spring of Drug on December 18th we passed shallow floodbeds descending from the rugged Jur hills in the east and then arrived after some miles march at the northern end of the tract of Besema. It stretches for about thirteen miles from north to south as a wide open valley. The almost level portion of the trough keeps an average width of about four miles and lies at an elevation of a little over 4400 feet near its southern end. The naturally fertile alluvial soil of the trough would permit here of cultivation over an extensive area if irrigation were possible or adequate rainfall assured. But the numerous floodbeds which descend from the hills on both sides of the valley carry water but rarely, and as they have cut deeply into the soft soil most of the water they bring down would be lost to the cultivator.

Nomadic population.—Numerous small patches of cultivation were passed as we moved up the eastern side of the valley but no signs of even semi permanent occupation could be sighted. The Brahū population claiming land in Besema and shown by the census of 1921 as 732 souls is entirely nomadic living by their flocks and tilling their fields only in years of good rainfall. A striking contrast is thus presented to the number of old mounds which rise over the flat ground of the valley attesting prolonged occupation by a once considerable settled population. An attempt was made by Nauroz Khan chief of Kharan towards the close of the last century to bring at least a small portion of this potentially fertile area under cultivation. But the Kuez dug for this purpose towards the mound known as Kurragi-damb failed as no adequate supply of water was secured.

Prehistoric pottery on mounds.—The first mound known Mammar-damb was reached close to the northernmost patch of Khushkaba (dry water) cultivation. It measures about 100 by 70 yards and rises to a height of about 10 feet only. On the slopes covered with rubble from decayed dwellings pottery remains were scanty. But the few painted pieces looked ancient (see MD I Pl I) and a small terracotta fragment evidently from the figure of a lumped hulk in view of finds made elsewhere distinctly suggests prehistoric occupation. Going about 2½ miles south south east we came to the Au-raqi-damb adjoined by cultivation. It rises to some 30 feet and has a diameter of over 120 yards. It is thickly covered with stones of which

the plentiful large ones must have been brought for building purposes from some distance the foot of the nearest hills being fully two miles away. Most of the potsherds found here are of a coarse undecorated ware. But some of the painted fragments like KD 1 2 (Pl I) which show well executed geometrical patterns in black over a red slip manifestly indicate prehistoric occupation.

After proceeding about 3 miles SSE and skirting the abandoned Kariz previously mentioned I was shown eastwards a flat patch of ground covered with pottery debris and recalling a Turkestan Tati. It was known to my guides as *Kashan damb*. Here but a few painted fragments could be found they show a red slip but no distinctive designs apart from lines in black. Two small fragments from this spot appear to be decorated with flat ribbing which suggests occupation started or continued after prehistoric times. The small mound called *Sayin damb* about 20 feet high and situated about half a mile to the south was heavily covered with rubble but showed little of potsherds all coarse undecorated ware of uncertain type.

*Taghaz damb*—Far more interesting and varied proved the ceramic remains of the largest of the Besema mounds which was reached at a distance of about 11 miles to the SSW of the last named. It is known as *Taghaz damb* and adjoined by Khushkaba fields. It measures about 140 yards from NE to SW and not much less across its height is about 10 feet. Among the plentiful rubble from decayed dwellings which covers the slopes of the mound fragments of painted pottery of a superior kind could be found in abundance. The great majority of them show carefully executed designs in black over a dark red slip but there are found also pieces which are decorated with brown or buff designs over a light yellowish or fawn coloured ground (TZ 4 8 10 Pl I). The specimens reproduced in Pl I will help to illustrate the great variety of patterns all geometrical and almost always executed with considerable neatness and freedom. Among them quite a number like TZ 1, 2 15 16 19 with their bands of hachured triangles or leaf shapes closely recall similar designs from the early prehistoric sites of Zhob and Loralai. There too parallels can be found to scrolls like TZ 3 9. But in addition to these we find here frequent patterns with elegant volutes like TZ 7 13 14 fern like bands (TZ 6) or feathered discs (TZ 17 18) which are not represented there.

*Character of painted pottery*—It is just these peculiar and finer patterns which establish a distinct link between this painted ware of Taghaz damb and that of prehistoric sites traced by me in the Mashlari valley<sup>1</sup> to the south. Considering that the distance in a direct line between the nearest of these Sumer and Besema is not much more than about thirty miles this close similarity in peculiarities of ornamental design is easily accounted for. If I am led to suggest for the painted pottery of Taghaz damb and that of its type a somewhat later origin than that of sites like Perino ghundar or Surjangan it is

because we meet among it also pieces showing the use in the designs of other colours besides black. Thus in T Z 12 we find in addition to black also a kind of terracotta red used over a buff ground with bands of dark purple while in T Z 21 brown lines are painted over buff and a curious hook like black ornament over a red slip. Similarly on the fragment of a bowl T Z 20 both purple and black designs appear over the light terracotta ground. It deserves to be noted that much of this Taghazai pottery is of a thin and very fine fabric and that in at least one piece T Z 28 neatly burnished narrow stripes are used for decoration as found also on early historical pottery from Sistan.<sup>2</sup>

**Pozhoi damb**—The days fruitful survey of old sites in Besēma ended at *Pozhoi damb* a debris area situated about 2 miles LSE of the Taghazai damb. It occupies the termination of a low natural ridge overlooking the drainage bed coming from the east above Zayak and known as Sajid kaur. The ground once occupied and marked by rubble from decayed dwellings and by potsherds extends for about 250 yards from west to east and about 200 yards across. But little of painted or otherwise decorated potsherds could be found here. The majority show either plain dark green and yellow glazes or else glazed polychrome designs which are likely to belong to the Muhammadan period. But a few small fragments have painted patterns resembling specimens from Taghazai damb. It agrees with the continued later occupation which the ceramic evidence indicates for the Pozhoi damb that here the lines of rough stone walls could still be distinguished on the surface of the top and slopes.

**Arrival in Zayak**—The days march brought us by nightfall to Zayak, a wide valley to the east. There near the head of a little streamlet fed by a perennial spring we struck again the motor track leading to Panggur and found the lorries with all spare baggage duly arrived from Surab at the rest house called Jangal. The shelter it offered was doubly welcome after the bitterly cold north wind which had pursued us all day and welcome too was the abundance of fuel which the low tree growth around this rest house offers and which recounts for its designation.

From the rest house I visited on December 18th the two mounds which had been reported above the spring of Zayak. They proved to be situated about two miles to the NNW and up the open valley which descends from the Katgik pass on the road towards Surab. On the way we passed the completely filled in pits of an old Karz said to have been abandoned long before living memory. The northern one of the two dams was found to rise above flat ground of hard alluvial soil cut up by numerous small ravines. Occasional inundation from the flood bed of the Sajid kaur which gathers here and turning westwards passes down to the Besēma trough accounts for the character of the ground and the small patches of khushkaba cultivation to be found here.

Northern mound of Zayak —The mound completely isolated rises to a height of 35 feet above the present level of the clayey plain around. It extends with quite irregular outlines for about 180 yards from north to south and shows a maximum width of about 100 yards at its foot. Examination of the fissures which erosion has cut into the ground near by clearly showed that the foot of the mound has become buried under alluvial deposit to a considerable extent and that the height of the mound must originally have been greater. For those fissures down to a depth of over 10 feet below the present ground level showed strata of rubble which could only have been washed down from the mound and embedded in the alluvial clay long after the decay of the structures once occupying it.

Types of decorated pottery —The top and slopes of the mound are thickly strewn with stones large and small, once serving as building materials and with potsherds. Among these painted pieces abound showing mostly designs executed in black over a fine red ground. Particularly frequent are rows of up curving hooks and scrolls (Z N 136 Pl I) as well as hachured geometrical patterns (Z N 39). Z N 814 are specimens of similar patterns more rarely painted in black or buff over a whitish grey or fawn slip. Quite by itself stands the fragment Z N 7 which combines a string ornament in relief with volutes and other elaborate designs executed both in black and red over a light fawny ground wash. Style and polychrome decoration suggest later origin for this piece and the same may be assumed also for most of the relief ornamented fragments of which Z N 10 11 13 are specimens.<sup>2</sup> That the locality marked by the northern Zayak mound continued to be occupied into historical times is proved by the occurrence of ribbed ware of which Z N 12 is a specimen. Finds of this were comparatively frequent on a slightly detached portion of the mound to the north. Of glazed ware only a single small fragment could be discovered lying on the surface at the east foot of this portion. It shows a freely treated pattern of brown and green spots over yellow ground.

Chips and cores of chert and other hard stones could be picked up in plenty on the slopes of the mound. But only a few small stone blades<sup>3</sup> are clearly recognizable as artifacts. These together with a small piece of copper confirm the conclusion to be drawn from the majority of the painted fragments that the occupation of the site goes back to chalcolithic times. That it continued also later is equally evident. To which period two small stone beads belong is uncertain.

Chalcolithic pottery on S W mound —At a distance of about 300 yards to the south west of the mound just described there stretches a low ridge in the direction from NND to SSW. Its highest point northward rises about 35 feet above the alluvial flat to the east westwards it merges gently into rubble covered little plateau which the floodbed coming from Katgah skirts

<sup>2</sup> The voluted band on Z N 10 distinctly recalls similar relief decoration common among the later Dababli ware see Dr. Haluch's *Ann. P. A. V.*



For about 300 yards the ridge is covered with potsherds and with stones all clearly marking that this strip of ground was once occupied by dwellings for a prolonged period. The painted pottery found here in plenty agrees closely as the specimens reproduced in Plate I show, with that of the mound to the north in fabric and type of decoration. Amongst the patterns almost all executed in black over a deep red slip scrolls of voutes and hooks (Z W 2489) prevail. Of special interest is the 'Sigma ornament (Z W 1) familiar from the painted pottery of chalcolithic sites of Northern Baluchistan, Sistan Tepe Musian etc.<sup>1</sup> The geometrical design of Z W 7 painted brown over light cream recalls the type of Nal ware.<sup>2</sup> Of two fragments of coarsely made terracotta figurines Z W 5 (Pl. I) seems to represent the head of a horse, the other perhaps a human trunk.<sup>3</sup> Also small fragments of worked copper were found here. From all these indications it appears safe to conclude that the occupation of this ridge was coeval with that of the mound.

Small stone enclosures.—On the small plateau to the west, little roughly circular enclosures of stones only a few feet across could be traced in numbers for about 200 yards from the northern end of the ridge. They recalled those funeral cairns<sup>4</sup> of similar appearance which at Moghul ghundai in the Zhob valley had proved to mark a burial ground of early historical times.<sup>5</sup> It is probable that here too the purpose of these stone circles was the same, but the few we could clear contained only soft earth with out any deposit of bones ashes or objects. Of the fragment of a dark blue glass bangle which was picked up on the surface of this ground the age cannot be safely determined.

Change of physical conditions.—Both the northern mound of Zayak and the Taghazamb would have strongly tempted trial excavation had it been possible at this season to secure even a minimum of local labour commensurate to the task. The total absence of a settled population either in Besāma or anywhere else within a radius of thirty miles did not more obliged me reluctantly to forego the attempt. But it also served fully to bring home to me the great change which has come over this region since prehistoric times. It seemed impossible to assume that the Besāma tract could have afforded subsistence to such a number of agricultural settlements as the mounds above described presuppose as existing during approximately the same prehistoric period, if the physical conditions then prevailing had been as unfavourable as they are now. The much discussed geographical question of climatic change or 'desiccation' had from the start helped to draw my attention to these and Gedrosian regions. It was hence of special interest to me to find myself here at an early stage of my explorations brought face to face with antiquarian evidence which distinctly pointed to the local climate having undergone a great change since chalcolithic times in its effect upon cultivation.

<sup>1</sup> See e.g. *A. Ind. & To r Pl. V. p. 93* *AT. MN. V. p. 10* *MM. D. G. VII. R. G. G. I. In eastern Asia Pl. XIII. CNV. Arise. For Ind. Stone Age Pottery p. 90* *Fig. 60*

<sup>2</sup> See below p. 16. *figs.*

<sup>3</sup> See *N. Baluchistan Tour Pl. 40 & 41* also below Chap. V. *Pl. I*

## CHAPTER III —OLD SITES IN RAKHSHAN AND PARŌM

### SECTION 1.—REMAINS AT THE HEAD OF RAKHSHAN

On December 20th we set out by motor from Zayak on our way into the Rakhshan valley. Nag fully 60 miles away had to be fixed for our initial stage as it is the first permanently inhabited place in it and also because at the only two points where dams were reported to exist near the route no water could be found. Right down to Nag the ground traversed by the route now belongs politically to Kharan. But as the division here drawn between Kharan and Makran is not based on geographical facts but only upon the limit which the establishment of the *Pax Britannica* towards the close of the last century fixed to the southward expansion of the Naushervan chiefs it may be here disregarded.

Across head of Reghai tract.—After skirting the southern extremity of Besema the road led through a maze of utterly barren hills and across the Kaparna pass to the arid plateau at the head of the Reghai tract which is drained by floodbeds feeding the Dhutari. This itself belongs to the headwaters of the Mashkan river which flowing due south through Jhalawan ultimately finds its way to the ocean as the Hingol. This on this plateau there meet two natural cross roads leading from Southern Persia to Kalat and the Indus and from the sea to Kharan and the Helmand valley. But on that day's drive we met no humans but two Brahms grazing their flock of sheep and goats near the well of Patakan the only one passed.

Mounds of Badrang dam.—Where the route about halfway to Nag first touches a stretch of Khushk ba cultivation<sup>1</sup> not far from the almost imperceptible watershed towards the Rakhshan drainage we reached the group of low mounds known collectively as *Badrang dam*. It extends over some 380 yards from north to south and about as much across. The average maximum height of the mounds is only about 10 feet. But as the level of the ground around has certainly been considerably raised by alluvium from the floodwater brought here for the sake of cultivation in years of good rainfall probably much of the lower portion of the mounds is buried below the soil.

Chalcolithic potsherds.—Over the whole area pottery debris is strewn in plenty and among it very numerous painted pieces showing prehistoric patterns were picked up. The specimens reproduced in Pl II will help to illustrate the most frequent motifs. Among these the hachured leaf shapes (B R 12 & 15) the rows of solid lozenges between horizontal bands (B R 2 & 6 12), the hachured geometrical forms (B R 8 & 9) have all their exact counterparts among the painted ware of the earliest Zhob and Loralai sites.<sup>2</sup> There too

<sup>1</sup> The position is approximately marked on Map No 35E B1 by the entry *Nat-Uah*. The name is locally unknown and probably refers to some well in one of the side valleys descending from the ranges which enclose the head of the Rakhshan valley.

<sup>2</sup> Cf. N. Baluchistan Tour Pl V VI XI XX

is found the Sigma motif of B R.3 The concentric squares and polygonal shapes of B R.16 17 17a as well as the parallel wave lines of B R.7 recur at Rana ghundai<sup>3</sup> But it deserves to be noted that the fine red ware with black patterns of those early sites is rare at Badrangdamb while buff grey light cream coloured grounds or slips prevail and the designs are generally painted in coarse browns or purples Of relief ornamentation only narrow parallel wave lines as in B R.18 could be found Only a single glazed fragment with a hatched pattern in brown and green over yellow turned up and that too close to a Muhammadan graveyard adjoining the western edge of the site The ancient painted potsherds which lay on some of the graves had evidently been found while digging these<sup>4</sup>

**Absence of water**—Considering the extent of the debris strewn area and the size of the ancient settlement which it indicates the total absence of any permanent supply of water in the wide valley plain around the site is significant This ground is temporarily occupied only when a good rainfall allows Brahm nomads to till the patches of Khushkaba land near by and then water may be found for a time in pools of the neighbouring Patakan flood bed If there is a crop to reap and the pools have dried up water would have to be brought in skins from distant wells or waterholes in the hills The same arid conditions continued when after crossing the divide we moved down the wide open valley of the Nag river which is one of the principal feeders of the Rakhsan No water was to be found until camp was reached at the point where the road passes within a couple of miles of Nag village There springs gather in the bed as it passes through a low chain of hills Hence it was impossible to halt at the site of *Kangushki damb* which was reached after about 20 miles from Badrangdamb But the rapid survey I was able to make of it sufficed to show its interest and I accordingly returned to it from Nag camp on December 22nd for closer examination

**Kalatuk damb of Nag**—On the day following my arrival at Nag camp I proceeded to the small village of Nag situated where the little spring fed stream debouches from the defile already referred to Of the several dams which had been reported close to the village the chief one is situated as the sketch plan in Pl 2 shows close above the left bank of the wide sandy flood bed of the river and near the easternmost patch of ground that is irrigated from the permanent streamlet meandering within it There a stony plateau between rubble built walls and with potsherds This area of ancient occupation measuring about one third of a mile from SE to NW and about 300 yards across where widest is known as *Kalatuk damb* ( the fort mound ) from the rocky hillock rising at its north western extremity to a height of about 100 feet above the river bed It is a naturally strong position and is crowned by rubble stone walls of very rough construction and probably modern

<sup>3</sup> See Vol. I Pl. VIII

<sup>4</sup> For a similar observation at the prehistoric mound of Pr. Al. 2a. of Vol. I p. 8

Painted pottery and terracotta figurine—Traces of ancient walls built with roughly squared freestone and resembling those to be described below in connexion with the Kargushka dam crop out on the surface of the site below. But more evidence of very early occupation is supplied by the plentiful painted potsherds found there. Most of them as seen from the specimens reproduced in Pl II show geometrical designs painted in black over a dark red or buff ground. Though the execution is on the whole coarser than in the case of the painted pottery at the prehistoric sites discussed in the preceding chapter and at those visited in Zhob and Loralai yet close relationship in the decorative motifs is unmistakable. Of peculiar interest is the ornamentation with rows of large horned animals probably representing Ibex in a bold pose, found in NK 2,6, also the appearance of parallel bands with close set upright strokes NK 5,8,9 which the recurrence of a similar motif in larger and better preserved specimens from other Makran sites permits us to interpret as meant to represent grass or scrub<sup>5</sup>. But the most interesting object picked up at Kalatuk dam is the small bird like head of terracotta NK 4,2 (Pl VI), it belongs undoubtedly to a very primitive rendering of the female figure found as a draped bust at the chalcolithic sites of Pernano ghundai Moghul ghundai Surjangal etc and evidently representing a goddess<sup>6</sup>. We shall have occasion to meet with far more numerous terracotta figurines of the same type at chalcolithic sites of Makran and Jhalawan to be discussed further on<sup>7</sup>.

Mound near Nag village—At a distance of over half a mile from the Kalatuk hillock and on the opposite bank of the river bed lies the village of Nag. Though it is the only permanently occupied place in Upper Rakhsan containing some two dozen dwellings and palm-mat huts, not more than ten able bodied men could be collected in it for the morrows proposed trial excavation at Kargushka dam. All the rest of the Brahui inhabitants were away with their flocks in the hills where grazing and firewood for protection from the winter cold are more easily obtainable. An orchard owned by a relation of the Naushirwan chief of Khaian and irrigated by a canal from the stream is with its date palms, mulberry trees and vines the only attractive feature of the little oasis. About 200 yards to the north of it I was shown a second 'dam', now for the most part occupied by Muhammadan graves clustering round the tomb of a saint known as Pir Mizam. That this low swelling of the ground marks the position of an earlier settlement was indicated by a few small fragments of painted pottery which bear patterns of the prehistoric type. But far more numerous were broken pieces of glazed ware plain or decorated which looked medieval.

Ridge of Singi Kafat—Proceeding half a mile eastwards up the valley and across a low rocky ridge we reached the third 'dam' of Nag close to the right bank of the river bed. Here plentiful pottery debris lies around the foot and on the slopes a steep rocky ridge about 75 feet high and known as

<sup>5</sup> See below pp. 122-159

<sup>6</sup> See *N. Baluchistan Tour* Pls LX, P, W 5, 9 Pls XII, K, 14, XVI, T, N, D, 9, S, J, 68


<sup>7</sup> Cf. below pp. 156-160 160 sqq. etc

*Si q' Kalat* the rock fort The very narrow top of the ridge is flat for about 60 yards and has been enlarged to the south by a roughly built but massive terrace of stones which looks old Part of the crest bears a sangar made of stone heaps and evidently recent Besides plain pottery of good make fragments of ribbed ware as seen in the specimens NS 1 a (Pl II) are here very frequent Together with the piece NS 4 showing incised decoration and a moulded handle these ribbed potsherds clearly point to occupation of the small site during comparatively early historical times It deserves to be noted that not a single ribbed fragment was found at Kalatik damb


*Tomb of Bib Ziarat*—On our way back to camp I visited on a low bare ridge about a mile to the south west of Singi kalat the ruined tomb known as Bib Ziarat (Fig 5) Built with burnt bricks and decorated with panels of carved bricks showing geometrical relief patterns over a sunk ground it is a typical specimen of the style of decoration to be found on Muhammadan sepulchral structures in Kharan and Makran apparently dating from late medieval times Within the little tomb chamber a corpse was exposed to view still retaining rigs of its cotton shroud or vestment

*Kargushki damb*—On December 22nd I returned for a renewed examination of the *Kargushki damb* which on our way down to Nag could only cursorily be inspected The motor lorry allowed me to take along the ten men collected at Nag village for a short trial excavation This extensive mound is situated up the valley a little over 11 miles from the point where the bed of the Nag river passes into the defile above mentioned It rises about half a mile to the east of the road and though not more than 40 feet high forms a conspicuous object in the wide flat plain of the valley At an average distance of some 120 yards its western foot is skirted by the dry bed of the Nag river As the plane table survey reproduced the sketch plan of Pl 3 shows the length of the mound from north to south is about 530 yards and its width where greatest some 360 yards Its slopes towards the river bed are steeper than those to the east and on both a considerable amount of fine drift sand has collected in eroded small Nullahs this extends also over the mostly flat top

*Extent of ancient occupied area*—The surface is throughout covered with flat pieces of freestone mostly small the debris of walls such as were found to crop out in at least three distinct places on or near the top Wherever the accumulation of drift sand is slight or absent potsherds are exposed in plenty on the slopes Their presence can be traced also over a considerable portion of the level ground around the mound especially to the north and north east The total area of ancient occupation thus indicated extends over about 900 by 350 yards to the east of the river bed But also on the right bank of the bed such debris can be traced for a length of some 400 yards A portion of the once occupied ground between the northern and western foot of the mound and the river bed is used for Khuzk ba cultivation The low earth embankment which the plan shows along a stretch of the left river bank serves to catch whatever rain water may descend the western slopes of the mound Similar patches of precarious cultivation are to be found scattered for a




7



8

9

10





considerable distance both above and below the Kargushki dam and on both sides of the flood bed. But there is none of it on the right bank just opposite to the mound and here potsherds could be picked up in places right up to the road which leaps to a slightly higher level. At one point a small eroded terrace resembling a Yardang of the Tann basin bears scanty remains of walls of the same construction as those excavated on the mound.

**Walls cleared**—Already on my first rapid inspection of the mound my attention had been attracted by a line of stone masonry cropping out on the western slope amidst debris at a level of about 6 feet below the top of the central portion of the mound. Some slight digging had evidently been done along it at one time or another. The excavation carried out here on December 22nd resulted in the clearing of walls belonging to one structure *A*, which extended over an area of about 40 by 35 feet and comprised at least four separated apartments. The plan in Pl. 3 will explain their disposition and the photograph in Fig. 7 illustrate the character of the masonry used for the walls. It consists of small slabs of freestone of varying thickness but rarely exceeding 8 to 10 inches in length set in fairly uniform courses with soft plaster of clay to secure cohesion. The fact that the average thickness of the walls is only 1 foot and 6 inches and that along the east side of the rooms *a* and *b* the walls were still standing to a height of over 8 feet proves the solidity of construction. The thickness of the wall dividing the small passage *c* from room *d* is only 1 foot 3 inches. It was interesting to note that in the rooms *a* and *b* the walls were provided with plinths varying from 2 to 9 inches.

**Rooms excavated**—In these rooms the excavation along the wall on the east side was carried to a depth over 8 feet from the extant top of the masonry without striking a recognizable floor. But the remains of a large pot of coarse make 1 foot 8 inches in diameter found at that depth in *a* close to the wall dividing that room from *b* showed that the floor could not have lain much lower. The walls to the west being on the slope were found broken much lower down. The narrow passage *c* only 2.4 wide appears to have given access to interior rooms of the structure but these could not be cleared with the few available men. A low doorway leading to this passage from the north could still be made out. The masonry of small stone slabs above the entrance had rested on timber of which the charred and rotted remains were traced *in situ*. Both in room *a* and beyond room *d* there were found walls of rougher construction possibly later additions. That the ground occupied by the structure *A* had been built over later is made probable by shallow wall foundations traceable on a higher level close by. These rested on loose earth and debris from completely decayed earlier dwellings.

**Painted pottery**—Similar material filled the interior of the rooms excavated. Embedded in this material were found numerous pieces of painted pottery and these may claim distinct interest on account of the stratigraphic evidence they afford. In room *a* there turned up comparatively large fragments of four different painted vessels at approximate levels of 3 to 5 feet above the probable flooring. The style of their decoration geometrical



throughout shows close affinity, though the motifs and their arrangement vary. Of the wide mouthed bowl Kara 1 the four pieces found (Pl V) fit together, showing that the diameter could not have been less than 2 feet. The decoration is executed in dark brown over a light cream coloured slip which may have been applied after firing for both this ground colour and the design over it have been affected by damp and are liable to suffer by rubbing. The decoration consists below the rim of the mouth of three narrow bands of lozenges separated from each other by four parallel rules. Lower down are two uniform courses of interlocking garlands the junctures of the descending and ascending loops being covered in each case by large oval ornaments. The courses are divided from each other and edged above and below by plain parallel rules.

Decorative patterns.—The pieces Kara 23 (Pl V) closely resemble the above in colour treatment. They also show below the rim courses of linked lozenges between parallel rules. But owing to the way in which two sides of the lozenges are elongated by strokes, a freer treatment of the lozenge motif is introduced. In Kara 3 we have a second course of lozenges and below this a course of concentric quadrangles separated from each other by a kind of triglyphs. In Kara 2 the place of the second lozenge course is taken by a band of open triangles and the rest is missing. In the bowl fragment Kara 4, Pl V, which lacks the mouth we find first a course of open triangles and below, separated from it by parallel rules a broad band comprising a pair of vertically arranged hachured lozenges flanked on either side by dark streaks and hachured triglyphs. Kara 5 (Pl II) is a fragment of a smaller bowl which evidently bore a similar decoration above its foot.

Resemblance to Nal pottery.—Most of the smaller painted potsherds excavated in the several rooms of the structure agree with the pieces already described in having their designs painted over a light coloured slip or ground wash which appears to have been applied after burning and is affected by damp or rubbing. Among them the pieces Kara 56, Kara 1 (Pl II) are of special interest because they show very close affinity to the painted ware recovered from the Nal necropolis by Mr Hargreaves and others, both in the patterns and their multicolour treatment. Kara 6 still shows red and green washes, though much effaced used to fill in different parts of the designs. The same is the case with the other two fragments. In Kara 14 (Pl II) the patterns are such as are found at sites where the ware of 'Nal type' is absent. By itself stands the small fragment Kara 9 (Pl II). It is of a very fine black fabric and shows a wheel like motif round a small raised centre. With these exceptions and that of some fragments of small flat bowls which have a plain black or dark brown paint applied before burning the rest of the painted pottery excavated shares the general characteristics above indicated. The evidence afforded is important because the conditions in which these pieces with more or less evanescent colours were found excludes the idea of this kind of colouring also the very small fragment, Kara 12 less than an inch in length which

shows on both sides remains of a mat green glaze. It was found about 2 feet below the surface of the slope. Whether it can be considered coeval with the latest occupation of the mound must remain doubtful at present.

It is obvious that the painted ware found in a structure almost at the top of the mound must belong to vessels actually in use during the latest occupation of the site. It is equally certain in view of observations made elsewhere that this period was a prehistoric one. In order to ascertain what deposits from preceding periods may be contained in the lower strata of the mound extensive excavations would be needed and for such the labour obtainable at the time was wholly inadequate. This task likely to yield very instructive results had therefore to be left for some future archaeological visitor of the site.

**Prolonged prehistoric occupation**—The search made by me for such indications as surface finds might furnish regarding earlier periods of occupation was much impeded by the drift sand which covers most of the slopes and the ground around. But enough of painted potsherds were collected to show that the prehistoric stage of occupation marked by the finds in the rooms excavated must have been a prolonged one. For among the painted pieces collected from the surface of which Pl II reproduces specimens those corresponding in type to those finds were the more numerous (see Kar 48). Fragments such as Kar 13 which show simple geometrical patterns executed in black or brown on a reddish clay apparently without a slip or ground wash may be earlier. This I think can safely be assumed of Kar 9 which shows a neatly drawn hook design over a fine dark red slip such as is common at the early prehistoric sites of Zhob and Loralai. It ought also to be noted that among undecorated potsherds those showing a carefully levigated and well burnt clay with a dark red or brown surface were very frequent. Judging from what experience at prehistoric sites of Northern Baluchistan has taught me such superior plain ware is likely to belong to earlier prehistoric deposits. From the fact that we did not come across a single potsherd with ribbing or other relief decoration it seems safe to conclude that the site was abandoned before historical times. What the direct cause of this abandonment was it is of course impossible to say. But so much is clear that no settlement of such size as the extent of debris area indicates could continue to exist here since the physical conditions of the ground have assumed the extremely arid aspect they now bear.

## SECTION II—IN THE PANJGUR OASIS

December 23rd saw me on the road to Panjgur. It was important for me soon to reach this chief northern oasis of Makran because only about Christmas could I feel reasonably sure to find Captain D. R. Smith Assistant Political Agent Makran and Commandant of the Makran Levv Corps at his Panjgur headquarters and thus conveniently to secure in advance all the local advice and assistance I felt in need of before starting my work in Makran. There

was nothing to detain me on this journey of some 82 miles, for the portion of the Rakhsan valley along which it led is throughout as barren as it is wide and lacks opportunities even for such precarious cultivation as is met with above Nag

'Damb of Mayai chah—The only place with marks of former occupation of which I could learn was a 'damb passed by the road some 2 miles above the lonely well of *Mayai chah*. We reached it after skirting low broken hills for about 8 miles from our Nag camp. There at the mouth of a small side valley there extends a little trough holding potentially fertile alluvium. A low rocky eminence rising within it is proved by the plentiful coarse pottery which covers it to have been once occupied. No painted potsherds were found among it beyond two fragments showing only black bands over buff ground (M Ch I, Pl II) and affording no chronological indication. But there were traces of a wall on the rocky crest with masonry resembling in type that found on the Kargushki damb.

Further on the road throughout leads across a dreary succession of Nullahs descending from the ranges on either side of the valley and over stony plateaus between. The floodbeds which furrow the latter, just like the bed of the Rakhsan river itself are too deeply cut into the valley bottom to afford here a chance for cultivation be it only of the Khushkaba type. On the days long drive we met only two nomadic families before at Senkoran we reached the uppermost of the string of small villages all ensconced amidst date groves which together are known as Panjgur. They extend at intervals along both banks of the river for a total distance of about nine miles.

Arrival at Chitkan—At Chitkan the centre of the whole oasis I found Captain D R Smith just arrived at his headquarters from a long tour along the Makran Levy posts towards the Persian border and received a very kind and hospitable welcome from him. The local information which the friendly help of this active and experienced political officer promptly secured for me made it possible to visit during the next few days whatever objects of antiquarian interest Panjgur has to offer. I subsequently derived great benefit from the arrangements he kindly made at the different border posts held by detachments of his Corps in order to facilitate my survey of any ancient remains to be found in their vicinity. The escorts from the Makran Levy Corps which under Captain Smith's orders were provided for my camp while moving along the Persian frontier and on my prolonged tour in the Dasht tract proved very useful in various ways besides assuring complete safety for all this help and the valuable support accorded to me through the exercise of his influence with the local authorities of the Kalat State I wish to record here my heartfelt thanks.

Irrigation of Panjgur—In Chapter I it has already been pointed out that Panjgur owes its importance as the chief centre of population in the northern part of Makran entirely to the fact of a permanent supply of water for irrigation of its lands being assured from karezes and from pools in the river bed which springs and flood water fill. In the absence of reliable records it is not possible to determine how far back in historical times the existence of Karezes

may go. But it is obvious that the configuration of the ground from the point where the Rakhshan river some miles above Serikoran emerges from a confined bed into a wide riverine flat must here at all times have facilitated cultivation and hence also the settlement from an early period of a larger population. It must therefore seem strange that no mounds definitely proving prehistoric occupation could be traced by me at or near Panjgūr.

**Absence of prehistoric mounds**—As so often in the case of negative facts it may seem risily to attempt an exact explanation. But in any case two local observations deserve to be kept in view as possibly bearing on this fact. One is that owing to the flatness of the ground the riverbed within the Panjgūr area is liable to considerable shifts in the event of exceptional floods. Such changes would easily again and again obliterate the debris deposits of ancient village sites. The other observation relates to the peculiar way in which the conditions connected with permanent irrigation and intensive cultivation such as is practised in oases like Panjgūr and Turbat affect the distribution of homesteads. Throughout these oases I noted that the cultivators huts or mud hovels almost invariably are placed far apart from each other and always within the individual plots of ground where they raise their several annual crops amidst clumps of date trees. Close agglomerations of dwellings or huts such as may be found in localities where cultivation is dependent on rainfall and is necessarily carried on over greater stretches are conspicuously absent in these oases. If we are justified in assuming that similar conditions of tillage and occupation prevailed on this ground already in early times the absence here of prehistoric mounds such as only accumulation of debris from prolonged occupation at close quarters would produce could be more readily accounted for.

**Mound of Kohna kalāt**—Yet Panjgūr does not lack altogether 'dambs' marking ruined sites. The most conspicuous among them is the mound known as *Kohna kalāt* the 'old fort'. It is situated about 1½ miles to the south of the date groves of Isākalāt village on the left bank of the river. Local tradition points to the seat of the Mahks of Makran having stood here during late mediæval times and after<sup>1</sup> and examination of the mound fully confirmed this dating of its occupation. The mound (Fig. 8) rises to a height of about 30 feet above the level of the fields around. On its top it measures about 160 yards from north east to south west, with a maximum width of about 35 yards across. On the eastern slope which erosion and digging for manuring earth have cut away steeply walls of sun-dried bricks are exposed on most of the height. Among the pottery debris embedded in the mound glazed ware is plentiful. Apart from plain green or dark blue pieces some fragments showing designs in dark outlines over brown or green glaze were also picked up (see P.K. I Pl. II). Pieces decorated outside with ribbing (P.K. 2) or inside with burnished lines (P.K. 4) may also be assigned to Muhammadan times. Only a few specimens of painted pottery were found with coarsely executed black designs easily distinguishable from prehistoric ware.

<sup>1</sup> See *Makran Gazetteer* pp. 206 sq.

Much eroded low mounds covered with potsherds were traced for about one third of a mile to the north and north east of the ruined fort. Here too glazed potsherds, plain or decorated, like the specimens P K a 14 (Pl. II) indicated mediæval occupation. Muhammadan graves edged with large mud bricks were exposed to view on the bank of the bed which a flood channel from the river now dry had cut into this 'Tati' like ground on the north-west.

**Site of Chiri-damb**—Indications of far earlier occupation could be traced on another area of the 'Tati' type which was visited near the right bank of the river below the present limit of cultivation of Tasp village and opposite to Isakht. It is known as *Chiri damb* and stretches down not far from the river bed for about half a mile. The river was said to have encroached here a good deal on land formerly cultivated. Here it was possible to pick up small painted pottery fragments showing prehistoric patterns in black like P Ch 12 (Pl. II) by the side of glazed potsherds plain or decorated manifestly mediæval for a small specimen showing remains of green glaze over neatly executed relief ornament see P Ch 5 (Pl. II). Here too for the first time in Makran I came across again a small fragment of that fine grey ware with black design of which rare specimens had been found by me at prehistoric sites so far away as Zhob and Sistan.<sup>2</sup> Among other relics left here by early occupation were a number of small stone beads acquired from a local villager, some of which show decoration with a very ancient method of white inlay,<sup>3</sup> and a stone scraper. The small terracotta figurine, P Ch 3 (Pl. VI), showing a female bust with arms akimbo has also its pendants at prehistoric sites. Pieces of ribbed pottery serve to bridge as it were the wide gulfs of time between all these small relics.

**Sari damb**—At the upper end of Tasp village I had occasion to see a Muhammadan tomb probably late mediæval decorated with blue enamelled panels which show figures of animals very coarsely executed in relief. Similar decoration of tombs was said to be found elsewhere in Makran. Where the last palm groves of Tasp down the river bank stand I was shown a small mound about 12 feet high known as *Sari damb*. Judging from the decayed stone walls its top had evidently been used as a place of defence in modern times. There was no pottery debris to afford evidence as to the age of the strata below.

**'Dams' above Chitkan**—Long rides from Chitkan, the Panjgur head quarters enabled me to inspect whatever 'dams' were reported up the river. The one shown between the upper end of Senhoran village and the road proved a low stony plateau strewn with scanty coarse pottery. As apart from a single fragment with black rules no painted pieces could be found nor any ribbed ware late occupation appeared probable. But a small stone flake found here shows signs of use. About 5 miles further up I visited a stony ridge rising to about 50 feet above the riverbed and known as *Damb-i-dambi*. It lies a little beyond the isolated patch of fields called *Bairan dan*, which marks the uppermost extension of Panjgur cultivation. Remains of rough

<sup>2</sup> Cf. *N. J. I.* in *T. o. P. J.* 1914, 431. *It. r. o. f. a. s.* pp. 977 sq.

<sup>3</sup> *See* in *the* *collection* of *the* *late* *Mr. Macgregor* *finds* of *Mr. Mackay's* *paper* in *J. P. A. S.* 1906, p. 1091.

stone walls could be traced here, proving former occupation. But what scanty plain pottery was found afforded no chronological indication.

Debris areas of *Sraduk* and *Besham*.—About a mile away to the west across the wide bed of the river a small date grove marks a patch of former cultivation known as *Sraduk*. It was said to have been abandoned some 25 years ago owing to the drying up of two *Karezes*. About 400 yards to the west of it there is reached a low plateau extending for about 300 yards from north to south and about 200 yards across. Among the heaps of rubble which cover it coarse plain pottery is plentiful. Among the few painted potsheerds found at this damb there are two (see *Sraduk* Pl II) which by their hatched black patterns applied on buff ground suggest prehistoric origin. Fragments with simple incised ornament like *Sraduk* 23 (Pl II) may also be early. A few glazed and ribbed pieces indicate occupation down to mediæval times. About 1½ miles further down there is reached the extensive debris area known as *Besham damb*. It stretches for nearly three quarters of a mile from east to west and on the average is about 500 yards across. Among the pottery found here the same types of decorated ware are represented as at *Sraduk*. *Besham* 1 (Pl II) shows a painted geometrical pattern of prehistoric type while *Besham* 2 mat-marbled looks also early. Continued occupation is indicated here also by glazed fragments.

Embankments of *Pardun damb*.—Proceeding down by the river bed for another mile or so there was reached the locality known as *Pardun damb* from a wide torrent bed that descends close to the west of it. The remains here proved to consist of three successive stone embankments solidly constructed of large unhewn stones. They manifestly were intended to secure flood water for level areas which extend between the torrent bed and the low swelling ground eastwards. The embankments are separated from each other by intervals of about 90, 100 and 200 yards respectively starting from the northernmost. It was curious to note that the true character of these embankments obviously old *Gabar bands* is not understood by the cultivators of Panjgur. Judging from present day conditions they find it hard to account for so much labour having been spent for the sake of so little cultivable ground. They could scarcely be expected to realize how much greater the pressure of population may have been in ancient times. Potsheerds were scarce here and all of plain ware.

Small dambs on right bank.—The same was the case on the stone covered plateau about one third of a mile across and known by the name of *Chorrak damb*. It was reached two miles further down after slirting the irrigated lands of Washbod with their continuous belt of date palm groves. Also at the small damb of the village of Gramkan which adjoins lower down the potsheerds consisted almost entirely of plain coarse ware the few fragments with painted parallel lines affording no clue as to age. Finally I visited about a mile to the west of Gramkan the mound of *Khudabadun*. It is crowned by the ruined walls of a fort which was said to have been built or restored by the father of present chief representative of the Naushurwan clan at Panjgur.

and subsequently destroyed by order from Kalat. Judging from the few fragments of decorated pottery including glazed ware, to be picked up on the slopes below the small mound is likely to have been occupied about the same period as Kohn Kalat.

**Panjgur in Muhammadan times**—From the survey of such remains as could be traced in and near the Panjgur oasis it would not be safe to conclude more than that the settlements comprised in it were once somewhat larger than the present ones anyhow during medieval times. It is possible to account for this without assuming any great change in the physical conditions and the economic resources dependent upon them by the fact that Panjgur owing to its position on a main route connecting Persia with the lower Indus must have claimed considerable importance with regard to whatever trade passed between those two regions in early Muhammadan times. The existence of such trade appears to be well attested by the references of early Arab geographers and travellers.<sup>4</sup>

As they all rightly describe Makran as for the most part desert Panjgur being a place where caravans could rest after many marches across barren ground may well have then enjoyed some degree of prosperity. Thus if the proposed identification of Panjgur with a stage on that trade route which the Muhammadan authors mention under varying forms of the name as Kanazbun, Kanarpur, etc., is to be accepted we could reconcile their references to its wealth with what the examination of the oasis and its scanty surviving remains has shown us. But it ought to be noted that the proposed location appears still to await critical re-examination on the basis of the original texts.

## SECTION II—THE BASIN OF PAROM

On December 28th I left Panjgur for the Persian border. I was anxious to visit the mounds in the Parom basin adjoining it of which I had received a report. A newly made motor track connects the Makran Levy Corps posts which guard this far off stretch of the North west Frontier and offered facilities for reaching Parom by a route combining geographical with quasi antiquarian interest.

**Visit to Grawak**—A drive of some 56 miles along the barren gravel plains of the Sulaiman range and well above the course of the Rakhsan river took me on the first day to the small fort of Grawak. It is situated at the point where the Rakhsan river joins the Mashhad close to the projecting angle of Persian territory comprising the tract of Kuhak. Held by a detachment of the Makran Levy Corps it guards the entrance of the narrow defile in which the united river makes its way into the Khuran basin. Next morning descending in the defile for about two miles I visited the delightfully green spot where springs issuing in a ravine amidst gloomy conglomerate cliffs permit the Bledji families of Grawak to maintain cultivation on terraced fields in

<sup>4</sup> I take the reference to Panjgur in the *History of India* as being in the Appendix where these Arab notices are collected. See also *Revue de l'Asie* Vol. 10, p. 47. At this time I conjectured identification of Panjgur with *Kanazbun* as given in the *Geographical Journal*, p. 257 sq. 1910.

a nook of these and hills. Above this there rises steeply a small rocky ridge, precipitous cliffs render it practically inaccessible on all sides except from a narrow ravine on the south. Potsheids lying on the crest showed that this ridge had served perhaps more than once as a natural place of refuge, but as they were all of plain coarse ware they furnished no indication as to the time of such occupation. It was no surprise to find the main spring duly honoured as a place of local worship, marked by the supposed resting place of a saint, Pir Umar Jan.

Gar post on prehistoric mound—The same day a drive of some 35 miles along a difficult track passing through utterly bare broken hills and desolate valleys brought us to the Levy post of Gar. It is situated to the south of the Rakhshan river, practically dry where we crossed it, and in the wide trough of a valley which descends from beyond the border. The small post had been established only for a few years to keep off cattle raiding parties from the Persian side, and within the little entrenchment nothing better than reed huts and dug outs had been provided for the shelter of the two dozen odd Brahui levies. Some distance outside in a little group stood the palm mat huts forming the homes of the men's families: these are liable to be shifted periodically with the detachment along the line of posts. It seemed an apt illustration of what a newly started Roman outpost held by local auxiliaries might have looked like on a Syrian or African *Limes* line.

But I soon realised that there was a more direct archaeological interest attaching to this lonely post of a modern British *Limes*. For fragments of painted pottery found amidst the refuse on the slopes of the little mound on which the post has been placed proved that the spot had been occupied already in prehistoric times. The potsheids picked up at Gar are almost all of a fine red ware, and among the patterns painted in black is found the hook design (Gar I, Pl. III) already familiar from the prehistoric mounds of Basima and elsewhere. The advantage of a height commanding the flat alluvial plain around obviously accounted for the latest occupation of the mound, and similar reasons, no doubt, caused it to be tenanted in the distant past.

Pipih-kafat—Our journey on December 30th lay first over a wide sandy plain stretching to the south east near one of the dry flood beds in which the Gwargo river descends into the lowest portion of the Rakhshan valley. One of our lorries there stuck in a shallow pool which the latest run had caused to extend across the road and it cost some hours before we could extricate it. Then not far off, at about 11 miles distance from the Gar post I visited a small hillock known as *Pipih-lalat*. It proved to be formed by a tamarsk cone of the regular type so familiar to me from the Turim basin, on its top, about 25 feet high it is covered by live tamarsk bushes. Coarse potsheids of uncertain age were picked up on flat ground when approaching the hillock from the south. Scattered rough stones on its top marked a rough walled enclosure which looked recent. That some cultivation had once been carried on in the vicinity was suggested by a line of pits marking an old *Kariz* which was passed about a mile and a half further on.



Kap marsh of Parom basin—Then the track turned south towards the gaunt serrated hill chain known as Pipiski after passing for some seven miles through the stony desolation of much eroded ridges it suddenly brought us into view of the long stretched dragnageless Parom basin. Its centre holds a great salt marsh extending for over 25 miles from east to west and fully 8 miles across where widest. It is completely dry except after a season of heavy rainfall and is known by the generic Baluchi term of *Kap*. With its absolutely level salt encrusted expanse smiling westwards below the horizon this *Kap* strangely recalled to me the dried up Lop sea bed. Fortunately its glittering surface of salt presents none of the difficulties encountered on the latter through blocks of hard salt upheaved into hummocks etc. Yet the salt crust covering the *Kap* is also cracked into innumerable pentagons after the typical fashion of such dried up salt marshes. Its soft surface offers ideal going for cars. So the small fort of *Diz Parom* at the foot of the wide gravel glacier descending towards the south western edge of the *Kap* was safely reached before nightfall even though we had followed too far the track leading to the present Levy post at the western extremity of the *Kap* and subsequently had to make a great detour to gain our destination.

Cultivation in Parom basin—*Diz Parom* lies near the eastern end of that portion of the Parom basin where the head of the salt marsh narrows to a couple of miles. There room is left for a wide belt of scrub covered ground along the foot of the hills forming part of the Central Makran Range which enclose the basin on the south. This gently sloping ground extends for more than twenty miles westwards to the watershed marking the Persian border, on it good grazing can be found and also patches of Khushkaha cultivation. The general belief in Panjgur was that with a population less scanty and less addicted to nomadic cultivation could be considerably extended even now for Parom is credited with a somewhat greater rainfall than the rest of the area comprised between the hills of the Central Makran Range or the valley of Rakhsheh.<sup>1</sup> But what may be considered quite certain is that this part of the Parom basin once afforded subsistence for an agricultural population of some size for only on this assumption is it possible to account for the number of ancient mounds which I was able to trace on this ground.

Fort of *Diz Parom*—The small fort of *Diz Parom* until some years ago held is a post of the Makran Levy Corps raises its thick mud walls on the top of a small mound about 30 feet high. That this is composed of ancient debris is certain. But owing to the accumulation of refuse on the slopes which prolonged occupation of the fort as a place of refuge in modern times accounts for and the presence of a regular nomadic camping ground immediately at its foot no close search of the slopes for potsherds was practicable. The few fragments of painted ware which were picked up here and of which Pl. III reproduces specimens are obviously prehistoric. They belong to two

<sup>1</sup> Cf. Hughes Bul. of Makran Gazetteer pp. 217 sq. The Census tables of 1921 show for *Diz Parom* and Sar Parom a total population of only 312 souls.

separate flat dishes and are both decorated with geometrical patterns neatly drawn in black. The design in D P 1 consists below of lozenges formed by conventional leaf shapes alternating with circlelets arranged to form smaller lozenges along the rim there is a row of small ovals. Outside there is below the rim a broad border composed of a lozenge diaper. The second dish appears to have been decorated inside with a similar but slightly larger pattern. The fabric of both dishes is a very fine clay of dark terracotta colour remarkably hard.

**Prehistoric mounds near Diz-Parom**—About a mile to the north of the fort there rise two mounds close together above the scrub covered ground. The one to the east has a diameter of about 50 yards and is about 20 feet in height. It is covered with abundant pottery of superior make both plain and painted. The colour of the painted ware varies from dark red to buff and a yellowish grey. The patterns (see for specimens D K 19, P I III) all geometrical are executed mostly in black or brown and comprise successions of stripes surmounted by small vandykes, hachured leaf shapes and a variety of scroll work. A number of pieces show dark pink bands besides black or brown as a second colour in their design. In addition to a few fragments with incised ornament of a simple geometrical type there was found here the piece D K 10 (P I III) showing the coarsely incised outline of a fish. Some pieces with raised ribbing and the fragment of a handle found here make me inclined to attribute the occupation of this mound to late prehistoric times. On a smaller mound about 200 yards to the west painted potsheids were distinctly fewer and their patterns coarser while pieces decorated with raised ribbing (D K b 1 P I III) were proportionately more numerous. But here too not a single glazed fragment could be found which might prove occupation into historical times.

**Early painted ware of Jai damb**—Riding westwards for about eight miles across a scrub covered clayey plain which clumps of trees and scattered Khushkiba fields varied in places we arrived at the small mound known as *Jai damb*. Its height is only about 12 feet and its top occupied by a roughly built enclosure of sun dried bricks measuring inside 20 by 26 yards. The enclosing walls as well as a small ruined tower at the north west corner are comparatively modern though the aged 'kandhi' (Katkhuba) or headman of the Baloch camping about Sir Parom declared that they were already in ruins when his grandfather came to use the little circumvallation for a time as a place of safety. But closer inspection soon showed that the mound itself goes back to a very early period. The plentiful painted pottery found on the slopes and around the mound provided a welcome surprise. The geometrical patterns boldly executed in black or purple over a ground which varies from red to buff and brown display an unmistakable affinity to those of the painted pottery with which the chalcolithic sites of Northern Baluchistan and Sistan have made us familiar. As seen in the specimens J D 1 12, 19 (P I III) we meet here with hachured leaf shapes, pairs of triangles meeting at the apex concentric squares, feathered bands all motifs which have their parallel at those early prehistoric sites.

Painted grey pottery of early type—But still more interesting is the abundance at Jai damb of fragments of a fine grey ware either painted or plain. They forcibly recalled to me the closely similar but far rarer pieces of such ware I had found at Pernan ghundai and at some of the prehistoric Sistan sites<sup>2</sup>. There the few painted pieces of this kind all belonged to flat dishes or open bowls and showed their designs along the rim on the inside. The fact that this is the case also with many of the Jai damb fragments of this type (see J D 13 15 17 18 Pl III for specimens) makes the connexion particularly striking. Characteristic of the Jai damb painted grey ware is also greater freedom in the scroll designs when applied on the inside. Other patterns on such ware as seen in J D 14 16 20 (Pl III) fall more closely into line with the geometrical designs of the red or buff painted pottery from this mound.

Occupation of Jai damb—Fragments of this grey ware were particularly frequent at the western foot of the mound. There a rough entrenchment made in the time of the Sar Parom headman's father had caused the soil outside the mound proper to be disturbed. This seems to point to pottery of this kind belonging to the earlier debris strata of the site. Neither ribbed nor glazed fragments were found which suggests that the mound was left unoccupied during historical times until it was turned into a place of refuge a century or two ago by the erection of the rough circumvallation on its top. Within this enclosure there is found an undoubtedly ancient well lined with large flat slabs of sandstone which evidently had been brought from the hill range to the south. The well measures 26 inches by 19 at its mouth and was measured to a depth of 40 feet. It is said to have been cleared by the present headman's grandfather and to have then yielded water for a while. It has been dry since for many years.

Mound of Sar Parom—The Makran Levy Corps post of Sar Parom was reached some two and a half miles further to the west. It had been moved to this advanced position from Diz Parom several years ago for the sake of offering better protection against cattle raiding operations from across the border. Attempts at such were said to be still frequent owing to the lawless conditions prevailing in Persian Makran. The name Sar Parom (head of Parom) is applied in general to this westernmost portion of the basin. After what I had seen at Gar I was not surprised to find that the newly established post also occupied the top of an ancient mound. This mound originally known as *Kuruzkol* could scarcely have been much higher than that of Jai damb before the entrenchment and mat-covered dug-outs constructed for the Levy detachment had changed the appearance of its top. Its diameter may have been about 50 or 60 yards. As the mound stands on a tongue of rising ground the outlook from the post is fairly wide. The painted pottery found both red and grey ware of the types there described being well represented (see SP 15 and SP 67 Pl III for specimens of the two types respectively).

<sup>2</sup> See *J. Baluchistan Tour* pp 34 35. 4 sq Pl. V. *Innermost As a*, p pp 657 sqq.

Peculiar to this site are some pieces like SP 8 showing decoration with a series of fine incised streaks. Of special interest is a small fragment from the rim of a stone cup (SP 9) evidently turned on the wheel. For finds of such small vessels mostly of alabaster are frequent at chalcolithic sites from Sistan to Zhob.

**Wutaki-damb**—From Sar Parom I visited the same day the mound known as *Wutaki-damb* and situated about  $1\frac{1}{2}$  miles to the north west. It has a diameter of about 60 yards and a height of 10 feet or so in the centre. Here fragments of glazed ware showing decorative designs, mostly black or brown over a green or white ground, were picked up in plenty on the surface. Occupation down to mediæval times is thus proved. But a few pieces of the previously described grey ware including a painted fragment from the rim of a bowl suggest that the formation of the mound started from a prehistoric period.

**Mound of Shami damb**—On New Year's day a ride of about 9 miles took me with a Levy escort to the mound known as *Sham damb*. It is situated in the middle of the wide peneplain furrowed in places by shallow flood beds which extends westwards of the head of the Kap right away to the watershed marking the Persian border. Only at a few points did I notice traces of abandoned Khushkaba fields though the ground with its good soil and easy slope seemed well adapted for cultivation in years of adequate rain fall. The mound of Shami damb rises within a pottery strewn area which measures over 200 yards in diameter to a height of about 15 feet. Its top measures from 30 to 40 yards across. Two pits dug at its north east foot one of which looked recent are evidently due to treasure seeking operations.

**Painted pottery**—The plentiful painted pottery found both on the mound and around it shows considerable variety both in the colour of the material red buff brown or a yellowish cream and in the colouring of the designs. These are executed directly on the ground in different shades of brown less frequently in black or purple. A characteristic feature is the appearance of dark pink or red as an additional colour as in Sh D 16 (Pl III). The patterns as shown by the specimens in Pl III are mainly geometrical. Parallel bands divided by vandykes or baluster like lines (Sh D 267) are very common. So also are rather coarsely executed scrolls and volutes (Sh D 1848). In two fragments we find animal figures introduced in Sh D 6 what seems to be intended for a horse and in Sh D 9 a badly faded piece a large bird with raised wings. All the painted decoration can be paralleled from sites undoubtedly prehistoric. But it deserves to be noted that the incised ornament of the raised band Sh D 10 might well be later and so also a fragment of what seems to have been a handle with mouldings. Of glazed ware only a single fragment from a pot in cerise blue was found. Not a single potsherd showing ribbing was seen. But four pieces belonging to the rim and shoulder of a bowl, Sh D 11 worked in fine clay show decoration with burnished lines such as in Sistan occurs in pottery from early historical sites.

Return to Panjgur—My ride that day was extended across the open divide for another three miles up to the undemarcated Persian border. But no other mound could be sighted either on this side or on the flat ground continuing beyond. The motor lorries had rejoined us at Sir Parom by the track from Diz Parom leading up the Kap and enabled us by January 2nd to regain Panjgur where a depot of all spare baggage had been left. The ground adjoining the main portion of the Kap to the north east and south consists almost throughout of low rocky knolls and eroded ridges. This together with the scanty drainage from the low hills on those sides explains why no cultivation on any scale can ever have been practicable on those shores of the dried up marsh bed. Nor were any traces of former settled occupation met with after leaving the Parom basin until approaching Panjgur we passed the Koha kalat site already described.

## CHAPTER IV.—IN THE KĪJ VALLEY AND DASHT

### SECTION I.—FIRST STAY AT TURBAT

Across the Central Makran Range—After my return to Panjgur on January 2nd camel transport was arranged overnight to carry such *impediments* including excavation implements for a hundred labourers as could not be taken by the lorries over the difficult route ahead to Turbat. Next morning we started for this the chief place and administrative centre of Makran. That day's drive of 90 miles carried us right across the Central Makran Range to Hoshab in the Kij valley. That it took our Dodge lorries fully ten hours to accomplish it safely may serve to indicate the difficulties of the trip. All the way we met only a single human being in the person of a camel rider employed on the postal service from Turbat to Panjgur. This sufficiently shows how little this wide belt of deeply eroded hill chains and winding narrow gorges has to offer even for nomadic existence. Before crossing by the Katag pass the last chain of hills overlooking the Kij valley we traversed another wide Kap, that of the drainageless basin of Balgattir for fully 13 miles. Fortunately the bare level plain was quite dry at the time such rain as came down six days later made it then impassable for weeks both to cars and camels. No remains of antiquity could be looked for on such ground.

Journey along Kij river—On January 4th we completed the journey to Turbat by a drive of 60 miles along the Kij valley. After crossing the Kij river bed some ten miles below Hoshab the track keeps on the glacis high above the left bank and thus far away from Sami Hirok and Shahnag the only two permanent villages which the Kij valley holds above Turbat. Wide and open as the ground is on the left bank sloping up gently towards the range to the south yet it could never have seen any cultivation for the torrents descending from the hills have all cut their courses far too deep into the stony glacis to afford any chance for inundation canals or Karezes.

Stay at Turbat—At Turbat I was kept busy for six days by collecting whatever local information could be secured about old remains in the main tracts of Makran by rapid surveys of those which were within reach of the Turbat oasis and by careful arrangements for the long tour which was to take me further south to the Dasht tract and the Arabian Sea coast. In all these tasks as well as in my subsequent explorations within Makran I received most willing and effective help from Muhammad Yaqub Khan the Naib Wazir of Makran and Mustafa Muhammad Hassan, his Deputy. Much useful local information was made available to me also by Sirdar Bai Khan, the local head of the Gichki family once ruling Turbat and the neighbouring tract and still holding most of the land, as well as by Muhammad Khan his active young nephew employed under the Assistant Political Agent. A fortunate chance had just at this time brought also Lieutenant L. W. Wooldridge, Adjutant of the Makran Levy Corps to the vicinity of Turbat. The arrangements for needful escorts and other help from the Corps greatly benefited by the presence on the spot of this energetic young officer.

Importance of Turbat oasis—A narrow strip of fertile irrigated land, comprising a practically unbroken string of villages mostly small stretches on both banks of the Kej river for a total distance of about seven miles both above and below the fort and headquarters of Turbat. This oasis appears to have since early times formed an important if not the chief centre of population in Makran. Hence we find the name *Kej* which applies in particular to it and the neighbouring smaller oases included in the mediæval designation *Kej Malran* used for the whole country.<sup>1</sup> The oasis now usually known as *Turbat* after its chief village owes this importance not merely to its economic resources being greater than those of any other tract in Makran but perhaps equally also to its convenient central position on the great natural highway which the Kej valley provides through the country.

Conditions of occupation—The local conditions affecting the survival of ancient remains on this ground closely correspond to those which I have endeavoured briefly to indicate above in the case of Panjgur. In the Turbat oasis too cultivation is carried on exclusively with the help of permanent irrigation which the numerous Karezes and canals (*Jaur jo*) from the river assure. Hence here also the cultivators' homesteads nowadays mostly palm mat huts are much scattered. Each is placed as close as possible to the owner's or tenant's own intensively cultivated small patch of land with its date palms which provide the principal crop. There is no reason to suppose that these conditions of occupation were essentially different during earlier periods. If in addition we take due account of the amount of alluvium annually deposited by canal irrigation from the river it becomes easy to understand why the number of localities where ancient remains can be traced above the ground is so limited.

Preliminary examination of sites—During my first stay at Turbat I visited every place within or near the oasis where 'dams' or other remains

<sup>1</sup> See above p. 9.

<sup>2</sup> See above pp. 17-19.

were reported. At two points my preliminary survey enabled me to recognize sites which deserved to be investigated by means of at least partial excavation. Various considerations induced me to postpone this task until my return from the coast a month later. It will hence be convenient to leave the description of the results which attended our subsequent labours at the mound of *Shahr-i-tump* and at the early burial ground of *Zangun* to a later chapter. Here it will suffice to note that at both places excavation has confirmed the diagnosis I arrived at after a rapid examination of the remains traceable on the surface.

**Castle of Miri.**—Among the remaining sites that of the ruined castle known by the generic designation of *Miri* ('the ruler's place'), was certainly the most interesting. It was visited by me twice, on January 5th and 8th, and only the pressure of other urgent tasks prevented my devoting to it the time which a detailed survey of this great ruined stronghold would have claimed. It rises about half a mile from the right bank of the river at a direct distance of close on five miles to the north west of the village and fort of Turbat. The ground around had long remained untilled in modern times, but a newly constructed *Karez* has once more brought to it water for irrigation, and fields now reach to the very foot of the *Miri*.

**Outer circumvallation.**—It is an imposing pile, as shown by the photographs reproduced in Figs 9-10. It has been built up by the efforts of successive rulers of Makran to an elevation of about 120 feet at its highest point. The castle appears to have been occupied until late in the last century, the inner fort being held by the Khan of Kalat's officials and garrison while some structures less ruinous than the rest in the eastern portion of an outer enclosure, were allotted to the *Guchki Sirdars*. These continued to share in the revenue from the Kol valley even after their submission to British rule. This outer circumvallation adjoins the inner fort on all sides except on the south and shows a length of about 300 yards between the massive corner bastions which flank its northern face. Its western face measures only a little over 100 yards while on the east the width of the enclosed area is somewhat increased. That the whole circumvallation is raised on an ancient debris mound can best be seen along the northern face. There the foot of the ruined clay walls rests on a level about 30 feet above that of the surrounding fields. The same is approximately also the level on which most of the structures within showing varied stages of decay appear to have been built.

**Substructure of inner fort.**—The natural slope of the ancient debris mound which underlies the greatest portion if not the whole of the outer-walled-in area strikingly contrasts with the steepness of the massive substructure on which the long but narrow inner fort is built. This substructure as seen in Fig. 10 showing the south face appears up to a height of about 50 feet to consist of solid stamped clay or mud brick masonry. Where it has suffered by erosion its breaches have been repaired with rough stone work. In the walls higher up courses of large waterworn stones set at slant intervene with sun-dried brick work. The latter method of construction has alone been used for the towers and walls of the inner fort. The former is still frequently found in modern structures of Makran and Kalat defensive



R O N U O T U R



O C O





or other. The gates of both the outer circumvallation and the inner fort lie towards the south east. Within the gate of the inner fort a long and deep cutting of which the origin or purpose is not clear has laid bare layers of clay or rubble to a depth of some 15 feet. In this cutting was found a potsherd with 'ribbing

Fragments of prehistoric pottery.—But far more significant for the early occupation of the site is the number of small fragments of pottery of undoubtedly prehistoric type both plain and painted which could be picked up even in the course of a rapid search not only outside and within the lower circumvallation but also on the ground within the inner fort. They comprise little pieces of fine red ware with simple geometrical patterns in black just like the pottery found at prehistoric sites from Topi damb to Parom and also specimens of the same grey ware with designs executed in black or purple as found so plentifully at the mounds of Jai damb and Shama damb and described in the preceding section.<sup>3</sup> The discovery of fragments of such early painted pottery high up on the slopes and top of the inner fort is accounted for by their having got embedded in the sun-dried bricks and clay brought up from the very foot of the mound on which the whole Miri is built. Evidence for this explanation was supplied by little pieces of such ware which we could pick out from the sun-dried brick masonry of walls still standing on the top of the inner fort. It is very probable that these bricks were made just outside the outer circumvallation. This obviously was the nearest and most convenient place to secure both material and water for brick-making especially if tradition is right in asserting that a fosse once surrounded the castle. I could not find definite proof of this fosse beyond a broad depression which runs along the foot of the northern face of the outer circumvallation and connects with the line of an abandoned Karez near its north east corner.

Evidence of later occupation.—Apart from the pottery just referred to striking evidence of prehistoric occupation of the site is furnished by two fragments of neatly worked stone cups, one of them alabaster which were found within the outer enclosure. The use of such lathe-turned cups and bowls is abundantly attested at neolithic and chalcolithic sites of Sistan and Baluchistan.<sup>4</sup> To the same early stratum belongs perhaps also the fragment of a black glass bangle. In addition to such early relics pieces of glazed pottery of all kinds ranging from apparently early mediaeval Persian ware to Chinese porcelain, could be collected in still greater numbers from the precincts of the Miri. There is every reason to believe that as erosion in the course of centuries proceeds at the ruined castle it will become still easier for future archaeological visitors to trace on the surface vestiges of the long history of the site. But the very extent of it and the heavy accumulation of late structural remains overlying the prehistoric strata precluded my sparing time here for trial excavations. This seemed to cause some mild surprise to my local Ghehki friends and to others for they were fully convinced that my visits to dams, etc. could only be prompted by treasure-

<sup>3</sup> See Pl. IV for specimens of red pottery T. M. 1-9 for grey painted ware T. M. 3-4 for glazed pottery (blue on white) T. M. 5-6 for blue on white stoneware (Chinese?) T. M. 5 for a piece of fine red pottery showing incised and hatched lines, T. M. 7.

<sup>4</sup> Cf. *Indian Antiquary* 1881 pp. 931-951 etc. & *Baluchistan* pp. 3-33-40 below pp. 63-64 etc.

seeking arms. They hence expected that the hidden hoardings of their ancestors would here be bound to offer me the very strongest attraction.

Smaller sites near Turbat—About two miles west of the Political Bungalow at Turbat I was shown a fairly large 'damb' on the gravel slope just south of the village of Gushtang. The mound rises to about 20 feet in the middle and measures about 110 yards in diameter. The few painted potsherds which could be found on it amidst coarse plain ware showed poorly executed designs which looked of late prehistoric type such as found subsequently at the head of the Mashkai valley and previously on mounds about Pishin.

Some 'dams' were reported to me in the vicinity of Kalatuk, a village situated near the right bank of the river about 11 miles from Turbat. They proved to be a group of about eleven small stone heaps roughly circular in shape stretching in an irregular line along a shallow drainage bed which descends over the stony glaciis about a mile east of Kalatuk. They are from 3 to 4 feet in height and measure between 10 and 15 feet in diameter. Those which could be opened with the few men at hand contained within only loose stones large and small. But there can be little doubt that they were meant for burial mounds like the numerous less roughly constructed tumuli which I subsequently was able to explore with more interesting results at Jiwanm on the coast and at Langian the previously mentioned site to the south of Turbat.<sup>5</sup> This conclusion was fully confirmed by the finds made within exactly corresponding little tumuli which I was able on my return from the coast a month later to clear on the same stony glaciis some 12 miles further west near Nasirabad.<sup>6</sup> Here I may conveniently mention that similar groups of tumuli were reported to exist near Bit in the valley of Buleda to the north of Turbat which want of time did not allow me to visit on my return as originally intended.

## SECTION II—ALONG THE DASHT VALLEY

By January 10th the camels bringing our heavy baggage from Panjgūr safely arrived and on the following morning we could set out with all needful equipment for the tour which was to take me down the Dasht valley and to the westernmost sea coast of British Malian. Its principal object was to acquaint me with certain ancient sites in that area which Major L. Mockler, for years stationed as Political Assistant at Gwadar, had visited and briefly described.<sup>1</sup> The first of these sites to be surveyed was that of Suktagan-dor near Suntsar. There the Dasht river formed by the union of the Kej and Nihing passes the last offshoot of the Maliran Coastal Range before entering the head of its delta. Route to Dasht valley—In order to reach this site the caravan track had to be followed which leads lower down along the left bank of the Dasht river and connects Turbat with the small ports of Gwadar and Jiwanm. It is practicable only for

<sup>5</sup> Cf. below pp. 77 seq. 86 seq.

<sup>6</sup> See below p. 8.

<sup>1</sup> For a reference to these tumuli of Hughes-Buller *Maliran (a letter)* p. 303. See his note 'On Ruins in Maliran' *J. R. A. S.* 187 pp. 121, 134.

laden animals but for the first march which lies through low and much broken hills to the south of the Kej valley a newly constructed motor track was available. So in order to save time and to use it for correspondence by the mail which leaves Makran only every second week by the sea route I sent our transport and mounted Levy escort ahead intending to catch them up by motor at the first camp. The arrangement reasonable enough except for its disregard of a change due to Makran's peculiar climatic conditions brought a somewhat trying experience in its train. This had a certain quasi antiquarian interest and may therefore fitly find here mention.

Overtaken by spate—Rain rare as it is in Makran is apt to come on suddenly and then very heavily for a short time. But when it started that day several hours after the camels with the baggage had moved off it was but an intermittent slight drizzle. This sufficed to make the track leading over clay and detritus rather heavy going for our motor lorries but there was no choice but to overtake the convoy. We had covered some six miles only and entered a wide floodbed coming from the low hills to the south and still practically dry but for the wetted surface when one of the lorries stuck in a small drainage channel holding only a trickle of water. While efforts strenuous but vain were made to lift the stuck hind wheel out of the little pool gathering around it the drizzle started afresh. Before it had time to turn into proper rain water was rapidly spreading around us and soon across the wide detritus fan too. I realized in time the threatening spate and had what little baggage was with us carried first to the bank of the floodbed and when that too became submerged to a small ridge of crumbling rock very steep and narrow which fortunately rose close by above the soft detritus.

Thoroughly drenched already before we had to seek refuge by crouching on this awkward rocky perch for over two hours in the rain. Then the flood all around began to subside even more rapidly than it had risen. It had topped the body of the lorries and covered the engines with silt. As the deep cut floodbed of the Sorab behind us remained unpassable the help early summoned from Turbat could not reach us until late next morning. Fortunately the sky became perfectly clear by the evening and what with the blazing tamarisk scrub which we managed to set on fire and the help of what bedding was with us in the lorries the cold night under the starlit sky was passed without too much discomfort for any one of the party—though it meant also a fast till next evening. By 11 A.M. the lorries were dragged out of the boggy bed with the help of a large posse of men who by then had arrived from Turbat and who were to manhandle them back there. With the baggage loaded on two camels we set out on foot for the camp ahead and before dusk gained its shelter at a water hole above the mouth of the Kim valley.

Incident on Alexander's march—The experience here gained may well serve to illustrate a far more serious incident which Arrian relates in connexion with Alexander's march through the country of the Gadrosians.

<sup>2</sup> Cf. Arrian *Anabasis* VI. xxv. I reproduce this extract as translated by McCrindle *Journales of Alexander*, p. 175.

Another disaster also befell the army which seriously affected the men themselves as well as the horses and the beasts of burden. For the country of the Gadrosians like that of the Indians is supplied with rains by the Etesian winds but these rains do not fall on the Gadrosian plains but on the mountains to which the clouds are carried by the wind where they dissolve in rain without passing over the crests of the mountains. When the army on one occasion lay encamped for the night near a small winter torrent for the sake of its water the torrent which passes that way about the second watch of the night became swollen by rains which had fallen unperceived by the army and came rushing down with so great a deluge that it destroyed most of the women and children of the camp followers and swept away all the royal baggage and whatever beasts of burden were still left. The soldiers themselves after a hard struggle barely escaped with their lives and a portion only of their weapons. Spates of this kind and volume are known to descend into the valleys of Makran even while the sky above keeps clear. This fully confirms the correctness of the record preserved by Arrian.

Remains of Haft brat—A march of some 28 miles lengthened by detours which the flooded condition of the alluvial plain necessitated in places carried us on January 13th down the main eastern portion of the Dasht valley. Where the barren side valley of Kani is joined by another before debouching into the plain the track passes curious remains known as *Haft brat* the Seven Brothers. There below a rocky ridge there stretch in a row thirteen walled enclosures adjoining like rooms. The average size of each is about 25 feet square diminishing slightly towards the eastern foot of the ridge. The lines of large unbewn stones looking as if meant for wall foundations can clearly be traced but no remains of walls rise above them. No potsherds or other helpful indications could be found near these strange enclosures and their purpose remains obscure.\*

Cultivation in Dasht—On the bare alluvial flat which stretches with a width up to 7.8 miles away to the right bank of the river patches of cultivation dependent on rainfall are met but no permanent settlements. What flood water descends to the plain from the hill range to the south is caught by low earth embankments around these Khushkaba patches. It is certain that with a less scanty and more settled population these scattered dry crop areas could be considerably increased here. But from my intelligent and helpful local guides the Naib and headman of the Dasht tract I did not learn of remains due to continued occupation in earlier times at any place but the village of *Kuddan* which was reached at the close of the day's march. It is situated at the point where the foot hills of the boldly serrated Sindh range first meet the Dasht river's course. On the opposite side of the river it is faced by the little fort of Kohak the administrative centre of Dasht some four miles away. So with its forty odd mat-huts Kuddan ranks high among the few more or less permanently inhabited localities of the tract. It owes this distinction to the possession of land within the low lying belt of ground which in years of good floods is rendered very fertile by inundation from the river.

\* Cf. below p. 137 for a larger account.

**Mound near Kuddan**—It is just above a portion of this land at about a mile's distance to the south west of the village that there rises a much eroded mound separating the cultivated low ground from the glacia of hard clayey soil sloping up to the foot of the hills. The mound known as *Maelaka* rises to about 12 feet above this glacia of *pat* and stretches for about 200 yards from east to west with an average width of 150 yards. It is on all sides deeply furrowed by eroded ravines and these made it easy to ascertain that the pottery debris very plentiful on the mound is more or less homogenous throughout its layers. Most of it is plain red ware of coarse fabric easily distinguished from the well levigated smooth surfaced pottery common at prehistoric sites such as Suktagen due to be presently described. But the examination of the decorated potsherds also numerous proved distinctly interesting.

**Glazed and painted pottery**—It is scarcely subject to doubt that the plentiful glazed fragments with well executed coloured designs mostly in greens and browns over light yellow or whitish ground as seen in the specimens of Pl IV Kud 5 7 9 11 belong to mediaeval times. But other glazed pieces showing a fine dark blue or deep green glaze without ornamentation may be somewhat older. Mediaeval is probably also the fragment Kud 8 with a rather elaborate geometrical pattern stamped in relief. It is significant to find painted ware of the type illustrated by the specimens Kud 1-4 10 associated with the glazed pottery for with the coarse brushwork of its patterns and the use of red and brown colours in addition to black it ranges itself closely with a type of painted ware from mounds in Loralai and Pishin which in the report on my North Baluchistan tour I found good reason to ascribe to the historical period. It deserves to be noted that not a single specimen of prehistoric painted ware whether red or grey nor of ribbed pottery could be found here.

**Mound of Panodi**—Here another and undoubtedly much older site in this portion of the Dasht may find convenient mention. It was only after passing Kuddan that information was obtained by me of a *damb* near the hamlet of *Panodi* situated on the other side of the river about seven miles to the north east of Kohal. It would have been impossible to visit the place at the time as the river was impassable for camels owing to the flood caused by rain above the *haz* valley. The specimens of painted potsherds which the Nib of Dasht promised to secure for me unfortunately did not reach me until my return to Turbat for otherwise I should have endeavoured on my return journey from the coast to find time for inspecting this mound. The painted potsherds brought from there as illustrated by the specimens Pan 1 5 in Pl IV, all show geometrical patterns of prehistoric type. They are executed in black or brown on fine well levigated clay either light buff or grey without any slip. Pan 4 is an interesting piece for it shows above a grey body a band of reddish clay either superimposed or due to some peculiarity of burning by the side of a pattern in black painted on the grey clay. From Panodi there was brought also a potsherd with mat-marking. This agrees with the early age assignable to the site.

<sup>1</sup> See *N. Baluchistan Tour* pp 67 299 6. 1 sq 81 sq etc

March to Suntsar.—Our march of January 14th close on 30 miles in length led for most of the way through a maze of completely decayed hillocks forming the foot of the frowning steep rock walls of the Sajidi range towards the river bed. Only at one or two points above the latter does that desolation of crumbling sandstone leave room for some fields while for the most part the river passes under high eroded cliffs. From the little temporary hamlet of Hor Nighwor where we halted for the night another long march brought us to Suntsar a guard and customs post of the Kōlat State watching the caravan tracks passing up the Dasht from the coast. That day much of the way lay between low decomposed ridges last outliers of the Sajidi range and often eroded almost to the flat level of the surrounding detritus. But in several of the intervening ravines passed I noticed patches of cultivation now for the most part abandoned to scrubby jungle. Beyond the rocky hill crowned by the Suntsar watch post the western extremity of the Sajidi range breaks up into a confused cluster of small serrated ridges and plateaus extending along the left bank of the Dasht river. We crossed the deeply scoured bed of the Sajidi kaur which drains a considerable portion of the southern slopes of the range and here has cut its way to the river and halted near the point where two lines of the Indo-European Telegraph one from the Persian Gulf the other from Panjgur and Turbat meet. Next morning after winding our way for about three miles through low rocky spurs we emerged by the river at our goal the site of Suktagan dor.

### SECTION III.—THE REMAINS OF SUKTAGAN DOR

The merit of having first recognized the archaeological interest of the site of *Suktagan dor* belongs to Major E. Mockler. Having passed it in 1875 and noticed remains of a brick wall exposed by the diarrage he carried out *some* excavations at and near this spot in February of the following year and published brief notes on the result and the main features of the site.<sup>1</sup> These are correctly described on the whole and an endeavour has been made to indicate the character of the structural remains exposed as well as that of the objects found. But in the absence of relevant details and any illustrative materials apart from a small sketch intended to show the general aspect of the site from the east it would not be possible to conclude more from these notes than that the remains probably went back to chalcolithic times. The want of any plan coupled with discrepancies between the recorded bearings and the configuration of the ground would not allow me when actually on the ground to locate the position where Major Mockler's excavations had been carried out especially as the ravages of half a century and local depredations appeared to have effaced whatever remains exposed might have afforded guidance.

Major Mockler's excavation.—Thus of the burnt bricks with which the walls of a small house first cleared by Major Mockler were built not a single one

<sup>1</sup> See *J. R. A. S.* 1877 pp. 12, 6.  
<sup>2</sup> Cf. *ibid.* p. 12.

could be found anywhere. But when returning later from the coast and passing to the north of the site on the opposite bank of the river I found that a number of graves in a modern Muhammadan graveyard not far from the present Levy post of Santar were lined with hard bricks undoubtedly ancient. As their measurements  $16 \times 6 \times 2\frac{1}{2}$  inches closely agree with the dimensions recorded in Major Mockler's paper it is very probable that they had been carried away from the brick built structure he had excavated. Others may have found their way into the foundations of some store huts and linesmen's quarters built at the Indo-European Telegraph post above mentioned. It is probable that the much disturbed ground of some low mounds to the east of the great walled enclosure of Suktagen dor marks the place where Major Mockler's excavations appear to have been carried into an ancient burial ground<sup>3</sup>. But here too no definite evidence in support of this location could be traced.

In view of these uncertainties I shall not attempt here any systematic analysis of Major Mockler's observations but only refer to them where they have found confirmation by the work I was myself able to carry out at the site. This work was necessarily limited on the one hand by regard for the available time and on the other by the small number of men it was found possible to collect for excavation. It was only by persistent efforts of my local helpers that in the course of my week's stay it was gradually raised in the end from 16 to 34 feet from efficient diggers.

**Position of Suktagen dor**—The site of Suktagen dor presents the appearance of a low rocky plateau rising in the middle of a bay about half a mile across which the alluvial flat adjoining the course of the Dasht river extends towards the chain of broken hills to the south. This bay like the riverine belt itself is covered for the most part with scrub and tree growth (Figs 16 16). Small patches of the little plain are used for Khushkaba cultivation while elsewhere its level surface is broken by little decomposed ridges cropping out from the alluvial deposit of fine clay. Closer inspection shows that the isolated plateau represents in reality a group of more or less detached small ridges which are joined up on the east and west by massive stone embankments and thus made to enclose in the middle a little plateau raised above the level of the surrounding plain. The reddish surface of this plateau due to abundant pottery debris has given the site its name (the burned bed). Reference to the sketch plan Pl. 4 and Figs 11 14 will help to illustrate the configuration of the ground.

**Configuration of ground**—The area of ancient occupation thus comprises in its centre two much decayed ridges of soft grey sandstone striking approximately from east to west and both rising at their highest points to 60 feet above the flat ground around. Two almost straight lines of thick wall and debris running north to south one over 100 yards the other 130 yards long connect these ridges at their ends. Together with the steep rock slopes of the ridges they form an irregular quadrangle capable of effective defence. The south western portion of the enclosed area shows an almost level surface (Fig 13) obviously due

<sup>3</sup>Cf. p. 67 & 120 q



to silt deposit from the slopes of the ridges around. All the drainage passes at the south west corner where the very massive foundations of what may have been two towers 8 feet apart clearly mark a gate. Below this a drainage bed (Fig 17) encumbered with large stones probably from completely decayed structures on either side runs down to the plain in the south. It is flanked by two small spurs which descend from the southern side of the enclosed area. The one to the east forms several small terraces along its top and wall foundations traceable on there as well as right down to the Nullah show that this spur was once closely occupied by structures. Also on the inner slope of the western outlier remains of walls crop out of the debris. It deserves to be noted that the eastern spur is protected by the steep rock wall with which it falls off on the outside towards the plain.


Remains N and E of enclosure.—The slope descending outside from the northern ridge also offers terrace like ground, and on this structural remains could be traced apart from plentiful pottery. On the other hand the western outlier of that ridge appears to have remained wholly unoccupied nor could I find any traces of ancient occupation outside the western wall of the enclosed quadrangle. From the north eastern corner of the quadrangle a massive wall runs along the slope of the north ridge for about 50 yards to a point where the ridge rises steeper and from this wall there descends a less thick one due north as if meant to afford some flanking defence to the outer slopes of the north ridge. Outside the eastern face of the enclosed area there extends at some distance from the foot of the massive embankment or wall a strip of ground 60 or 70 yards wide, covered with hummocks of debris marking ancient occupation. Whatever structural remains may have stood here they all appeared to have been greatly disturbed by previous diggings. Erosion too had added much to the havoc. The foundations of rough stone walls apparently of small structures however, still showed in places.

Enclosing stone walls.—The most striking feature of the ruined site is the great stone wall over 110 yards long already referred to which forms the eastern side of the quadrangle (Fig 16). Its outer face is in most parts encumbered with debris. But a little clearing sufficed to expose in places the fairly regular courses of large stone slabs carefully set with but little clay between the courses. That the slabs were roughly squared in most cases was ascertained when digging down from the top on the inside. Here the wall was built up vertical while its outside face seemed to slant at the steep angle of about 40 degrees. At its base the wall appears to have a thickness of fully 30 feet, while its height as far as preserved varies from 20 to 25 feet. The northern continuation of this wall shows the same massive construction. The wall closing the quadrangle on the west has suffered far more decay, and owing to the heavy accumulations of alluvial dust the position of its foot outside could not be exactly determined. But it seemed probable that the dimensions and methods of construction were about the same as of the east wall.

Modern defences.—There can scarcely be any doubt about these walls having been built for the purpose of rendering the area between the northern and southern




G N U S O P O D R S U T A O U T N G



O O U S U T O O O O B V



N O U D R



O S O D O



ridges safe for occupation and capable of defence. Direct evidence of their having served this purpose in a recent period is afforded by the thin walls of manifestly modern date built with small stones and in the roughest fashion, which crown both the northern and southern ridges (see for the latter Fig 14). In addition towers of the usual *sangar* type now in ruins have been raised on the highest points at the four ends of the ridges.<sup>4</sup> The evident object was to supplement the defences provided by the ancient wall lines and the natural steepness of the ridges. This modern fortification makes it all the more noteworthy that no trace of ancient walls can be found either on the northern or on the southern ridge. This negative fact obviously calls for an explanation. The only one necessarily quite conjectural which has occurred to me lies in the great change which since prehistoric times has come over the means for attack. Defenders of the fortified area of Suktagēn dōr in the last few centuries would have had to protect themselves against firearms by walls and towers however rough. In ancient times the height of these ridges and the great abruptness of their outer slopes may have been thought to afford adequate security from attack.

Miscellaneous surface finds.—Before I proceed to describe the results of such trial excavations as I was able to carry out during my stay (January 16-21) at Suktagēn dōr it will be convenient to give an account of the various classes of the miscellaneous objects which erosion has exposed on the surface and which could be collected in quantities. A review of them, even if summary will help to bring out the remarkable uniformity in the character of these relics pointing to a single if prolonged period of occupation. It will also help to demonstrate the close relation of the civilization revealed by them with that of chalcolithic sites in far off parts of northern Baluchistan for which I have been led in the course of my preceding explorations to assume a particularly early age.

Objects in stone shell etc.—With regard to the last point the great abundance of small stone implements found over all parts of the site deserves, perhaps, to be mentioned in the first place. Of stone 'blades' or scrapers not less than 127 were picked up on the surface almost all showing marks of prolonged use. Most of them are of small sizes but there are specimens too ranging up to 4½ inches (Su 14 Pl VI). It is significant that not a single piece definitely recognizable as a chipped core was found. This clearly points to these small implements not having been worked on the spot. Of arrowheads Su 5 leaf shaped and perfectly worked in flint is a fine specimen. Fragments of stone vessels, also turned up including a portion of an elegantly shaped alabaster bowl Su 23 Pl VII. Fragments of bangles cut from shells are very numerous (Su 69 Pl VI) as might be expected considering the close vicinity of the sea coast. Fragments of shells with simple incised ornament occur also (Su 10 Pl VI). Among beads in stone a finely worked elongated bead of Onyx (Su 12 Pl VI) may be mentioned. The fragment of an elaborately decorated glass bangle, Su 12a (Pl VI) is interesting. It is composed of three layers (cobalt blue brown and

<sup>4</sup> These ruined towers occupy the points marked in the sketch plan Pl 4 with the height figures 60 40 60 and 47.

yellow) fused and has its keel decorated with a row of small raised light blue spots. Closely corresponding glass bangles were found by me on prehistoric mounds in the Sistan desert.<sup>6</sup>

**Plain pottery on surface**—Of ceramic products it is important to note first of all the extreme abundance of plain well levigated ware of light terracotta or reddish colour fragments of this strew the whole site. The thinness of the prevailing fabric seems characteristic of the local potters' craft. Often a fine slip of dark red colour is applied in bands (Su 20 Pl VI) or over one face of the pottery. The diminutive base found in some fragments of small bowls (Su 21 Pl VI) is a feature which has its exact counterpart among the bowls and jars of Perano ghindai.<sup>6</sup> The same holds good of the almost straight-shaped jar Su 22 (Pl VII). A curious little pottery object Su 35 might be a toy cup.

**Rare painted potsherds**—By the side of the abundance of superior plain ware the comparative rarity of painted potsherds is striking. The pieces Su 14 19 (Pl IV) illustrate practically all the simple geometrical motifs (parallel bands, hachures, leaf shapes and meanders) to be found. The designs are always executed in black and in the great majority of the fragments including Su 14 19 on a fine dark red slip. By itself stands the fragment Su 13 (Pl IV) which shows what may be taken for two symbols or characters unfortunately incomplete painted on a plain potsherd after burning. Of dark grey pottery so plentifully in Parom less than a dozen pieces could be found. All belong to little bowls or flat dishes only one small fragment showing remains of a pattern painted in black.

**Perforated pottery**—Of handles only a single ring shaped specimen (Su 24 Pl VI) of rather primitive form was found on the surface but excavation in Su 1 yielded two more attached to flat bowls. Of pottery incised with thin hachures like Su 25 (Pl VII) several pieces were found. Su 26 (Pl VII) is of interest as it shows neatly executed decoration in relief with narrow parallel ridges quite distinct from the later ribbing. Very puzzling for a time were pieces such as Su 27 8 (Pl VII) perforated all over with rows of small holes. Similar fragments all apparently from jars large and small were subsequently found at several prehistoric sites of Kej and Mashkar. The discovery of a complete large jar of this kind filled with charcoal at an Awaran mound<sup>8</sup> makes it appear highly probable that these vessels served for heating or warming food.

**Clay bangles copper fragments**—Fragments of red clay bangles (for specimens see Su 29 30 Pl VI) were very numerous just as at the chalcolithic sites of North Baluchistan and of all sizes. The half dozen fragments of grey clay bangles (Su 32 3 Pl VI) were all much thicker. Of miscellaneous surface finds there still remain to be mentioned many small fragments of copper most of them indeterminate. But there is among them also a heavy barbed object (Su 34

Cl. *Inverness Asia* 2, pp. 963-967

<sup>6</sup> Cf. e.g. the small bowls and jars in *N. Baluchistan*. *Ten* Pl. VII  
Cl. *ibid.* Pl. VII P. 8 W. d. 2 Pl. XXI P. A 1

<sup>8</sup> See below p. 10

Pl VI) which perhaps may either be an arrowhead or a hook for catching large fish. It seems to have been worked in thin layers subsequently joined but the manner of attachment is not clear. There are also recognizable a small copper bead and fragments of needles.

**Finds in trenches a c**—The trial excavations were started on January 16th on a debris covered outter of the north ridge which descends near the north eastern corner of the ancient enclosure and within it. Three trenches marked a b c on the sketch plan were cut here and in a b carried down to the live rock struck at a depth from 8 to 9 feet. The cuttings passed everywhere through layers of earth and rubble deposits which in this position could be accounted for only as due to the decay of structures built with clay and rough stones on the rocky slope. The finds made here included half a dozen of stone blades or scrapers, numerous fragments of clay and shell bangles, the base of a small alabaster cup (Su 11 Pl VI) and among plentiful plain pots/benrds of the type described, fragments of a shallow bowl with handle (Su 12 Pl VII), a small bowl with diminutive foot (Su 13 Pl VII) and what seems to have been an elaborately moulded stand for a beaker or similar large vessel (Su 14 Pl V). Su 15 (Pl VII) is a specimen of covers for a small bowl or dish of which several were excavated here and elsewhere. Su 16 (Pl V) illustrates a type of broad edged flat dishes, fragments from different large sized specimens were found. There is evidence that in some cases such dishes were raised on high stands or bases. Su 17 (Pl V) is a piece from a large deep tray.

**Excavation on slope of N ridge**—Our next experimental clearing was made on a debris covered little plateau on the outer slope of the northern ridge near where the outline of a quadrangular enclosure could be traced on the surface (see n in the sketch plan). The walls of rough stone work brought to light on three sides of a space measuring about 40 by 25 feet stood to a height of 2 to 3 feet only and may have belonged to foundations. Among the broken pottery found here two small jars (Su 11 2 Pl VII) showing shapes familiar from the Chalcolithic mounds of Zhab. About 20 yards to the east of this structure a small square marked by slabs 2 feet 4 inches apart and exposed on the surface attracted attention. Under about a foot of earth there was found a large pot about 2 feet in diameter covered at its mouth by rough stones. Within there were found ashes, numerous small fragments of bones which seemed to be human, two broken small jars of the type just referred to together with fragments of thick plain pottery. That the pot contained a cinerary deposit after the fashion of those found at the Zhab and Localai sites appears very probable. But this could not be so definitely proved as in the case of the pots unearthed at Su v and to be presently mentioned.

Descending the small Nullah which divides the main northern ridge from the outter bearing the debris layers of n there were noticed traces of a wall running across the mouth of the Nullah. On clearing it was found to be 8 feet thick and to be built with carefully set large slabs extending from the massive masonry wall near the north eastern corner of the enclosed area to the rocky foot of the outter. From its massive construction this wall may be assumed to have

formed part of an outer enclosure. But as no continuation of it could be traced on the slope or top of the outer this explanation remains doubtful.

**Cinerary deposits cleared**—On the outer slope of the eastern wall and about 15 feet below the point where this wall adjoins the steep rocky slope of the hillock marking the south eastern corner of the enclosed area, erosion had exposed the mouths of three large pots in the position marked v in the sketch plan. The photograph reproduced in Fig 18 shows them after clearing. They had evidently been deposited in the debris accumulated at the foot of the wall. That they contained cinerary deposits was made probable from the first by their upright position, one above the other, as seen in the photograph, and by the fact that they had been intact when placed there. The uppermost deposit proved to consist of two pots, one stuck in the other. The outer one had become badly crushed and could not be measured. The inner one showed a maximum diameter of 23 inches, the height as far as preserved being 15 inches. Within were found numerous small fragments of human bones, unmistakably calcined, a small disc made from a shell and ornamented on its under surface (Su v a 1, Pl VI), a piece from a shell bangle, Su v a 2 (Pl VI), fragments of a small painted jar, ornamented with double black bands, and a complete small jar 4 inches in diameter, of rather friable clay, unpainted.

**Finds in cinerary pots**—The pot in the middle of the row, Su v b had its mouth crushed by a large flat stone which had once been placed to cover it and was now found within the cavity. The pot measured 29 inches across at its widest and had a height of over 31 inches. Amidst the earth filling it ashes and small fragments of calcined human bones were found throughout. Against the inside wall lay a jar of unpainted fine clay, Su v b 1 (Pl V), also containing ashes with a disproportionately small foot closely recalling small jars of the same shape found in cinerary pots of Pērāno ghundai. A small jar Su v b 3 (Pl VII) of identical type is of remarkably fine clay and bears a dark red slip, but no pattern. There was found inside also the fragment of what seems to have been the elongated foot or stand of a large dish or bowl (Su v b 2) resembling those found both at Pērāno ghundai and Dabar kōṭ. The lowest pot, Su v c, about 30 inches wide in the middle, had its side crushed in by the weight of the pot above it. Within there lay amidst ashes and calcined bone fragments the small jar Su v c 1 (Pl VII). A larger one lay at the bottom having a maximum width of 11 inches. It had suffered badly from crushing but its contents of ashes and bone fragments could be clearly made out.


**Burial customs**—The contents of all three pots as described make it quite certain that they had served for cinerary deposits. That these were put inside after the pots had been placed in the ground is obvious on comparing the thinness of the walls of the pots, only 6/16 of an inch on the average, with the great weight of the receptacles when filled. They could thus not have been carried without breaking. The proof here afforded of burial customs identical with those observed at Pērāno ghundai, Moghul ghundai and Dabar kōṭ is distinctly



1 1 No R - III 90R 2 DO 7 RO 4



0 7 5T LL SU T G N O TH VI OR R  
M<sub>2</sub> n of d



1 0 1 T P O T 5 AT 0



1 H OTS T O T 5 T 0





important as it confirms the quasi-chronological conclusions to be drawn from the general evidence discussed below <sup>10</sup>

Ground within walled area.—An examination of the ground within the walled area revealed in most places indications of ancient occupation in the shape of pottery debris and earth reddened by fire. But denudation combined with alluvium from the ridges around was bound to efface here all distinct traces of structures on the surface. At one point about 50 yards to the south east of a trial trench revealed shallow stone foundations about 3 feet thick for the walls of a small quadrangular structure. But as nothing was left of the walls themselves apart from burnt earth evidently due to a conflagration I preferred to turn the scanty available labour to the excavation of some structural remains by the side of the Nullah descending from the gate at the south western corner.

Dwelling cleared outside S. W. corner.—They were indicated by lines of stones exposed on the surface. Here at a distance of about 20 yards to the south west of the gate the small building Su iv a' was cleared as shown in the sketch plan Pl. 4. Its outer walls 2½ feet thick could be traced on the north and east for 25 and 20 feet respectively. They were built of sandstone slabs roughly set in the same fashion as in the great enclosing walls. They stood solid to a height of about 5 feet while the interior walls showed stone masonry only to a height of about 3 feet and above that what seemed to be mud bricks. Towards the west the surviving height of the walls decreased owing to the rise of the slope on which the building stood. That it was a dwelling is proved by the character of the numerous interesting small objects brought to light but what the special destination of the several little apartments within was could not be determined. In the passage 1 only 4 feet wide which runs outside the east and south walls of the room 2 three round stone drums were found roughly curved and placed against these walls. They measured 11 across and were 8 high <sup>11</sup>. There can be little doubt as to their having carried wooden posts. But why these should be needed just in this position is in view of the narrowness of the passage not clear.

Pottery jars and cups.—Among the finds made here the many jars and cups all plain may on account of their number receive first mention. As the specimens reproduced in Pl. V VII (Su iv a 1 2 5 8 12 13 20 24) show they are very varied in size and to some extent also in shape. Most of them in the latter respect resemble the jars and cups found at the Chalcolithic sites of Zhob (Periano ghundru and Moghul ghundai) and Sistan as a reference to the plates illustrating these will demonstrate <sup>12</sup>. Somewhat different is the jar Su iv a 12 (Pl. V) widely bulging

<sup>10</sup> It appears to me very probable that Major Moeller's description (*loc. cit.* p. 12a) of wide mouthed earthen pots about 10 and a half feet high filled with earth stones bones (occasionally charred) teeth charcoal and in one a small knife refers to exactly similar cinerary deposits. These are said to have been found within small oblong enclosures roughly built of stone on mounds at the foot of the eastern wall. Major Moeller calls them Behman the term applied by Baluch to any ancient structures.

<sup>11</sup> Three flat round stones of about the same size which Major Moeller found in a structure no longer traceable and which he took for pedestals of idols (*loc. cit.* p. 124) may have served a similar purpose.

<sup>12</sup> See A. Baluch *Tour Pl. VII VIII X. Inner and Outer* in Pl. CIV.

in the middle and narrow mouthed Su iv a 24 (Pl VI) is also rather peculiar in its shape and, like the other miniature cups shown in the same plate seems to be intended for a toy. A very curious little piece is Su iv a 23 which has a small hole at one end of the top [As Mr Mackay points out to me it is meant for a whistle] It is of interest to note that besides two painted potsherds of red ware one with a kind of hour glass pattern Su iv a 17<sup>13</sup> there were found in this run also two fragments of grey ware. One (Su iv a 3 Pl VII) of them shows a pattern in a faded brownish purple which recalls ornamentation frequent in the funerary vessels of the Shahr-i Kump mound to be discussed below. The other grey fragment Su iv a 25 (Pl VI) is from a small bowl and of remarkably fine and hard ware very different from the poor fabric to be found among funerary ware of Shahr-i Kump.

Miscellaneous finds in Su iv a.—Fragments of clay bangles greatly varying in thickness (see Su iv a 9 Pl VII) as well as of bangles cut from shells (Su iv a 26 Pl VI) were numerous. The purpose of the baluster like clay object, Su iv a 4 (Pl VII) is not clear. We may safely recognize an import in the fragment of well made light blue coloured glass Su iv a 19 from the rim of a bowl. As it was found some four feet below the surface its antiquity is not subject to doubt. Several of the stone blades a dozen or so in all including the largest Su iv a 16 (Pl VI) were excavated close by at the same depth. From the small room to the north the floor of which apparently lay on a somewhat higher level there came besides many of the objects already mentioned the fine copper celt Su iv a 10 (Pl VII) 5<sup>1</sup>/<sub>2</sub>" long and over 2" across at its broader end as well as fragments of a copper knife and copper needles (Su iv a 18 18a Pl VI). The discovery of these miscellaneous objects in the same small building all pointing jointly to occupation in Chalcolithic times affords full support to the conclusion which the examination of the surface finds has already led us to draw.

Clearing of structure Su iv b.—At a distance of about 30 yards to the south of this run remains of another small building adjoining the rocky slope could be traced. Parallel to a stone wall 3 feet thick and standing to a height of less than that there was cleared a second shorter one to the west at a distance of about 6 feet. On a small semicircular projection formed by this wall there stood a wide mouthed pot probably once intended to hold water. Below it in a small recess built against the natural slope there stood a second and larger pot having a height of 23 inches with a maximum width of about 22 inches. Only earth and small potsherds were found in either. Of other objects there were found here some pieces of pottery, including one of painted grey ware, and the first Su iv b 1 (Pl V), a few stone blades and fragments of clay and shell bangles of copper and of a blue glass bead.

Trial trenches below S E corner.—There still remain to be mentioned trial excavations made on the small terraces of the ridge which descends from the south eastern corner of the enclosed area. It has already been stated that lines of decayed walls could be traced here on the surface at a number of points

<sup>13</sup> Cf I & a Pl CxIV K G 28 for a closely resembling design

Those cleared at the point marked vi proved to be mere remnants of foundations. A piece of painted red ware Su vi 1 (Pl VII) found in the debris shows a geometrical pattern with interlacing scrolls and rows of pendent beads some what more elaborate than the designs on other painted pottery from the site. The perforated sticks of clay Su vi 23 (Pl VII) may possibly have served as a kind of knitting needles. Some stone blades and fragments of clay and shell bangles were also found here as well as in the ground at vii where several trenches were cut as marked in the sketch plan Pl 4 without hitting structural remains. The small cup like fragment of clay Su vi 1, which like the similar piece Su sa (Pl VI) shows little indentations and scratches at its outside bottom might perhaps have been used as a thumb nail.

Period of chalcolithic occupation.—Having completed the account of the observations and finds made on my visit to the site I may now in conclusion briefly call attention to those points which by themselves or by comparison with observations elsewhere may help to throw some light on the character and relative period of the civilisation represented by its remains. That the occupation of Suktagen dor dates back to chalcolithic times and to those only is sufficiently shown by the uniform character of the objects found there whether above or below the ground. Two facts appear to me to indicate that the stage of development reflected by the relics of the site was a comparatively early one in the chalcolithic civilisation of the region which comprises the Indo-Iranian borderlands. One important fact is the close resemblance of the painted pottery to that found at the early chalcolithic sites of Zhob and Loralai (Perano ghundai Mogbul ghundai Sūrjangal) in decorative style colouring and fabric. This resemblance links it also with painted ware from the prehistoric sites of Sistan. The other fact is its striking rarity when compared with the great abundance of undecorated pottery of exactly the same superior fabric. Taking the two together it seems to me difficult to avoid the conclusion that the ceramic remains of Suktagen dor point to a stage somewhat less advanced than that represented by the painted pottery of the sites in North Baluchistan and Sistan.

Profusion of stone implements.—In support of this conclusion reference may be made to the remarkable profusion of stone implements found all over the surface of the site and wherever excavation probed the ground below it. The number of worked stones collected at Suktagen dor is disproportionately large in comparison with those from Perano ghundai and Mogbul ghundai or with those which could be found over the far greater area of chalcolithic occupation represented by the mounds in the wind eroded desert of the Helmand delta.

Rarity of grey pottery.—In view of the indications just noted the presence of a very few pieces of grey pottery with two or three exceptions all unpainted is of interest. Its rarity contrasts strongly with the prevalence of painted grey ware among the funerary deposits in the uppermost stratum of the Shahi tump mound. This together with the coarser execution of the patterns found on the latter ware suggests a later date for the chalcolithic burials.

While at Shah tump the burial remains all consisted of complete bodies buried in the ground the cinerary vessels cleared at Suktagen dor v and those found in the course of Major Mockler's excavations prove funeral customs identical with those attested at Perano ghundai and Moghul ghundai

**Absence of Nal type painted ware**—This difference in funeral practice deserves particular notice in view of what must be pointed out here in connexion with two negative observations concerning the ceramic remains of Suktagen dor. The systematic excavations carried out by Mr Hargreaves at the burial ground of the Sohr damb of Nal have conclusively proved there the association of burials containing complete bodies interred in the same fashion as at Shah tump with a type of painted pottery which may conveniently be designated as the Nal type. This painted ware is characterized by patterns mostly geometrical executed in different colours and elaborate design largely composed of scrolls and curved lines. Plentiful specimens of it undoubtedly from vessels in ordinary use of the living were found at numerous sites of Kolwa and Jhalawan<sup>11</sup>. But at Suktagen dor not a single potsherd of this type could be traced. Nor were any such patterns to be seen at Shah tump where the painted patterns on the funeral vessels of the topmost layer are closely related to those of the red painted ware of Suktagen dor and the above mentioned early Zhob sites though executed with far less care and with colours easily effaced.

**Absence of terracotta figurines**—On the other hand the Shah tump mound in its lower layers composed of the debris of dwellings has furnished a large number of terracotta figurines of exactly the same character as those which were gathered in plenty from the Kolwa and Jhalawan sites showing painted pottery of the Nal type. They represent either a humped bull or else the upper portion of a female figure which judging from the elaborate head dress and other ornaments may be taken as that of a goddess. Now a few of such terracotta figurines were found at the Zhob sites the painted pottery of which agrees with that of Suktagen dor but not a single one at the latter site. If we consider all these indications conjointly and take account in particular of the stratigraphic evidence afforded by the finds at the Shah tump mound the assumption may be hazarded that the occupation of Suktagen dor dates back to an earlier phase of chalcolithic civilization represented in the north by the two principal Zhob mounds and that the mounds with pottery of the Nal type belong to a later phase when interment of complete bodies took the place of cinerary deposits.

If this assumption is right we should have to look upon the Shah tump mound as preserving the burial remains of an intermediate period when cremation had given way to interment but the vessels used for funerary deposits with the bodies were still painted in a style reproducing the patterns of earlier chalcolithic pottery. In the present state of our knowledge however it would

---

For specimens of such Nal wa c. see Pl. XX, XXI, XXIV, XXVII.  
Cf. below pp. 32-34

not be safe to disregard altogether the possibility of the distinctions just indicated in burial customs as well as in ceramic remains being perhaps connected at least partly with differences of racial origin or of cultural spheres. I shall have occasion to return to this question further on.

Character of Suktagen dor site.—It only remains for me to refer briefly to what inferences if any can be drawn as to the character of the Suktagen dor site from its topographical position. Major Mockler has already referred to the Baloch local tradition that the place was once reached by the sea and served as a bandar or harbour. But he justly expressed his doubt as to this tradition being more than a guess intended to account for the shells and other marine deposits belonging to the geological formation of the low hills around.<sup>16</sup> At present even small fishing boats cannot pass more than about 15 miles beyond the bar at the mouth of the Dasht river where it empties itself into the sea in the bay of Gwatar.<sup>17</sup> That point is over 36 miles below Suktagen dor and it is difficult to believe that even if the rainfall and consequently also the rivers drainage be assumed to have been considerably greater in prehistoric times than it is now, the river course could ever have served so far up for navigation by sea-going boats. Nor is the very limited area which is available for cultivation at this point of the left bank between utterly barren hills likely to have favoured a considerable agricultural settlement.<sup>18</sup> But Suktagen dor occupies a position upon which convenient routes towards Kej converge from a number of little fishing harbours on the coast between Gwatar Bay, Pasu bandar and Gwadar. These routes are now much used by the considerable fishing trade which finds its way from the coast into the interior of both British and Persian Makran and this traffic accounts for the present Sumtsar posts situated close by on both sides of the river. The junction of these routes may well have claimed some importance in prehistoric times also.

## CHAPTER V.—REMAINS ON MAKRĀN COAST

### SECTION 1.—OLD REMAINS NEAR GWĀDAR

On January 23rd I started from Suktagen dor for the coast of the Arabian Sea. My visit to it was prompted by the intention to examine two localities near the little harbours of Gwadar and Jiwan where Major Mockler had noticed small 'dams' marking old burial places. But a motif quite as strong perhaps was the wish to gain some personal acquaintance with at least a portion of that coast of the Ikthiophagon along which Alexander's fleet under Nearchos had slowly made its way from the mouth of the Indus towards the Persian Gulf and which at more than one point had seen the great

<sup>16</sup> Cf. J. R. A. S. 1877 p. 126.

<sup>17</sup> See Captain R. G. Lockwood's account of the terminal course of the Dasht River in *Marguerite Wanderings in Balochistan* 1882 p. 70.


conqueror himself pass by. The stretch of the coast between Gwādar and Jiwann which my tour allowed me to see did indeed give me some personal impressions of the inhospitable nature of the ground and enabled me to visualize as it were the difficulties and trials which attended this concluding phase of Alexander's Indian enterprise. But the portion of the coast actually seen was too short to justify in this place any attempt to review the much discussed questions raised by this famous retreat. My account here will therefore be restricted to a description of what antiquarian remains came within the reach of my survey and to brief indications of their topographical setting.

March to Gwadar.—Our first march towards Gwadar led through low broken hillocks stretching south of the Sajdi range and across completely denuded peneplains to the foot of a south western outlier of the coastal range known as Garre kōh. From the halt there made at the water hole of Pishal the port of Gwadar was gained next day over a gently sloping glaciis of detritus and a belt of scrub covered sand dunes extending along the sea shore. The town of Gwadar is situated at the southern end of a flat and narrow isthmus of sandy ground which joins a steep rocky headland some nine miles long to the main shore line. The headland as similar promontories rising from the sea at Pasmā and further east show is a remnant of an otherwise submerged outer hull range. It affords shelter in roadsteads for such craft as can enter the shallow bays on either side of the isthmus. The sea around swarms with fish and just as fishing is now the main industry of Gwadar and the export of its products the staple trade of the port<sup>1</sup> it is likely to have secured some importance to the place already in early times.


Maritime relations of Gwadar.—No direct evidence is at present available as to whether navigation along the coast of Makran had in prehistoric times played an essential part in establishing and maintaining relations between the Indus region and the territories adjoining the Persian Gulf including Mesopotamia. In Achaemenidian times coastal trade of this kind could scarcely have prevailed to any large extent else the dispatch by Alexander of the fleet under Nearchos would not have borne the character of an exploratory expedition. But the enterprise which makes the present sailors of Gwadar mostly Meds with their native craft seek parts as distant as the Malabar Coast and Zanzibar may all the same be of old growth. Of the overseas relations of Gwadar there is significant political evidence for the town of Gwadar and the territory which extends in an arc up to the foot of the hills from a coastal base measuring about 30 miles belong since the last quarter of the 18th century to the Sultans of Muskat. Much about Gwadar town especially the modern fort which guards the approach to the town from the narrow isthmus seemed to me to bear a curiously Arabian look.

Muhammadan domed tombs at Gwadar.—The remains of antiquarian interest at Gwadar town are few. The mound in the middle of its mean

<sup>1</sup> The *N. Iran Gazetteer* 1: 289 puts the number of fishing boats belonging in 1900 to Gwadar at 646 in addition to 23 large native craft. Of the population on the coast reckoned at about 4300 persons some 3700 were Meds practically all fishing folk. *cf. ibid.* p. 230.



ANALYST FOR THE YEAR 1914



For information on any other of our plastic tools call 1-800-1-234.





fly infected lanes which bears the small and now abandoned old fort is probably composed of ancient debris. But the high dwellings which occupy its slopes make close examination impossible. To the south of the town Muhammadan cemeteries stretch along the foot of the precipitous cliffs with which the promontory above referred to falls off eastwards to the beach. Near their southern end are found two domed Muhammadan tombs or 'Gumbaz' built with slabs of somewhat spongy sandstone. One is almost completely thrown to the ground while the other, as seen in the photograph (Fig 19) still shows its essential architectural features. These comprise a dome, constructed with horizontal courses and resting on four monolithic quadrangular pillars and enclosing walls which form a square measuring  $26\frac{1}{2}$  feet outside on the plinth. The wall facing south through which the entrance lies has almost completely disappeared. The other three walls have in the centre arched niches which originally seem to have all been closed on the outside. Small arched windows provided with screens pierce the walls at the NW and NE corners. Simple arabesque carvings in low relief decorate the semi-detached columns on the outside of the niches and windows and traces of them remain also on the masonry courses inside the dome. The architecture of the small structure agrees with the date 879 A. H. (A. D. 1488) which an inscription recorded in the Makran Gazetteer but no longer *in situ* indicates as the date of its completion.

**Barrage on Batel plateau**—From the end of the sandy plain occupied by these cemeteries a steep ascent of about 200 feet leads up the scarp of the promontory to a small plateau known by the name of *Batel*. Passing from its edge for about half a mile over bare rock there is reached a narrow ravine through which the drainage of a trough-like depression of the plateau further west finds its way to the sea. By closing the upper end of this ravine the bottom of the trough is put under water in years of adequate rainfall and the ground thus heavily irrigated subsequently used for intensive cultivation. At a distance of about 30 to 40 yards below the roughly constructed dam of earth and stones which serves as the present barrage there is found a very massively constructed embankment of quite imposing strength (Fig 23). It is built entirely of large blocks of stone and faced on the upward side with carefully dressed sandstone slabs measuring on the average  $2 \times 2 \times 8$ ". The dam proper is 34 feet wide and extends for a distance of 134 feet from the rock slope on the west. Beyond this distance the dam has been completely broken, leaving the bottom of the ravine open for a distance of about 40 feet.

**Broken end of barrage**—Slabs evidently from this destroyed portion of the dam are found scattered along the drainage bed which passes from the dammed up lakelet towards the broken eastern end of the old embankment. The intact portion of this rises 9 feet above the level of the pool which I found covering its foot. It bears on its top a very massive parapet-like wall built with carefully morticed stone blocks measuring up to 5 feet in length, 2' 1" in width and 1' 7" in height. This wall ends with a well recognizable corner close to the broken end of the dam. Through the middle of the dam and about

6 below the foot of the parapet like wall there passes a conduit 15 wide and 19" high. This manifestly was intended to provide a means for keeping the embanked water of the reservoir at the desired level. But so modest a conduit would not suffice on occasions when heavy rainfall might rapidly raise the level. It may hence be assumed with some reason that the broken eastern end of the embankment was provided with one or more sluice gates intended to facilitate rapid drainage in such an eventuality. Whether the destruction at this end was due to an exceptional flood or was intentional when the later barrage was raised further up I was not able to determine. But it appeared to me very probable that the construction of this later embankment became necessary owing to the inevitable rise of the level at the bottom of the trough through silting.

**Supposed Portuguese construction**—Local opinion as communicated to me appears to connect the ruined dam with the period of the Portuguese occupation of Gwadar in the 16th 17th century. The very careful construction and the evident engineering skill which it betokens seem to support this attribution. Considering that the water about Gwadar town obtained from shallow wells is brackish the reservoir created by the dam may well have been intended also to assure a more or less permanent supply of good water. This is certainly utilized now a days as shown by the strings of donkeys we met descending with water skins from the rocky plateau of Batel.

**Burial cairns of Gatti**—From Gwadar I visited on January 24th the small hamlet of Gatti at the foot of the conspicuous hill known as Jabal-i-Mahdi which rises with steep and fantastically eroded rocky crests immediately above the sea shore about 6 miles to the north east of the town. Major Moeller in his previously noted paper 'On ruins in Makran' had mentioned here small 'dams' which from his brief description seemed to be of the same type as the burial cairns examined by me near Moghul ghundai in Zhob and traced also in Loralai.<sup>2</sup> The examination of the remains fully confirmed this. The first group of little stone circles was reached after passing for about a mile along the north foot of the wall like Jabal-i-Mahdi where rain water caught from its slopes permits of cultivation on patches of dammed fields. On a small stony terrace situated about three quarters of a mile to the NE of the triangulated point shown by the map with the height of 1344 feet there are some fourteen little stone heaps roughly circular in shape on a somewhat scattered lower terrace close by there are about forty more (Fig 21). In the centre of these stone circles from 5 to 7 feet in diameter and rarely more than a foot or two in height there is usually a patch of loose earth.

**Finds in cairns examined**—A number of these little dams seemed to have been previously disturbed. Among the half dozen examined here the majority were found to contain in the centre a few bone fragments apparently human and unburnt and small pieces of coarse unpainted pottery. In one

<sup>2</sup> See J. P. I. P. 187 p. 133

<sup>3</sup> See A. Baluch et al. Tour pp. 46 sqq. 104

there turned up numerous fragments of a small copper or bronze vessel. On the surface of the lower terrace there were piled up a few potsherds with thick bluish green glaze and one showing coarse 'ribbing' on the outer surface. A piece of such ribbed pottery was found also within one of the little 'dumps' of another smaller group situated about a quarter of a mile to the north west by the side of a dammed up field. Others were empty. Scanty as these finds were they sufficed to support the conclusion to be drawn from Major Mockler's account as to the relative age of these burial remains. The fragments of iron and a green glazed bottle of elegant shape which he mentions among the objects yielded by the clearing of six dams, combined with the above noted glazed or ribbed ware prove that these deposits like those of Moghul ghundai and those of Jiwanri to be described presently date from early historical times.

Reasons for moving W. of Gwadar.—From Gwadar I decided to follow the coast to the small harbour of Jiwanri situated on the eastern shore of Gwadar Bay and near the mouth of the Dasht river. My choice of this move westwards was prompted in the first place by the wish to examine the extensive series of dams obviously burial cairns, which Major Mockler had observed near Jiwanri but of which but a few had been searched by him.<sup>1</sup> But at the time I also entertained some hope that it might become possible for me to visit two important sites, evidently of the same character situated on the Persian side of the border which Major Mockler had described. These two sites of 'Damba kuh' and 'Darmam ban' (corresponding to the Kuhl Kashu and Damba Kuh of the map Sheet No. 31 G) lie in the practically independent Dashtian territory, near the old bed of the Bahu river and within about sixteen miles of the Perso British border line. But it was not considered advisable for me to visit them without being accompanied by an escort from the Makran Levy Corps and on this ground the higher political authorities felt obliged to withhold the permission I had requested for the visit. Notwithstanding this disappointment however I had no reason to regret my decision for the results of my exploration of the Jiwanri site proved more interesting than expected. On the other hand a move eastwards to Pasni would have probably implied a considerable expenditure of time without adequate antiquarian profit local information not indicating ancient remains in that direction.

March along coast to Ganz.—On January 27th we left Gwadar and after a long march skirting the desolate shores of Gwadar West Bay camped by the dry flood bed of the Pasao kaur some four miles above the fishing hamlet of Pishuk n. The march was made very trying by the icy Gurich or north gale which had sprung up after the hot days at Gwadar and continued to blow with more or less violence all the time we spent by the coast. With temperatures which at Panjgur sank as low as 22 degrees of Fahrenheit it helped to bring home the climatic amenities enjoyed by Makran. On the following day our route led through and past headlands of clay capped by hard


layers of limestone, which erosion has caused to assume fantastic shapes, to the little fishing village of Ganz Thence in order to reach the reported 'dams' of Take-dap we had to ascend to the rocky plateau on the top of the headland with which the small peninsula between Ganz and Gwatar Bay juts out into the sea There the track, impracticable for camels, led over absolutely denuded rocky terraces of calcareous sandstone until some seven miles from Ganz the little valley of Take-dap was reached It holds some fields abandoned for many years and a tiny streamlet descending into the sea below

**Burial cairns and middens of Take-dap**—The reported 'dams' which we examined next day were found to be scattered over an absolutely flat plateau of calcareous sandstone. This rises eastwards about 200 feet above the bottom of the valley and overlooks the bold cliffs which line the sea shore all along this southern face of the headland Over an area measuring about 306 yards from SE to NW, and some 170 yards across we traced altogether thirty-two 'dams' or cairns They are invariably formed by roughly circular heaps of stone blocks collected on the spot and rise to a height of 2 to 3 feet (Fig 22) These little enclosures measuring up to 8 or 9 feet across always proved to contain in the centre loose earth right down to the natural rock floor In the majority of the cairns this earth was found to be mixed with the broken shells of crustacea Large spoil heaps or kitchen middens composed of shells of all kinds and up to 40 feet or so across, strew the plateau by the side of the cairns, in some instances the latter were found to be placed over them This makes it very probable that the plateau had in early times been occupied also by the living The very hard, almost fossilized, condition of the contents of these middens indicates their great age In some places there was evidence of their having been dug into in recent times in order to furnish material for the lime which is needed for 'liming' the fishermen's nets<sup>5</sup>


**Finds within burial cairns**—Within most of the cairns examined small fragments of human bones turned up and in half a dozen of them also fragments of coarse undecorated pottery The bones showed no definite marks of calcination A small pot of such ware about 6" high which was found badly broken, had its side fitted with two 'ears' perforated just sufficiently to permit a string to be passed through The fragment of a similar ear was found in another cairn An open mouthed cup, with flat bottom, *Tabl. 1.* is reproduced in *Pl. V* The bones of a fish and the shells which were found in a coarse pot mark food provision made for the dead The only find of metal was a fragment of a copper pin or wire

**Traces of early fishing settlement**—Scanty as were the objects recovered by our rapid search of the cairns they suffice to make it clear that the remains of Take-dap belong to a small settlement of fishing folk of primitive ways such as the Ichthyophagor whom Alexander's fleet encountered on


<sup>5</sup> I regard as this process of liming of nets as now practised on the Makran coast of *Makran Gazetteer*, p 203



U U G O G G O H



H U K T T n



O U U



its voyage along this coast. The little inlet of the sea at the mouth of the Take-dap valley may well have served as a convenient shelter for small fishing craft. The plateau high above it was perhaps used as a breezy resort during the torrid summer or as a place for occasional feasting before it was occupied by the cairns raised over remains of the dead. The question as to the disposal of the latter will best be considered in connexion with the far more extensive burial remains traced near Jiwanri. This small harbour with a population of some 600 people mostly engaged in fishing was reached the same evening from Take-dap most of the seven miles march having led across a bare rocky tableland.

### SECTION II—THE DAMBS OF JIWANRI

The plateau of Lak.—At a distance of close on two miles to the north of the large cluster of mat-huts which forms the village of Jiwanri there stretches a narrow but long plateau with the general direction from west to east. It is known by the name of *Lak*. At its western end where it commands a fine view across Gwatar Bay it rises very abruptly to about 120 feet above the sandy foreshore of the sea. Eastwards it gradually merges in the rising tableland its relative height above the ground to the south diminishing to 60-70 feet. Here at a point about two miles from the sea shore it is crossed through a small gap by the route which leads to Ganz. The plateau has its greatest width over 1000 yards as the sketch plan Pl. 6 shows at its western extremity. Thence it gradually narrows eastward and becomes more and more indented from the south by eroded ravines while it keeps a fairly straight line where it drops with a steep scarp to the north. The surface on the top of the plateau is formed by a layer of hard calcareous sandstone. Below this layer which is nowhere more than about 5 feet thick lies clay easily affected by erosion whether of water or wind. Hence everywhere along the plateau edge the hard rock of the surface is being gradually undercut and blocks large and small which have thus become detached from the top layer strewn the eroded slopes.

Groups of burial cairns.—Burial cairns of the same type as described at Take-dap but somewhat larger are to be found on the top of the plateau over a total distance of about 2200 yards from west to east. As the sketch plan Pl. 6 shows they occupy two main areas one in the extreme west of the plateau the other about half a mile farther to the east. The latter area comprises the majority of the cairns the total number of which over the whole plateau is well in excess of two hundred. Out of this number fully 178 were opened and examined by us in the course of four days strenuous work. For facility of record the scattered cairns were numbered according to groups their relative position was noted at the time and is marked with approximate accuracy in the sketch plan.<sup>1</sup> Two of the groups I and II comprising 45 and 17 cairns

<sup>1</sup> Individual cairns were marked at the time of examination with small Roman figures e.g. I. vii. etc. In the sketch plan these numbers have for want of space been shown with Arabic figures.



respectively are situated at the extreme western end of the plateau, while a third with about 30 cairns left unsearched lies about 400 yards to the south east of them on the opposite side of a shallow dip in the plateau top. The other three groups III V occupy for the most part narrow tongue like portions on the east of the plateau depressions and ravines of different width all due to erosion divide them from each other. The numbers of cairns examined in these groups and but few are likely to have escaped here attention were 77 in III, 22 in IV and 16 in V. Several of those situated in groups III and IV along the very edge of plateau tongues were found undercut or partly destroyed through erosion. As this is likely to have steadily progressed for centuries the probability is great that the number of cairns was in these groups originally larger.

**Construction of cairns**—The cairns in all the groups resembled each other so closely in method of construction and in the character of the deposits for which they were built that a general description of these essentially uniform features will be appropriate here. The cairns consist throughout of an enclosure formed by building up walls with rough pieces of the hard calcareous sandstone found on the spot around an earth filled interior varying from 3 to 5 feet in diameter. These enclosures are almost throughout of a roughly circular or oval shape and outside at their foot measure from 8 to 12 feet in diameter or across their greater axis. Less than half a dozen only of cairns near the northern end of group III showed a roughly quadrangular shape being probably identical with those mentioned by Major Moekler as square shaped. Two of them had their enclosures almost levelled to the ground obviously in the course of some previous search. In no case did the walls of intact enclosures rise to more than 3 feet above the hard rock surface of the ground. No where was there any trace of a 'door' to these enclosures such as Major Moekler had found in the dams of Dambakoh and as he was inclined to suspect the existence of here, too.

**Deposits of human bones**—Within the earth filling the space thus enclosed there were found in most cases fragments of bones, generally very small. But in numerous instances (eg I xxi, III xvi) fairly large bone fragments were found which could be readily recognized as human such as thigh bones arm bones face caps etc. None of the bones showed distinct marks of calcination nor were bone fragments or ashes ever found within the vessels deposited in the cairns. Considering how small the bone fragments from most of the cairns were not much importance can attach to the apparent absence of bone remains from a number of others for as time would not allow of very careful sifting of the earth such small pieces of bone may well have escaped attention.

**Ceramic remains**—The same observation applies also to ceramic remains. In the vast majority of cairns the burial deposits were found to include either coarse potsherds of varying sizes mostly small or else more rarely complete

vessels. The latter were very often found intact but in other cases had suffered damage while buried owing to the inferior quality of their fabric or otherwise. Before I proceed to detail individual finds of interest in these burial cairns reference may conveniently be made here to two negative observations of some significance. Nowhere on this site whether within the cairns or outside them on the surface was a single stone implement found. Nor did I observe shells of crustacea such as were abundant at Tale dāp among any of the deposits.

**Finds of complete vessels.**—In recording notable individual objects I propose to distinguish those recovered from the several groups not so much because these objects differed essentially in character but as on account of a certain divergence in the relative yield of each group. Of the two groups at the western end of the plateau one II adjoins a Muhammadan tomb and Ziārat known as that of Khīdar Sahib situated on the very edge of the cliffs descending to the foreshore. The other group I with more numerous cairns is separated from it by a shallow rocky dip draining northward. At both groups the number of complete vessels found was small but as the specimens reproduced in Pl. V VII show a variety of typical shapes is represented among them. The pot II xii (Pl. V) of a coarse red clay is flat bottomed like all the vessels from the site and has its counterparts in several other pots of somewhat larger size. The flask II x a (Pl. VII) is of an elegant form narrow mouthed and looks as if intended for oil or an unguent. Very characteristic is the flat bottle I iv (Pl. V) of thick but coarse red ware which as three ears on the circumference and a groove running through them show was intended to be hung or carried upright. The spout is set askant obviously to facilitate drinking from the pot while in this position. Its upper surface is decorated with shallow grooving. I viii (Pl. V) is a specimen of several small lota shaped pots. The small flat dish from I iii is of fairly hard dark grey ware. Of the same fabric is also the small jar II xi (Pl. VII) found with its stopper.

**Evidence of later origin.**—The shapes of these vessels quite different from that of the Chalcolithic ware and betokening advanced skill in the use of the wheel would by themselves point to a latter origin. The find of a thick iron hook II x (Pl. VII) no doubt intended for fishing fully agrees with this. It deserves to be noted that scraps of iron are mentioned also by Major Mockler among his finds in the eleven dams which he opened at this site. Apart from the hook just referred to no metal object nor any object which might have served as an ornament was recovered from the cairns searched by us in the groups I and II. As this result is in striking contrast with the comparative frequency of trinkets, etc. recovered from the groups III V, the conclusion suggests itself that the burial remains of the latter belonged to a rather more affluent class of the ancient population. In this connexion I may point out that to the south of the plateau there extends a considerable area of arable land which though badly neglected by its present owners of the Shāhza tribe might at one time have provided agricultural resources of some consequence.

Ceramic objects from groups IV V—The types of pottery vessels and of other deposited objects found in the cairns of groups IV V were so uniformly distributed that it will be justified to describe them without separating these groups which as the sketch plan shows, closely adjoin. Taking the ceramic finds first it deserves to be noted that several cairns contained a number of complete pots jars or bottles up to a total of four thus eg III vi vii xvi, lxxvi IV n. These like the vessels found singly were usually placed against the inner face of the enclosing wall. Among undecorated vessels there were particularly frequent large flat-bottomed pots of coarse reddish ware up to 12 inches in diameter with narrow spouts mostly placed sideways. Of the specimens reproduced in Pl VIII IV n and III lxi show shapes represented by several examples. In the case of III liv there is evidence of the vessel having been meant for hanging a groove encircles the convex heel-shaped projection of the side and is provided with four perforated ears through which a string was passed. III xxxi is of interest as it shows two narrow spouts one in the centre of the top and the other placed on the side obviously to facilitate drinking. Smaller pots too with narrow mouths in the centre of the top were provided with ears either two or four for hanging as III vii and the painted specimens III lxxvii a (Pl IX) and III xxxiii show. The plain jar III viii (Pl IX), with a wider mouth illustrates a type repeatedly represented.

Shapes of vessels—Among the painted ware the last two shapes also occur but as the specimens reproduced in Pl IX (III xvi a b xxxiii lviii IV n) show usually with two or four ears provided for hanging. In addition to these shapes we meet here also with examples of jars (III xvi c lxxvi b Pl IX) which have by the side of wide mouths also small pointed spouts resembling those of a modern milk jug. A fine and almost classical looking shape is that of the painted vase III lxxv a (Pl VIII) which alone among the pottery of the site is provided with a hollow high base.

Painted patterns on vessels—Turning to the decoration of the painted pieces it must be noted in the first place that the colour of the design usually black but in a few pieces a dark buff appears always to have been applied after burning and therefore is liable to be easily effaced by rubbing or the application of water. This leaves little doubt as to this decorated ware having been specially prepared for funeral purposes. The same is suggested also by the often very inferior make of the body. Among the decorative designs that of the vase III lxxvii a (Pl VIII) is the most interesting as the principal motif a scroll of carefully executed volutes exhibits a certain resemblance to motifs known to classical and other western art. Coarsely painted parallel bands border it above and below with vandykes inserted immediately above the scroll. A closely corresponding scheme of decoration is seen also on the graceful little jar III xvi c (Pl IX). A band of volutes forms part of the decoration on III lviii a (Pl IX) and much effaced on III lviii (Pl IX) also. In III xxxiii (Pl IX) large vandykes take their place. A pair of double volutes branching from a central stem is seen as a detached ornament on III vi (Pl VIII). A similar ornament is found on the top of the flat small mouthed pot III xxxiii a.

(Pl VIII) simple wave lines and vertical hachures decorating the side. Else we find simple wave lines inserted between parallel bands as in III vi (Pl VIII) and III xvi b c and III xi b (Pl IX). In IV vii (Pl VIII) the central zone between such bands shows a succession of semi circles formed with parallel lines and separated by a band of hachured triglyphs. On the large jar III xvi (Pl VIII) the place of the triglyphs is taken by upright ornaments comprising what look like two highly stylized trees. Quite by itself stands the small gracefully shaped jug III xxxi (Pl IX) with a very narrow mouth and a now broken handle. Its surface badly rubbed still retains portions of a creamy white glaze which has turned iridescent.

Miscellaneous deposits.—Among the miscellaneous deposits in urns of J. III IV are two well preserved copper bracelets or anklets III xvi c f (Pl VII) which were found placed over the mouths of two small jars. They appear to bear simple incised designs which still await cleaning. From quite a number of urns (III ii, iv, lxvii IV ii, xvi V viii) there were recovered small thin rings sometimes several stuck together which appear to be silver. The copper ring found together with a carnelian bead in IV xiv, is provided with a bezel. Fragments of small iron implements no longer recognizable turned up in III ix xii. The use of iron conclusively proves that these burials date from a later period than that of the chalcolithic sites in Makran. This fully agrees with the inferences to be drawn from the character of the burials and the ceramic deposits found with them. The use of iron accounts for the bones found in III xii (Pl VII) and III vii.

Funeral customs resemble those of Moghul ghundai.—The evidence of the observations and finds above detailed suffices to prove close agreement between the funeral customs uniformly prevailing at the Jiwanri site and those which I had first occasion to note at the burial urns explored close to the Moghul ghundai mound in Zhob.<sup>4</sup> At the latter site Hellenistic motifs on some relief decorated small pots and the intaglio design on a seal furnished definite evidence that the burials could not date back further than the early centuries of our era. No painted pottery was found at the Moghul ghundai burial urns hence the help which such might have furnished for chronological determination is not available. On general grounds however I should be inclined to assign to the Jiwanri burials an earlier date, though also within the historical period.<sup>5</sup>

Exposure of dead bodies.—There still remains the question to be considered as to how the bodies of the dead were disposed of at Jiwanri before remains of their bones came to be deposited within the urns. At the Moghul ghundai site the condition of the bone fragments all quite small seemed to indicate that they were left behind after cremation. Among the corresponding remains of the urns,

<sup>4</sup> See *J. Baluchistan Soc.* 1910 p. 119 fig. 10.

Here it may be noted that at the Damb Koh site situated in the Damb Koh tract to the north west of Gwadar Bay and above referred to, Major Macleod found a "burial urn," apparently Parthian when opening one of the ruined dwellings of J. R. A. S. 1877 p. 130.

These dwellings are assumed by him probably rightly to belong to the same period as the many tombs or burial urns found in close proximity on the same hill. In view of the extent and obvious interest of this site I must specially remark that the opportunity of visiting it was denied to me.

on the Lal plateau there were found also large human bones while definite evidence of calcination was absent. Hence the assumption seems justified that the bodies here may have been exposed to wild animals more or less after the Zoroastrian fashion and only such remnants of the bones as could be readily traced subsequently deposited in the cairns. Doubts may arise as to how this could be done without the provision of the orthodox Dakhma.

Practice of *Ortair* recorded.—But that the practice in a primitive form was known in a region adjacent to the coast of the Ikththyophagor is proved by the mention which Diodorus accounts of Alexander's march from the Indus to *Varis Gedrosia* makes of the barbarous custom practised by the *Ortair* with reference to their treatment of the dead.<sup>6</sup> For when a man dies his relatives naked and holding spears carry away his body to the oak coppices which grow in their country and having there deposited it and stripped it of the apparel and ornaments with which it is arrayed they leave it to be devoured by wild beasts. The *Ortair* according to Arrian occupied the country situated immediately to the east of the *Gadrosior* and evidently corresponding to the southernmost portion of *Jhalawan* together with the coast between the *Purah* and *Hingol* rivers.<sup>7</sup>

### SECTION III.—FROM GWATAR BAY TO MAND AND TURBAT

On February 3rd we started from *Jiwani* northward in order to reach *Mand* near the *Nihung* which joins the *Kej* river from the west and with it forms the *Dasht*. My choice of this route for the return journey to *Turbat* was prompted by antiquarian as well as practical reasons. The move to the *Nihung* would offer an opportunity for the examination of certain old mounds in the tract of *Tump* which stretches along it towards the Persian border. At the same time it was to enable us to pick up my *Pathan* orderly and a *Khalasi* who during our stay at *Sultagan-dor* had through their own carelessness received very serious gunshot wounds and had since been undergoing surgical treatment at the hospital of the *Makran Levy Corps* post of *Mand*.

Before the start from *Jiwani* I was able to visit the supposed site of an ancient fort which according to the local tradition of *Jiwani* once occupied the end of a clay ridge stretching towards the southern end of the roadstead and overrunning inland. Here beads, coins, bits of metal and other small objects were said to be picked after rain. No such relics were to be obtained at the time in the village and examination of the spot showed only fragments of plain coarse pottery and scanty remains of the walls of a ruined mosque.

March to *Suntar*.—Two marches aggregating some 13 miles and done in the face of the cutting *Gurich* still blowing brought us *via* *Gabd* village to the *Levy* post of *Suntar*. The route led across the wide alluvial flat to the east of the terminal course of the *Dasht* river until this was crossed to the right

banl a couple of miles below the Sukhtagen der site. Except for small patches of cultivation between Gabd and the hamlet of Kalatul all the ground traversed was a waste either of bare *shor* encrusted clay and sand or low broken ridges. Nowhere did I notice any trace of former cultivation such as with the help of canals or embankments might well have been practised here. From Santsar we reached the fort of Mand after two long marches totalling about 51 miles. The first lay across utterly barren stony plateaus funowed by divi torrent beds which descend from the watershed towards the Persian border. The second led across a western extension of the Gokprosh hills which skirt the Kej valley on the south. Here the appearance of some vegetation above an occasional spring fed pool seemed to suggest approach to less arid ground on the Persian side of Makran.

Koh i-kalat W of Mand.—From Mand fort which guards the Nihing tract against incursions from the lawless Pishin tract across the Persian border I was able in the course of a day's long ride on February 7th to examine a series of small ruined sites which the assembled greybeards had reported in the neighbourhood. Proceeding westwards up the gently rising trough of the wide valley I was shown first the small rocky hillock known as *Koh i-kalat* at about 3 miles distance from the fort. It rises to a height of some 60 feet above the surrounding Kluishkaba fields. Remains of rough stone walls with masonry resembling that seen in the uppermost structures of the Turbat Min cover its slopes. The few fragments of painted pottery showing simple geometrical patterns in black did not indicate early occupation nor was such to be inferred from a piece of blue glazed ware. The top of the hillock is only 20 yards long and some 13 yards across and hence could afford room only for a small place of safety.

Site of Tumpak.—Riding some 7 miles farther through stretches of thorn jungle we reached another small site known as *Tumpak* not far from the Persian border. It comprises a small mound of whitish clay about 20 yards long and 8 feet high and a narrow belt of pottery strewn ground surrounding it. Among the plentiful potsherds a considerable number were painted, showing geometrical patterns in black also brown over red or buff ground. The prevailing motifs were zigzags triangles and triglyphs. As no glazed or ribbed pieces were found it may be concluded that occupation was confined to prehistoric times.

Karagi site.—The other two small sites were found to be situated to the north east of Mand fort. That known as *Karagi* not far from the hamlet of Gohar occupies the top of a stony ridge at the foot of the low hills which flank the Nihing river on the west. It lies at a distance of about 6½ miles from the fort. The top of the ridge, about 150 yards long from east to west and from 30 to 50 yards wide is covered with remains of rubble built dwellings constructed in the same way as at Koh i-kalat. As the ridge is completely isolated and at its eastern end rises to a height of over 100 feet the position is a naturally strong one. The few painted potsherds found gave no definite indication as to the time of occupation. But judging from fragments showing ribbing and incised patterns

as well as from a few pieces of glazed ware this is likely to have extended into mediæval times. The terracotta fragment MK 1 (Pl X) representing a beast's head bears also a later lool. It was of interest to note traces of an old canal passing the foot of the ridge tradition alleges it to have once carried water from the Nihing river as far as Tumpak.

At present the fairly extensive cultivation of Mand is dependent wholly on Karezes or on rainfall. Among the scattered groves of date palms which are watered by the former there rises within a mile from Mand fort the mound known as *Kohna kalat* to a height of about 20 feet. It is manifestly of artificial origin but no ancient potsherds were to be found among the Muhammadan graves which cover it.

Journey down Nihing R.—At the hospital of Mand fort I had found the condition of our two wounded sufficiently advanced towards recovery to permit of arrangements being made for their transport to Turbat by motor lorry. There I was called myself by two interesting tasks which the reconnaissances of my previous stay had indicated. For this reason I was glad that the arrival of at least one of our lorries, successfully repaired from the damage their engines had suffered at that flooding nearly a month before enabled me to cover the distance to Turbat quickly and at the same time to survey whatever old remains had been reported along the route. Irrigation from the Nihing river accounts for a string of small oases being found along its banks. Starting down the valley on February 8th I first halted at the village of Tump which gives its name to the whole tract. There I examined the high mound reputed to be old on which the modern fort held by the local family of Gichkas is built. The continued occupation of the fort and the consequent absence of denudation may explain why I failed to trace here any ancient pottery on the mound.

Prehistoric mound of Nazarabad.—At the village of Nazarabad about six miles further down the valley we fared better. Here a conspicuous mound rises to a height of over 40 feet at the edge the stony glacio descending to the village lands. It measures about 95 yards along its southern foot. Its slopes are thickly covered with rubble used for roughly built walls and traces of such can be made out at different points near the southern foot of the mound as well as on a kind of terrace projecting from its slope to the southwest.

Chalcolithic pottery.—Among the potsherds which mix abundantly with the rubble all over the slopes painted fragments varying greatly in body colour and patterns could be picked up in plenty. It was hence of particular interest that almost at the beginning of our search we picked up a complete small alabaster cup Naz 1 (Pl X) and the small cup Naz 2 (Pl X) which by its shape and its geometrical design painted in black over a dark terracotta slip closely recalled These finds were made in a cutting produced by erosion on the lower slope of the mound. Smaller fragments with geometrical patterns of similar early type

<sup>1</sup> For a specimen of such cups cf. *N. Baluchistan* To r. Pl. VII P. SW d 2.

painted either on a dark red slip or else direct on the terracotta coloured ground are illustrated in Pl. X by Nos 311. In all these pieces the body is a fine well levigated clay just as is usually found in the chalcolithic pottery of the Zhōb and Sulgen dor sites. Similar patterns were found painted in black buff or brown but in a coarser fashion on numerous potsherds of less finished ware and of varied colours as seen in the specimens Nos 11 a 18 26 27 33 38.

Grey painted pottery.—Special interest attaches to the numerous fragments of fine grey ware (see Nos 20 26 28 31 for specimens) which show geometrical patterns painted in black rarely in a brownish purple. The motifs and execution agree with those found on the grey pottery from Purom mounds and also on the funerary grey ware of Shahi tump to be described presently. But in contrast to the latter the painted decoration is fast while the body is of superior strength and hardness. There can be no doubt about the vessels to which these grey fragments belonged were intended for use by the living. The decorative style of the brushwork on the grey ware and on the above mentioned coarser pottery of red buff or pink colour is so similar as to make contemporary production highly probable. The fact that not a single fragment of glazed or relief decorated pottery could be found on this mound suggests its having remained unoccupied during historical times. I therefore regretted that regard for the tasks awaiting me at Turbat did not allow of time for a systematic probing of its strata.

Smaller mounds near Nining R.—Proceeding down the valley I next visited the site known as *Duckun* below the village of Asnabad and at a distance of about 4½ miles in a straight line from Nasirabad. It proved to be situated on the side of a southern branch of the Nihing river's floodbed and far away from any ground cultivable at present. Judging from the absence of any painted pottery among the rubble from decayed dwellings which for about a hundred yards covers what looks like a low natural terrace occupation did not seem to reach back very far here. A third mound in this neighbourhood, called *Kasano damb* was reported on the other side of the river and apparently about 3 miles to the north east of Asnabad this could not be visited by me within the available time. Specimens of painted potsherds which were subsequently brought to me from there all look late coarse ware. They include a piece showing the same voluted scroll as found on the vase J1 III lxxvi (Pl. IX) and the vases J1 III lvi a lvi b (Pl. IX).

Burial mounds near Nasirabad.—From the village of Nasirabad some 4 miles to the north west of the junction of the Nihing and Kēj rivers I visited on February 9th a series of small 'dams' situated on the wide stony Dasht stretching down from the hill range of Kēj band in the north and at a distance of about 1 to 1½ mile from the village. They are small burial mounds of the same type as described at Jiwann heaped up with rough stones from the shallow flood channels which furrow the glacio and along which they are scattered at irregular intervals. We counted altogether 72 of them, but as many are little more than rough stone circles only a foot or two in height with a patch of earth in the centre some others may have escaped notice.



Near most of them a few potsherds of coarse red or buff ware could be picked up on the surface. With only few digging implements at hand our search of these *dambs* was restricted to less than a half a dozen. Apart from small fragments of bones apparently human found in all cairns opened there were recovered from two cairns three pots of coarse red ware with a whitish outer surface. The smallest of the three contained a few bone fragments. In a third cairn small pieces of some iron implement turned up. These finds sufficed to establish the identity of the burial customs at this site with those observed at Jiwani and Moghulghundai. On my first stay at Turbat I had already ascertained the existence of an ancient burial place of the same type but much larger in the vicinity of that chief oasis of Kēj. Hence instead of delaying at Nasira had I decided to save time for its exploration by returning to Turbat the same day.

## CHAPTER VI SITES IN THE KĒJ VALLEY

### SECTION 1—THE BURIAL CAIRNS OF ZANGIAN

A rapid reconnaissance made from Turbat from January 7th had shown me that the site known as *Zangian-damb* comprises an extensive area of low rocky hillocks covered with burial cairns. It is situated about 3 miles to the south west of the Turbat fort and headquarters. As the sketch plan Pl. 6 shows these remains are found in different groups along the wide floodbed of the Sorabkaur which descends from the Gokprosh range and joins the Kēj river opposite to Kalituk. The main groups of cairns extend along the right bank of the flood bed on either side of the caravan track which passes here towards Pasni. The area over which they are spread measures over 1 000 yards from east to west and about half that across where widest. The whole of this ground consists of much decayed little ridges and hillocks of dark calcareous sandstone furrowed by small drainage channels. Together with the utterly bare eroded hills around it presents a truly desolate appearance. The terrace like westernmost portion of the ground lies about 30 feet above the bottom of the flood bed to which it drops with almost vertical cliffs. Further to the east the cairns occupy the slopes of hillocks rising some 50 60 feet higher.

The groups of cairns on the left bank are much smaller and are principally found at the foot of a gently sloping hill raising its top some 210 feet above the flood bed. In the latter are found some small springs of brackish water and a little scrub. The name of *Kambar shor* also used for the site seems to apply properly to this portion of the bed.

Number of cairns.—In the groups on the right bank of the flood bed to which our work of three days was confined about 490 cairns were counted in all. But as many of the cairns are quite low and the little heaps of rough stones ridges over which they are scattered it is probable that the total number is greater. Out of this altogether 69 cairns were opened among those which were

found on the triangular terrace to the west of the Pasni track and along the right bank of the Sorab bed. As some of the cairns were found on the very brink of the clay cliffs which line the latter others are likely to have been destroyed through the progressive undercutting and fall of the bank.

Shape and contents of cairns.—The photograph in Fig 24 illustrates the general appearance of this ground and the typical form of the cairns. Their walls of roughly heaped up stones usually form irregular oblongs with an approximate east to west bearing and enclose earth filled spaces from 2 to 8 feet in length and 2½-3 feet wide. Within this space there were ordinarily found fragments of human bones in most cases very small together with pieces of plain pottery of reddish colour and coarse fabric. In the majority of the bone fragments there were indications of calcination by burning. In ten of the cairns examined there were deposited vessels from a single one up to a total of six. They were placed almost always near the eastern end of the enclosed space and about 1½-2 feet below the top layer of earth. The shapes of the pottery vessels found resemble in most cases those of the corresponding funerary deposits at Jiwani. Flat pots having small spouts on one side as seen in the specimens of Pl XI Zang I xiii and xxx, were common here too. In the case of the former it is curious to note that owing to the construction of the vessel only about half of it could have been filled unless carried upright. The very coarse body and imperfect firing observed in most of these vessels seem to point to their having been made for funerary deposit only.

Decoration of pottery vessels.—This accounts also for the poor preservation of the majority and for the effacement of the painted decoration in the case of those few vessels which had any. In I ii this consists of parallel bands in buff red and black round the widest part of lachured sprays above them and a buff band with a hanging scroll encircling the top. Another type of pot with a long straight spout like that of a modern teapot and a wide mouth is illustrated by I xiv and II v (Pl XI) the latter shows remains of a painted pattern with triangles hanging from a band round the neck. Somewhat better preserved is a similar pattern coarsely painted in black over a whitish surface on the jug II xvi a (Pl XI). This is provided with two handles one grooved connecting the everted rim of the mouth with the shoulder the other meant to represent a loop of rope passed over the mouth for facility of carriage. A similar rope like handle and spout with everted lips belong to a large pot I iv (Pl XI) found completely broken. An interesting piece is the vessel II vii (Pl XI) found with five other plain ones it is shaped to represent a bird perhaps a cock with a crested head serving for a spout a short tail behind and a mouth opening close to a handle on the top. Specimens of a type repeatedly found also at Jiwani are the two flat bottles II viii xix (Pl XI) provided with two ears on the leaf shaped side for hanging. The small flask I iii (Pl XI) is of interest as with its shape size and small mouth it corresponds exactly to a similar flask found in one of the burial cairns of Moghul ghundai.<sup>1</sup> Incised zigzag lines on the top and sides serve as decoration.

<sup>1</sup> Cf. A. Baluch etc. to p. Pl. XI. M. v.

Miscellaneous burial deposits—This close relation of the ceramic ware with that of Jivanni and Moghulghundā affords a chronological indication which is fully confirmed by the other funerary deposits recovered at Zangan. These comprise besides fragments of copper and iron from small objects no longer recognizable a badly rusted and broken large iron sword blade from II viii and another smaller and similarly damaged iron weapon with what seems to be a bronze fastening at the hilt. Both objects still await cleaning. Of other deposits may be mentioned the decorated bone (or shell?) disc II vii (Pl. X), the pottery ring II xvi c (Pl. X) and a few beads in stone. The small figurine II vii a (Pl. X) seems to represent a dog-like animal and probably was used as a toy. A novel feature in the burial deposits of this site was the discovery in two cairns (I xx II xxxix) of a horse's head. It showed no signs of having been cremated like the human bones found with it and obviously proves that the funerary rites practised at the time included on occasion also the immolation of a favourite mount. In conclusion it may also be noted that two small pieces of pottery with a thick coat of mat blue glaze were picked up on the surface close to one of the cairns.

It is possible that a complete search of the cairns would yield other relics permitting a closer determination of the period over which the deposits here extended. I therefore had to regret that after the prolonged labour claimed by the excavations at the Shahn tump mound there was not enough time left for resuming work at Zangan on a scale commensurate to the extent of the site without the risk of being unable within the available season to also solve the rest of my programme in the wide region eastwards. For the same reason I had to forego the intended visit from Turbat to the side valley of Buleda northward where a series of similar small dams or cairns were reported between the villages of Mianaz and Bit.<sup>2</sup>

## SECTION II—THE MOUND OF SHAHI TUMP

Already in the course of my first reconnaissances at Turbat the mound known as *Shahn tump* (the royal mound) and situated about four miles to the west of the fort and headquarters had attracted my attention owing to the numerous painted potsherds of fine red and grey ware which could be picked up on its slopes among rubble from decayed stone walls. It rises within about a hundred yards from the southern edge of the date groves of the village of Tump. It takes its name from the mound and is one of those stretching along the left bank of the Kāj river. A short distance further down lies Kalat, one of the larger among these villages while beyond a stretch of bare clay a couple of hundred yards to the south of the mound a new abandoned Karez runs along the foot of the gently ascending glacis of the Gokprosh hills.

<sup>2</sup> The *Makran Gazetteer* p. 303 notes that there are many dams or cairns on the banks of a hill torrent called the Damlan Kaur. The torrent meant is evidently the one which flows past the Damlan Kaur about 3 miles to the east of Mianaz.



FIG. 2. SAND BEACH LOOKING SOUTH EAST FROM THE ATD




FIG. 3. ROCKY TERRAIN LOOKING SOUTH EAST FROM THE ATD



Mound traditionally respected—The name given to the mound seems to indicate some traditional respect for it. I could not ascertain whether this had anything to do with the choice made by a holy man claiming to have come from Herat who a few years before had settled down at the southern foot of the mound. His local disciples had built a small dwelling for him by the side of some trees and a well. On the adjoining slope of the mound an enclosure had been laid out to serve as a mosque and a *taikhana* dug above it into the mound to provide a cool retreat for the teacher and his acolytes during the heat of the summer. The fact of trees of some age growing on that side of the mound as shown by Fig. 25 suggests that the spot also enjoyed some local veneration before the arrival of this holy person. Fortunately by the time of my return he had started for a pious peregrination and thus no trouble arose about the disturbing effect necessarily accompanying the excavations which we carried on here from the 12th to the 23rd of February. Fortunately too the employment of a large number of labourers up to 100 at one time was facilitated by the close vicinity of several villages.

Size of mound—The mound as the sketch plan Pl. I shows measures about 85 yards from east to west and but little more from north to south. Its top rises to a height of over 27 feet but this may have been slightly greater before part of the top was levelled a year or two before to provide a small platform (b) for praying and teaching. Erosion had caused the slopes to be furrowed with little ravines and had laid bare in them plenty of ancient potsherds as well as some other significant relics. Before I proceed to describe the results of the excavations made it will be useful to cast a rapid glance at these small objects collected from the surface were it only to see to what extent a comparison of them with the objects excavated in different layers would bear out an *a priori* diagnosis as to the character of the mound.

Finds on surface—That the mound marked a site of early occupation could be seen at once from a number of fragments of alabaster bowls and cups of which Sh. T. 26 (Pl. XIV) is a specimen. Similar evidence was afforded by a much used chert blade or scraper Sh. T. 27 (Pl. XIV). By the side of a good deal of plain red pottery recalling Suktagedor in fineness of body there could be picked up fragments of similar ware with geometrical patterns painted in black also in dark purple on a red or pink body. Though executed more coarsely their motifs as the specimens (Sh. T. 18) reproduced in Pl. XII show distinctly recall those found at the early Zhob sites and Suktagedor. But more numerous were pieces of painted grey ware showing similar patterns but executed for the most part with far bolder brushwork. Among the specimens reproduced in Pl. XII Sh. T. 11, 13 are fragments from the rims of small bowls made with superior care both in body and design. Sh. T. 14, 16 seem to illustrate the rise of free motifs including star shapes and circles while elsewhere hachuring within straight lined motifs and leaf shapes is the prevailing style of decoration. No potsherds with flat ribbing or other relief ornamentation were to be seen on the surface of the mound and pieces of stoneware with grey or light green glaze were so few as to suggest merely occasional visits in quite

recent times. On the other hand a relic of manifestly early times could be recognized in a fragment of perforated plain ware of just the same type as so frequent at Suktagen dor.

Trench cut through mound—In order to gain definite information within a limited space of time as to the contents of the mound in the different layers composing it I decided to have a trench 16 feet wide carried from the eastern foot of the mound right through to its centre. The detailed plan of this trench in Pl. 7 shows the several sections into which it was divided and the section in the same Pl. 7 the depth to which the excavation was carried in each of them. From the section it is seen that in sections i to v the level of the surrounding ground was reached, the maximum depth from the surface being 21 ft. in v and not much less in iv and vi. When the clearing in vii had disclosed the presence of a small burial ground on the top of the mound the trench was extended westwards for a distance of some 34 feet and widened by the sections xi-xiv both to north and south. Fig. 29 shows the work in the trench while in progress from the east.

Remains of walls—The remains noted in sections i-iv made it clear that the mound had been formed from the start by the accumulation of debris of dwellings built probably for the most part with walls of rubble set in clay but in places also with rough stone walls. Throughout loose stones obviously brought from neighbouring torrent beds for structural purposes were found embedded in the earth while in places the comparative solidity of the soil suggested remains of walls built with stamped clay or mud bricks. It was however only between sections vii and viii both containing complete burials that remains of a wall built with sun-dried bricks were distinctly determined and measurements of the latter obtained. Remains of rough stone walls up to 2½ feet thick were struck in i and ii close to the surface of the slope. Another wall found in iv from 4 to 7 feet below the surface is likely to have served as a foundation. Different in character is the massive wall 6 feet thick and standing to a height of over 6 feet which was cleared between v and vi and which Fig. 29 shows in course of excavation. It seemed to continue towards SE and NW and may well have belonged to a *circumvallation* built before the mound attained its present height, the top of the wall being found at about 7 feet from the surface of the slope.

Pottery from sections ii-v—Throughout sections ii-v the objects unearthed were with one exception so uniform in character as to permit of their being described here together. Nor was there any appreciable difference observed between successive strata as far as the pottery the most frequent of remains was concerned. The great mass of the potsherds were plain reddish ware of thick well-levigated clay very often showing a dark red slip on the surface. On the fragments of painted ware of the same make the decoration (Pl. XII) and in 5 (Pl. XI) both found at a depth of 12 feet from the surface

we have neat parallel black bands below the rim also painted black of what evidently were large dishes. In v 2 (Pl XII) and n 7 (Pl XI) vertical parallel ripples descend from below the rim to horizontal bands above a second imperfectly preserved zone. The fragment n 5 (Pl XII) found at 12 feet from the surface and belonging to the mouth and shoulder of a large bowl or pot shows a pattern composed of hachured half leaves above and triglyphs below this has its close *pendants* among the motifs of the painted pottery found at the chalcolithic sites of Zhob.<sup>2</sup> This piece is interesting also on account of its very fine slip dark red outside and terracotta within. The boldly hachured motifs of v 3 (Pl XII) & 5 (Pl XI) all three found at a depth of about 16-17 feet are similarly reminiscent of that early painted ware. In v 3 as also in n 2 v 2 (Pl XII) and on the outside of n 4 the painted decoration is combined with waved or straight ridges gracefully applied in relief. In n 8 & 9 (Pl XI) similar relief ornaments are found without colouring on fragments of large vases. The piece m 2 (Pl XI) from a small bowl of fine ware shows outside a kind of stepped surface.

**Painted grey pottery**—Compared with the red ware painted or plain the small number of grey pottery pieces from n v is striking. The thick walled bowl m 3 (Pl XI) shows outside three narrow ridges in relief and appears to have had a scroll design painted inside below the rim almost completely effaced through prolonged use. Motifs like those on the grey painted ware from the surface are found on the fragments n 12 m 1 (Pl XII). But more interesting are the two delicately worked bowls m 6 and iv 1 Pl XIII both of very fine clay. The narrow painted bands of Sigma shapes and contiguous lozenges on the latter vessel practically complete and the contiguous triangles in m 6 have their almost exact counterparts among the motifs decorating fragments from the chalcolithic sites not only of Zhob but also of Sistan.<sup>3</sup>

**Shapes of chalcolithic ware**—Here reference may conveniently be made also to the few other vessels, all of reddish clay and with a single exception plain which come to light in these sections and show shapes still partly recognizable. These shapes as the specimens reproduced in Pl XIII show all more or less resemble those of the small bowls and cups found at Pernanoghundai. The beaker iv 4 shows a simple geometrical pattern coarsely painted in brown. The cup iv 3 of fine thin clay with its small low foot and bulbous shape recalls cups frequent at Pernanoghundai.<sup>4</sup> So do also the pieces m 7 & 8, iv 2. By itself stands the fragment of a small vase of dark grey clay, (or stone?) Sh T m 9 it bears an incised geometrical pattern composed of motifs which are closely akin to those found on painted chalcolithic ware from Zhob and Sistan sites.

**Terracotta figurines of bulls**—Apart from pottery the most numerous finds made here were terracotta figurines of humped bulls of which no less than 80 were recovered all with a single exception in sections n and m. As

<sup>2</sup> Cf e.g. A. Balch's *Tour* Pl XII PSW b 14

<sup>3</sup> Cf *Innermost Asia* m. Pl LXX LXVI A. Balch's *Sistan To* Pl V P 2 VI P 2 XI MILE 6 etc.  
See A. Balch's *Tour* Pl XII PSW b 1 P C



the specimens reproduced in Pl. XIV show, their sizes range from 4 inches in length to miniature representations of only  $\frac{3}{4}$  of an inch. Inured as most of them are, they yet often show naturalistic skill in rendering typical features of the Indian 'Brahman' bull with its big curving hump and the ample dewap hanging from below the neck. Two of the larger specimens, n 17, 19, are coarsely painted in black with stripes over the body and around the head. By the side of so many bulls it is of interest to note that only a single figurine of a cow, n 13 was found, besides a very primitive representation of a non-descript animal, n 12. With the single exception of the miniature figure n 18, all the bull figurines were found about the centre line of the adjoining sections n and m, and on an average level of about 5 feet above that of the surrounding ground. As this level was reached also in iv, v and vi where no such collection of bull figurines was found the conclusion seems justified that their presence *en masse* in n and m was the result of intentional deposit.

Cult use of bull figurines.—It appears highly probable, that this had its reason in some motive of cult and the abundance in which exactly corresponding bull figurines were recovered under similar conditions at the Kolwa and Mashkal sites of Kulh and Mehri fully confirms this conclusion. It deserves, however to be noted that of the figurines of an ornamented female, obviously meant for a goddess of which specimens were found at the Zhob and Lōralai chalcolithic sites and in far greater numbers also at the Kolwa and Mashkal sites not a single one turned up at Shah tump. It seems probable that these little representations of a humped bull had served as votive offerings to some divinity representing the creative power in the world. Thus the similarity of the humped bull, the *vāhana* or emblem of Śiva necessarily suggests itself. The similarity is striking enough to raise the question whether we may not have to recognize here the influence of an ancient cult established already in pre-Aryan India. But it is a question which only further discoveries and researches will perhaps in time permit us to answer.

Miscellaneous finds in n v.—Among other small objects of which specimens are seen in Pl. XIV there were numerous little stone blades found throughout n v at greatly varying depths, fragments of bangles of clay and shell, a stone ring in 13 a small hone in 14. Apart from some small fragments of copper the only metal object found was the well preserved ornament or stamp of copper, with a small shank on the back n 20 (Pl. XIV) showing a raised design. It closely resembles other copper ornaments of the same kind possibly used as seals which were recovered with the burials on the top of the mound. It was found in n under 3 feet of earth and debris, but may perhaps belong to some later burial otherwise completely destroyed by erosion. The only human remains found were those of a badly crushed skeleton apparently in a crouching position which was unearthed in iv at a depth of about 4 feet. No funerary deposits were discovered with it, but in view of the observations made higher up on the mounds it seems probable that two fragments deposited near that body stuck together but in pieces, were originally



FIG 27 SECTION 3-A-B, SHANT TUMP, IN COURSE OF EXCAVATION



FIG 28 SECTION 3-A-B, SHANT TUMP, IN COURSE OF EXCAVATION



FIG 29 NETS OF TONGUE ROLLS ETC. IN SECTION A-B SHANT TUMP




FIG 30 TONGUE ROLLS IN SECTION A-B, SHANT TUMP, IN COURSE OF EXCAVATION



## SECTION 11—BURIAL DEPOSITS ON SHĀHI TUMP

It was on approaching the top of the mound in section vi that the excavation first disclosed remains of a novel and very interesting nature. A couple of feet from the south western corner and at a depth of about 5 feet from the surface there was laid bare a large painted urn vi1 about 14 inches in diameter at its widest. It was badly broken in its upper portion and crushed also below. Within it were found fragments of bones all burnt including pieces of a sheep's or goat's jaw bone with teeth and of the spine mixed with ashes and earth. There was also the fragment of a glass handle. By its side stood a triplet of small bowls joined like a cruet stand vi3 (Pl. VIII) and in a semicircle around it a series of small bowls, cups and dishes, most of them of thin grey ware and with coarsely punted patterns. Two of the bowls had their mouths covered with a small painted grey cup in the one case with an alabaster cup (vi62 Pl. XIII) in the other. They evidently had contained some food or liquid. In four instances two or three wide pots or bowls (vi 2a c Pl. XV XVIII 4a Pl. XVII 10a Pl. XV 11a c) were found stuck one inside the other forming nests. This arrangement proved quite common among the funerary deposits subsequently unearthed on the mound. A flat dish vi7 found much broken held animal bones. vi8 a large pot damaged was also full of such bones apparently burned while below it lay more bones of a sheep or goat.

**Decoration of painted pottery**—Close by was found a large cup vi 12 of thin red ware closely resembling in its shape smaller vessels of this kind found in funeral deposits of Peroglundai. Its painted decoration also has its parallels there and among Sistan chalcolithic ware. But the thinness of the body and the coarseness of the painting with colours often but imperfectly fired features which are common to this piece and to the prevalent grey ware, clearly indicate that this pottery was not intended for ordinary use. It may be different in the case of some small jurs of elegant shape (vi3 a b Pl. XIII) which show no decoration but are of stronger body and better finished. That their shape has no parallel among the early chalcolithic pottery of the North Baluchistan sites or of Suktagedor is a point which deserves to be noted. The style of the decorative patterns will be more conveniently discussed after recording all the burial deposits which the clearing of the other sections vii-xiv brought to light.

**Human body discovered**—The true significance of the clusters of vessels was revealed when under a still more closely packed set of bowls and cups vi 14 about 3 feet to the south east of the first and on a slightly lower level there came to light poorly preserved remains of a human body with the legs bent at the knees and the hands jointly raised towards the chin. The body lay with the head towards the west. The feet had been injured during the removal of the vessels which were cleared close above and around them before the presence of the skeleton was realized. Among the pieces found here was the small crucible shaped bowl vi14a (Pl. XIII) raised on four high legs of which three remain. It is obviously intended to imitate a cooking utensil.

of metal. Another interesting piece is the patera like cup vi 14 e (Pl. XVI) raised on a high base. The small bronze ornament vi 29 (Pl. XIV), was probably deposited with this body, it turned up when sifting the earth removed from below it.

Objects in deeper strata of vi.—Before I proceed to describe the far more abundant funeral deposits found by the side of two bodies to the west of the burial remains of section vi, it will be useful to record the miscellaneous objects which were found while continuing the excavation in this section further down to a maximum depth of 20 feet. Though comparatively few in number, these objects, mainly ceramic help by their marked difference in character to bring out the chronological distance that separates these lower strata of the mound from the one containing the burial deposits on its top. Low down at depths from 14 to 20 feet there were recovered a complete little alabaster jar besides fragments from others: a broken bull figurine of the same type as in ii and iii; the fragment of a leaf shaped copper arrow or javelin head vi 16 (Pl. XIV); a glass fragment apparently from a ring or handle, and pieces of strong well made pottery evidently from ware intended for every day use. Apart from plain pottery of well levigated red clay there were found also fragments decorated with designs painted in black or with raised ridges. In some cases both methods are combined as in vi 17 and vi 25 (Pl. XVI). The latter piece is of very hard dark grey clay with a hachured scroll.

Painted patterns differ from funerary ware.—The painted patterns are throughout of the same simple geometrical type as found at Suktagendör, parallel bands or wave lines prevailing. The difference in decorative style and make from the funerary ware of the top stratum is very striking and cannot be due to mere distance in time. We shall see further on when re-viewing the patterns on the painted funerary vessels from vi and vii that they comprise motifs which cannot be derived from the decorative style of the pottery in actual use when the Shalu tump was an inhabited site and its lower strata in course of formation by the decay of dwellings.

Funerary vessels.—The clearing of section vi had disclosed a large agglomeration of vessels embedded in the ground about the middle of its western edge and on approximately the same level as the body already described. That these funerary deposits belonged to another and far more elaborate burial became evident when excavation was continued westwards into section vii on the very top of the mound. The closely packed cluster of pots, bowls, cups and jars marked vi 13 when first disclosed stood to a height of about 2 feet and comprised not less than fifteen vessels. Owing to the thin and brittle material most of the larger pieces like vi 13 (Pl. XVII) had become broken during their long burial and could be extracted only in pieces. This accounts for the condition of the two painted bowls vi 13 a & b reproduced in Pl. XV, XVII. Most of them were bowls of grey painted ware, up to 10 inches wide but so weak in their body as to show at once their unsuitability for actual use.

Painted jars.—But on the top of the pile were found two painted jars which on account of their shape alone would deserve attention. Like the two

little jars vi 3 a b (Pl XIII) they are small at foot and mouth but bulge out widely in the middle. This is a shape unknown to the early chalcolithic sites of Zhob or Sulitagēn but quite common among the Nal pottery. Still more noteworthy is the fact that while the jar vi 13 b (Pl XIX) shows its pattern of hachured triangles and sprays painted in brown brushwork over a light pink clay vi 13 n (Pl XIII) has the interstices of its simple geometrical motifs in black filled in with red paint after firing. This particular method of decoration is typical among the funerary ware of the Nal site but unknown at the early chalcolithic sites above noted or in the deeper strata of Shahī tump. The important clue thus furnished for the relative age of the Nal ware will be discussed below. This jar vi 13 n had its mouth closed with the alabaster cup vi 13 n a (Pl XIII) and may have held some liquid. Associated with it were three small elongated beads of transparent stone and a small copper stud not yet cleaned. All these were mingled with little fragments of bone evidently from offerings of food.

Bodies buried in vii.—When excavation in section vii had reached a level of about 6 feet below the top of the mound it revealed close to the NE corner of the section a complete body laid with its head to the west and at about 2 feet distance south of it a second one also laid in the direction from east to west. All round the head and at the back of the upper part of the first body A which judging by its size was evidently a male there was ranged a collection of beakers, bowls and cups as seen in Fig 30. Other vessels were found placed near the feet while a still larger number were disposed all over and around the second body B. A superficial reckoning indicated close on fifty separate deposits but in numerous cases bowls and cups proved to be 'nests' made up of several similarly shaped vessels. To this stock must be added the vessels comprised in vi 13 which occupied a position between those found at the feet of the two bodies.

Position of bodies.—As seen in the photographs Figs 31 and 32 taken during and after the clearing the two bodies were not laid in exactly the same way. The body A was laid on its left side with the head slightly dropped and facing north. The arms laid one above the other and bent so that the joint hands were raised to the level of the chin. The legs with bent knees drawn up as of a person resting on a couch. The body rested on rough water worn stones. The other body, B was lying on its back with its less well preserved head turned slightly to the left proper with the right arm resting on the right leg which was but slightly bent and the left arm close to the breast. Here I may note that the poorly preserved bodies subsequently unearthed in other sections also appeared to have been laid on their backs. The heads of the bodies A, B were removed for expert examination (see Appendix).

Funerary furniture.—In the case of body A where the funerary furniture was less crowded around head and back a summary account may usefully be given of the disposition of the several objects. Starting from the left proper of the head and proceeding round to the right of the body there were found

two cups and a large beaker standing on a miniature base as so many of the cups of Periano ghundai next within 6 inches of the top of the skull two small cups and three bowls stuck one into the other. Then followed two large bowls nest-wise with a small cup on the top by their side a small inverted flask and a small stone pestle such as had been found also in vi. Behind the curved back stood two large bowls one inside the other. To the west of the inverted flask lay a heap of small snail shells with a small bowl in their midst and beyond it at intervals of about a foot two more small bowls. Almost all these vessels were painted and the majority of grey ware. In most of the larger vessels small fragments of bones apparently of lambs or fowls were found mixed with the earth ashes also were commonly associated with them evidently all these deposited from offerings burnt to provide food for the dead.

On and around the body B the funerary furniture was so closely packed that no attempt can be made to detail its disposition. The shapes and painted designs represented among the vessels comprised in it will be discussed together with those of the rest of the funerary ware found at Shahu tump in the next section. For an illustration of the conditions in which these vessels were unearthed reference to Fig 28 showing vi 16 17 19 21 30 37 may be useful. Here too the larger bowls proved to be packed in nests up to five being thus found *eg* in vi 8 12 17 small animal bones could be traced in all of them often ashes also.

Ornaments etc buried with bodies.—But the objects buried with these dead were not confined to provisions for their food in another life. At the neck of the body A there was found a small copper ornament vi A 1 (Pl XIV) and below its head a beautifully worked small polygonal bead which might be a spinet or ruby. Below the bowl vi 1 b (Pl XVIII) close to the head lay a very small flint blade. A small terracotta fragment which turned up near this body may have belonged to a bull figurine and have come there only by accident. Far more abundant were the objects recovered from the second body. Below its neck were picked up some 19 small stone beads mainly agate and lapis lazuli and two large ones including the neatly worked onyx vi B 1 (Pl XIV). These evidently belonged to a necklace. Seven more small beads of stone and bone were found near the breast and three small roughly rounded stone balls of uniform size close to the right shoulder of the body. They might perhaps have served for some game. Below the vessel vi 6 placed on the breast of the body lay a small stone blade and within the bowl vi 12 d the lowest of a nest a copper spear head vi 12 d 1 (Pl XIII) broken but complete. It is 9" long and 1 1/2" broad where widest. Underneath the bowl vi 34 there came to light the massive copper axe head vi 35 (Pl XIII). As the verdigris left on some bones showed it had been placed directly on the lower part of the body. It measures 3" in length and 2" along the cutting edge. Spear head and axe head conclusively prove that the body here buried was that of a man obviously a warrior.

Wall between vii and viii.—The extent and character of the funerary deposits brought to light in section vi left no doubt about the bodies here buried




Fig. 41 BURIED BOULLS A, B, IN SECTION VII, SHADI TUMP, AFTER CLEARING




Fig. 42 BURIED





having been those of men of some importance. A comparison of the level on which they had been found with that of the bodies in vi and ix suggested that the sloping surface of the mound as it existed at the time of these burials was likely to have been used elsewhere also near the top for the same purpose. In order to test this assumption it seemed best to continue the trench across the actual top and for some distance on the opposite slope. On proceeding with the excavation to the west of vii there was struck on a level of 2 feet above that of the bodies and of 4 feet below the top surface a wall built with rough stones, most of them rounded by water action. It was 5 feet thick, but stood only about 2 feet in height. That it had served as a foundation was proved by the presence above it of solid masonry of sun dried bricks. This is likely to have once risen much higher and to have been levelled down in the course of the operations previously referred to when a preaching and praying platform was laid out for the holy man established at the site. The bricks measured  $19'' \times 10 \times 3$ . Below the wall foundation there was seen a thin layer of burnt clay and ashes. Whether the wall was built after the bodies of vii had been buried or whether the latter had been laid to rest after the wall had fallen into ruin could not be made out with complete certainty.

Burials in viii and ix.—The latter however appears very probable for in section viii two large funerary pots containing ashes and fragments of animal bones but no human remains, were found under only about a foot of earth near the SE corner and close to the surviving top of the wall of sun dried brick masonry (Fig 27). The same was the case also with a cluster of seven bowls and jars of small size which were cleared near a badly decayed body apparently of a child towards the western edge of the section. At yet another point farther south two small bowls were found at a depth of 6 feet together with fragments of a little copper ornament and a bone bead. No body was traceable on this level or further down. In section ix the next to the west the three burial deposits found all lay close to the surface the levelling done on the top and probably also the preceding erosion having removed much of the soil. In consequence the bodies had suffered much damage. It was only possible to make out that they were placed in an east to west direction. Among the odd dozen of small bowls and jars of ix 2 the squashed bowl ix 2 f 4 (Pl. XVI) may be mentioned. Its misshapen form affords curious proof of the haste and want of care with which this funerary pottery was produced. Both here and at ix 1 the vessels had been placed on the body. With ix 3 was found a small copper stud, ix 3 a (Pl. XIV) with a raised geometrical design on its flat face and a shank at the back. It closely resembles the copper ornaments of the same type but larger found in ii and xiv.

Burials in xi and xiv.—In section xi cleared to the north on sloping ground burial deposits consisting of a few vessels each were found in three different places and a body without vessels in a fourth the levels varying from 3 to 8 feet below the top of the mound. At xi 1 the bowl instead of the usual animal bones contained small shells. In xi 4 there was found the fragment of a bull figurine below one of the two bowls. The section xiv to the west

of the last held a cluster of ten coarsely painted vessels but no human remains. Of the two bodies found in xiv the one near the centre of the section was that of a child. Over the middle of its body lay a badly decayed thin copper disc 4" in diameter with a raised edge and in the centre of the disc a copper stud, xiv 1 a (Pl XIV) with a raised geometrical design corresponding exactly to those already noted from ii and ix. The repetition of the identical design consisting of symmetrically arranged semicircles and two wave lines between seems to preclude the idea of these objects having served as seals. The shank at the back and the raised outlines on the face would have allowed of their use as stamps. Had the design some symbolic meaning? A large number of coarsely painted jars etc. were found arranged around the body, and some more of the same kind near the detached bones of a second body. Section xii was the only area to the south of the main trench where excavation was possible near the centre of the mound without interfering with the tukhana dug into it for the holy man's hot weather quarters. Two bodies were found here at a depth of about 8 feet both much decayed, the few funerary vessels which had been placed over them were badly fired and broken.

Varying level of burials.—It only remains here to note that the greatly varying levels at which the burial remains of vii ix xi xiii xiv were found clearly indicate their having been placed on the slopes of the mound when the latter had owing to progressive denudation already assumed a configuration not unlike its present one. Such a process presupposes a fairly lengthy interval of time between the decay of the dwellings the debris of which has formed the mound and its use as a burial ground. This observation deserves to be taken into account when considering the marked divergence in type which exists between the ceramic relics dating from the occupation of the site by the living and those found buried with the dead.

#### SECTION IV—FUNERARY POTTERY AT SHAHI TUMP

Uniformity of funerary ware.—The uniformity of the pottery deposits found in the graves of Shahi tump in respect of body technique form and decoration is as great as their number. This sufficiently explains why the characteristic features of this pottery may be examined here without regard to the position of the individual burials in the several sections cleared on the top and on the slopes immediately below it. As already stated in the preceding section there is every reason to assume that the difference in the level of the graves is due merely to the fact that the mound at the time when it was used as a burial ground had already undergone considerable denudation and this had assumed a shape not essentially different from its present one.

Ware not intended for use.—What strikes one most in this funerary ware is the fact that with a very few exceptions already noted above<sup>1</sup> all of it is very thin very brittle and hence so fragile that only in rare cases had it

<sup>1</sup> See above pp 93 &c.

escaped being broken while buried in the ground. For the same reason but few of the bowls etc. deposited in nests or stacked close together could be recovered complete. It is certain that this ware was not intended for practical use in the household but made for funerary purposes only. The brittleness of all this pottery would alone suffice to distinguish it at once from the ware found in the interior of the mound or from that of other chalcolithic sites of Baluchistan, thus even when thin shows remarkable strength and hardness. The same cause inadequate levigation and firing accounts for the total absence among all this mass of pottery of any pieces showing the fine red or dark grey colour which with or without slip prevails among the abundant ceramic remains both of the lower strata of Shahi tump or at the other chalcolithic sites described in this report. Hasty and careless manufacture characteristic of this ware is well illustrated by several misshapen pieces.

Repetition of painted motifs.—Another striking peculiarity of this funerary pottery is the constant repetition of the same or but slightly varied scheme of painted decoration as applied to a particular kind of vessel. This restricted range of motifs and the limitation of their use to certain well defined shapes contrasts strongly with the great variety of the motifs to be found on the painted pottery for ordinary use of which Shahi tump and the other chalcolithic sites have preserved such abundant if mostly fragmentary remains. This clearly points to a well established convention for which tenacious tradition fostered by religious notions supplies the obvious explanation. An exact parallel to the peculiarities just indicated distinguishing the funerary ware of Shahi tump from the ordinary painted pottery of this and other Makran sites of approximately similar date is furnished by the painted pottery found in the graves of the earliest zone at Susa and known as Susa I. The true character of this has now been very lucidly and convincingly set forth in an interesting paper of Mr O. L. Woolley.

Type of rimless bowls.—Just as in this Susa pottery the relation between the scheme of decoration and the shape of the vessel is also in our Shahi tump funerary ware so close that it will be best to describe it according to the several types of vessel met with in the graves. The number of these types is very limited as it is also among the Susa I pottery, another noteworthy point of contact. We may begin our account with the type of open flat-bottomed bowls which are by far the most numerous class, not less than 60 specimens being counted among the ceramic deposits of the Shahi tump graves. As shown by the specimens reproduced in Pl. XV, XVI, XVII the great majority is rimless. It varies in size from about 8 to 11 inches in diameter and from 3<sup>1</sup> to 4<sup>1</sup> inches in height. Small bowls like 12 f 4, xv f 4 (Pl. XVI) with a diameter of only 3 to 4 inches are much rarer. The closely approximating sizes of the larger bowls may have been intended to facilitate the convenient deposition in nests within

See The Painted Pottery of Susa, J. R. A. S. 1908, pp. 3-499. I regret to be unable to follow up this parallel more closely by a reference to the *Mémoires de la D. D. G. en Perse* in which the materials concerning the Susa pottery are furnished, and to Mr Woolley's own *Ur Excavations*. Neither of these publications are at present accessible to me.

the limited space of the grave. In the great majority of open bowls the colour of the body is light grey varying often in parts to a dirty pink or yellow. Rarely the colour is throughout light pink, as in vi 33 c (Pl XVI), or yellow as vi 11 a (Pl XV).

Colouring on outside of bowls—Taking first the decoration on the outside it has to be noted that the colour of the painting varies from light brown to dark brown and an almost black purple. This is the case also on the inside. It is probable that these changing shades which often vary over different portions of the same ornament in the same vessel are due to the originally applied colour which may have been throughout black having assumed different tints in the firing. On a number of bowls, as vi 2 b, 10 a, vi 28 b, 33 c, there appear below the edge streaks of irregularly incised hachuring or striation. These extend, *e.g.* in vi 28 b (Pl XV) also over lower portions of the outer surface. Were they not so irregular and in some places confined to mere narrow bands the suggestion might occur that these streaks were due to 'mat marking'. Possibly an imitation of this early hand made ware was intended.

Motifs on outside of bowls—The painted decoration on the outside consists mostly of a plain band below the edge of the bowl (vi 10 a, vi 13 a, 33 d, ix 2 b 1). A festooned band is found in vi 11 a, 33 b, a hachured band in vi 1 b, xiv f 4, a row of pendent triangles in vi 13 d, ix 2 f 4, xiv f 5. A coarse netting covers the whole outside in vi 13 b. While all these designs are plainly geometrical vi 34 d shows both outside and inside a roughly executed scroll ornament composed of double hooks. It curiously recalls the rows of large horned ibexes or antelopes which is so frequent a motif on painted pottery of the chalcolithic sites of Kolwa and Mashkan, but may well be quite independent of it. With the exception of the row of triangles none of these motifs recur on the other types.

Motifs on inside of bowls—Within the bowls by far the most frequent motif is a Svastika like wheel placed in the centre with five curving arms (vi 10 a, 13 a, 13 c, vi 12 b, 13 d, 28 b, 33 c, d, 34 d), in vi 13 f the same motif appears with four arms only. Above this on the sides of the bowls we find rows of double hooks as above mentioned (vi 13 d, 34 d), triangles, vi 11 a, or miscellaneous small geometrical forms (vi 13 c, vi 33 c, ix 2 b 1). The rows of lozenges in the fine grey jars Sh. Tiv 1, m 6 (Pl XIII) found in the lower strata of the teler in vi 2 b, vi f 1, ix 2 g 2 while the place of the 'Svastika' is taken by a kind of quatrefoil with hachured leaf shapes in ix 2 b 1, xiv f 4, h 2. The plain hachure of the outside is in vi 13 b repeated also on the inside.

Bowls with rims—A separate but much rarer type of bowl is represented by the specimens vi 4 a b (Pl XVII), vi 2 (Pl XVII), vi 3 b (Pl XVI) which are shallower and have an inverted rim and a comparatively small base. They all show on the inside broad cross lines and within each of the four segments a hachured oval shape. Below the inside of the rim is painted a zigzag scroll, and hachures adorn the outside of it.

**Painted decoration of pots**—The type of pots all of which painted only on the outside, is illustrated by the specimens shown in Pl XVII. The largest among them vi 13 l is decorated with vertical rows of feathered leaf like shapes separated by pairs of high curving stalks. It measures 13 inches where widest and is 12 inches high. The rim at the mouth is slightly inverted. Hachured triangles arranged in vertical or horizontal rows are the more usual motif as seen in vi 3 d, vi 13 a, 35 b. Elongated hachured lozenges take the place of the triangles in xiv f 2. The decoration of vi 13 h is of interest because it consists of what seem to be very roughly drawn figures of animals, some with high horns some with upstanding tails placed under arcades or arches. Underneath this painted decoration there appear as also on vi 13 a the curious parallel lines incised diagonally to which reference has been made above as suggestive of 'mat-marking'. Very peculiar is the decorative scheme of vi 15 b. It shows above a zone of Svastikas, below it another filled with a kind of Greek key pattern and last a hachured band.

**Shape of cups**—From the pots we may proceed to the smaller vessels which can be described as drinking cups. It deserves to be noted that all these, with a few exceptions like vii 14 are of a light red or buff body and more uniformly fired than the bowls. Among the specimens shown in Pl XVIII vii 14 and ix 2 b 3 are flat-bottomed like pots and decorated like most of these with triangles on the outside. More interesting are the cups having disproportionately small feet and bulging out about their middle part (vi 2 a, vi 2 c, 17 e) for their shape corresponds very closely to that of the numerous small cups no doubt made for use in the household which the sites of Perano ghundai Moghul ghundai and Suktagen dor have yielded in plenty.<sup>2</sup>

**Decorative motifs on cups**—In this case we have clear evidence that the makers of the funerary pottery of Shahi tump were reproducing a type which was originally meant for practical purposes and in all probability thus used at an earlier period. The type is no longer found at the chalcolithic sites of Kolwa and Mashin. The decorative motifs on these cups all of a simple geometrical character such as triangles lozenges and parallel lines placed vertically on horizontal ones are all to be found also on the painted pottery from the Zhab sites. The misshapen piece ix 2 b must have been spoiled in handling before it was fired. That it was all the same thought fit for a burial deposit is a significant illustration of the quasi-symbolic purpose for which all this funerary ware was manufactured on occasion probably in great haste. This may have been different in the case of the small wide mouthed pot xiv f 3 the only specimen of its kind. It is flat bottomed without a proper foot and has a broad everted rim which looks as if meant to pass a string round. It is of thick reddish clay but appears to be but slightly fired. It is possible that it was an article meant for actual use. If that were the case it would indicate a distinct falling off in ceramic craft at the period of its production. By itself stands also the chalice vi 14 e (Pl XVI) of light buff clay inadequately fired. Its body is fairly thick. Its shape is paralleled

<sup>2</sup> See A. Baidar's paper Pl. II X also at pp. 6 sq. 11 & VII.

by that of P SW 16 from Perano chundai and pieces like Mehi II 22 51 63 (Pl XXIX below) etc

Alabaster cups and goblets.—On the other hand we may recognize an archaic shape and material in the several alabaster cups having the form of an inverted cone vi 13 e (Pl XVIII) is a specimen. The employment of such cups for deposit in graves can best be accounted for as due to archaic convention. We find a shape of equally early use in nearly a dozen of curious goblets of which vi 1 c (Pl XVIII) vi 1 e ix 1 b (Pl XIX) xi 4 a (Pl XVII) xiv d (Pl XIX) are characteristic specimens. They range in height from 12 to 4 inches. It seems difficult to believe that ceramic pieces of such shape and size could ever have been produced for practical use. All these goblets have feet far smaller in proportion to their height than even those of the cups already described and of their original models as found at the Zhob and Sultagen dor sites. Their form unambiguously suggests a traditional reproduction of forms which belong to a far earlier period when the use of skin made receptacles prevailed.

Decoration of goblets.—On all these tall goblets the painted decoration shows a simple geometrical scheme executed in dark brown or black. But what is particularly noteworthy is that in these cases the pattern is painted over a slip. This vi 1 e is light buff and in vi 1 c and ix 1 b dark red. In the latter piece a third colour is introduced by bands of light buff laid over two narrow zones. This colour appears to have been applied after firing. Here then we find a technique which is common among the Nal ware used also for the decoration of a shape which may be counted among the earliest among the prehistoric pottery known to us from Baluchistan. I shall presently have occasion to refer to the appearance of this later technique also on the jar vi 13 n (Pl XIII). On the other hand it deserves to be noted that in the fragmentary specimen vi 27 (Pl XIX) the thin body shows clay as fine and hard fired as any of the ancient ware meant for practical use from Sultagen dor or the lower strata of Shahu tump. The same care has been bestowed also on the modelling and the drawing of the neat geometrical pattern. Is it possible that in this case a piece of early pottery dating from the first period when Shahu tump was an inhabited site accidentally found its way into the grave deposit?

Shape of painted jars.—There still remain to be noticed a series of painted jars of which Pl XIX reproduces specimens. They are column shape with narrow flish base and short neck. Their greatest diameter varies from 8 to 3 inches. Their characteristic squat shape is found also in some plain jars like vi 1 g (Pl XIX) and vi 3 a b (Pl XIII). This shape in its typical flatness is very common at Nal and in a modified form slightly less squat appears also in some pieces of Mehi as seen in Pl XXIX. It is not found at any of the early chalcolithic sites of Zhob and Loralai nor at Sultagen dor and the sites of Kohwa.

Pieces with characteristics of Nal type.—It is important to note this negative fact as when considered in conjunction with the position of the Shahu tump graves

it helps to indicate the later chronological sequence of the Nal ware. In this connexion it is of particular interest to note that, as already mentioned above<sup>5</sup> the deposits of the Shahi tump graveyard include also one jar of this specific type, vi 13 n (Pl XIII) which shows the application of different colours after firing a characteristic feature of the Nal pottery in general. Taking into account also the superior body and technique of this piece which points to its having been intended for practical use there is reason to assume that pottery of the Nal type, while completely absent from the lower occupation strata of the Shahi tump mound, was being made and used at the later period when the burials on its top took place.

**Decoration of jars**—The painted decoration of these jars appears to have been applied after firing. In any case it is easily removed by even a slight rubbing. Except in the case of vi 13 b where there is a light-yellow slip the patterns are painted in different shades of brown direct over the body. This is fairly thick and mostly of a reddish colour but buff or grey in ix 2 c ix 2 g 3. The decorative scheme, very uniform throughout is adapted to the shape of the jars and comprises mainly triangles pointing upwards and leaf shapes as in vi 13 b vii 9 b xiv b or schematic sprays (vii 1 a ix 2 c ix 2 g 3) inserted between them.

**Shapes and patterns reproduce earlier ware**—We have now reviewed the various types comparatively limited in number of the ceramic products found in the Shahi tump graves. We have seen that as was to be expected in the case of funerary ware they show for the most part shapes and decorative patterns which tradition had taken over from the pottery made for practical use in an earlier period of chalcolithic civilization and preserved with religious care in order to enable the dead to live their future life after the fashion of their ancestors. These shapes and patterns are with one exception, all such as can be derived from the same prototypes as the ceramic ware intended in actual household use of which remains are preserved for us in the interior of the Shahi tump mound and at other early chalcolithic sites of Makran. The exception referred to is the Svastika like motif which has not been found in the ordinary decorated pottery of any of those sites. We may safely recognize in it an emblem specially connected with the sepulchral rites of a later phase of local chalcolithic civilization.

**Later evolution of Nal type**—That the complete burials of Shahi tump date from this later phase is definitely proved by their position on the very top of the mound. If then we find associated with them also some ceramic objects showing a shape and a method of decoration peculiar to the Nal type we are justified in concluding that the evolution of this type belongs to a period later than the one during which practical daily life knew only pottery reflecting in all essential the same prototypes as the great mass of the funerary vessels.



## CHAPTER VII.—RUINED SITES OF KOLWA

### SECTION 1.—MOUNDS BY THE NORTH AND SOUTH ROUTES

Start for Kolwa.—On February 25th we left Turbat where the packing of the plentiful antiquities brought away from Shahi tump and Zangan had detained me for a day and started on our journey eastwards by the motor track which leads to the Kolwa tract and Jhalawan. The services of Naib Tāj Muhammad a very intelligent and active local official who had formerly been in charge of Kolwa were made available to me by the kindness of Naib Wazar Muhammad Yakub Khān, the head of the Makrān administration. From the information communicated by the former, I knew that in Kolwa a considerable number of ruined sites scattered over a wide area, awaited examination. Regard for this as well as for the rapidly increasing heat made it desirable to leave the low lying Kēj valley quickly. But the necessity of letting the lorries return to Turbat to fetch the remainder of our *impedimenta* which the antiquarian proceeds of the last two months had much increased obliged me to stop for two days at Hoshab, the meeting point of the roads from Panjgur and Jhalawan.

Traces of former occupation at Hoshab.—I employed this enforced halt for examining the mounds and old Karezes in the neighbourhood of which I had learned on my previous passage through Hoshab, and for using the last chance of regular postal communications by the fortnightly mail steamer *ra* Turbat and Pasni. Of the reported 'dams' that of *Gharah* on the left bank of the Kēj river proved a natural ridge of decomposed rock measuring some 120 yards from north to south and less across. Occupation was proved only by scanty fragments of coarse pottery but the find of a small stone scraper on the top seemed an indication of this occupation dating from early times. Thence I proceeded eastward for about 1½ miles across the sandy riverine flat to the terrace like ground known as *Zwarati* *damb*. The extensive Muhammadan burial ground which covers it, with its much decayed graves afforded support to the tradition of the neighbouring alluvial plain having once been cultivated and permanently occupied.

Abandoned Karezes.—A few scattered patches tilled in recent years after good rainfall were to be seen in the neighbourhood and also traces of some long abandoned Karēzes. Tradition alleges the former existence of nine of these and derives the name *Hoshab* fresh water, from them. The ground known as *Ērakap*, by the river about 2 miles to the SE of the lonely rest house and telegraph store room of Hoshāb is a regular halting place on the direct caravan route connecting Panjgur with Pasni harbour. As this is crossed here by the equally frequented track leading down the Kēj valley from Kolwa and Jhalawan the Hoshab area, now practically uninhabited but for nomadic visits, may have claimed some modest importance even in later times.

Remains of Thale *damb*.—Permanent occupation at a prehistoric period was proved by the examination of the large and conspicuous mound of *Thale* *damb*

situated about 1½ miles to the south-east of the Hoshab rest house. It takes its name from the torrent bed of the Thale laur which descends from the hill range to the south and passes close to the west of the mound. The flat top of the latter rises about 50 feet above a branch of the Kej flood bed which skirts the mound on the north. The circumference of the mound at its foot is about 430 yards. Owing to the plentiful debris of stones I was inclined at first to take the mound for a natural ridge of decomposed rock though its position in a wide alluvial trough ought to have warned me against this assumption. But the experience subsequently gained at the numerous mounds of the Kolwa basin has since convinced me that as e.g. at the site of Kulhi, this deceptive appearance of the surface is due to the decay of ancient structures built with rough slabs of sandstone such as are easily brought from the foothills to the south. Remains of a roughly circular walled enclosure built with such flat stones and decayed to the level of the ground were traced all round the top as also of what seemed to be the foundation of a tower flanking the approach to the top from the south east.

Decorated pottery at Thale damb.—That most of the mound if not the whole, is composed of debris accumulations of very early date was shown by the abundance of superior red pottery to be picked up everywhere on the slope. Both the plain and the painted ware showed closest resemblance to the prehistoric ware found at Suktagen dor and in the deeper strata of Shahi tump as seen in the specimens of Pl XX. The plain potsherds showed often a fine dark red slip the painted pieces simple bands hachures and zigzags either on the same slip or on light red or buff ground. Just as at Shahi tump such simple painted designs were found combined with relief decoration of sharp edged ridges either in straight or in wave lines. Fragments of perforated pottery or with simple incised patterns were also frequent. The only piece of grey ware was of a thick hard body decorated with ridges in relief just like the fine bowl Sh T m 3 (Pl XVI) found low down at Shahi tump.

Decorated potsherds of the kind just described were particularly frequent on an embankment resembling a counterscarp. It could be traced for about 120 yards curving round the western foot of the mound and separated from it by a fosse like depression 20 feet wide. A fragment from a bowl or pyx Thal 4 (Pl XX) found here shows a row of running mountain sheep or ibex. The only mark of occupation continued into historical times is the fragment of a large vessel having a handle and bearing a thick blue glaze much corroded. I believe that if an adequate number of diggers could be collected from the little oasis of Sam some 30 miles down the Kej valley trial excavation at the Thale damb would yield interesting results. About half a mile further up the left bank of the river lies the smaller mound of Ekup about 20 feet high and 60 yards across on the top. Here two outlines of walls built as at Thale damb could be made out on the surface and painted potsherds of early type piled up.

The tract of Kolwa.—The tract of Kolwa for which we set out from Hoshab on 28th February after transferring all spare *in primis* to camels, comprises a broad stretch of open valley ground bordered by the Central Maran range in

the north and the Coastal Range in the south. It extends in continuation of the main Kej valley from south west to north east for a distance of about 100 miles with an average width of about 10 miles between the foot of the hills. Water sheds almost imperceptible to the eye divide Kolwa into four hydrographically distinct areas. While the south western end above Hoshib is drained by the Kej river and the opposite extremity about Anaran by the Mashui river, a tributary of the Hingol the major portion in the centre consists of two drainageless basins known as Kap and Mariah respectively.

Cultivation in Kolwa—Apart from certain comparatively limited areas within these basins which in years of good rainfall are temporarily covered by floodwater but otherwise salt encrusted wastes with scanty scrub most of the alluvial soil at the bottom of this wide trough is potentially fertile and capable of dry crop cultivation. But owing to the precarious nature of the rainfall, the scantiness and semi-nomadic ways of the population and similar causes such as want of manuring only a small portion of this great area of arable land is annually under cultivation. Irrigation is limited to a few insignificant patches of ground. All the same Kolwa is famous for its production of barley. In years of fair rainfall its produce is an asset of great importance for the whole of Makran and attracts harvesters in their hundreds from distant parts of the country to share in the yield.

Significance of numerous ruined sites—It is necessary to keep in view the physical features and present economic conditions just briefly indicated if we are to realize the significance in a geographical and antiquarian sense of the numerous ancient sites revealed by a rapid survey of Kolwa. More than anywhere else in Makran a comparison of the observations gathered at these sites with present day conditions is bound forcibly to draw our attention to the question as to the cause or causes which alone can satisfactorily account for so great a change since prehistoric times. The importance of this question from a wider point of view will justify a full record of those observations even though it was only at one site that practical considerations allowed me to test them by excavation.

Routes through Kolwa—Kolwa is traversed in its whole length by two main routes. One leads along the foot of the hill range to the south the other some what more devious keeps to the north of the Kej and skirting the gorges of the northern hills successively passes the areas of Khushkaba cultivation to which the torrent beds descending from them carry flood water after adequate rainfall. The motor track keeps mainly to the northern route and as the majority of the old mounds seemed to be situated in its vicinity I decided to follow it by short stages. Such sites as were reported to be near the southern route were to be visited as far as time and distances would permit by striking across the basin from those stages. The choice of the latter was largely determined by the chances

<sup>1</sup> The Motor Route is shown on the map.  
 Statistical notes.

of finding drinkable water in recently formed water holes for owing to the rain fall of the preceding year having been poor in Kolwa the water to be found in wells near the usual camping places of the semi nomadic cultivators proved too brackish for ready consumption by outsiders. That I was able to carry out this programme within the available time and with much archaeological profit was due chiefly to the thorough local knowledge and unflinching practical intelligence of Naib T. J. Muhammad. I am greatly indebted to him for the help he gave during my work in Kolwa and the Mashkar tract of Jhalawan.

**Remains near Marastan**—The first of the sites in Kolwa was reached soon after crossing the watershed dividing its main basin from the Kuj drainage. There on a scrubby plateau at a distance of some 23 miles from Hoshab the road passes a roughly oblong enclosure measuring about 60 by 45 yards formed by what looked like low decayed ramparts of clay and stones. The enclosure nowhere more than 8 feet in height is covered with plentiful potsherds of old look the comparatively few painted pieces showing decoration with simple black bands or wave lines of the type common on the painted ware of the Thale dumb and Pak mounds. The cultivated patches near by belong to Marastan.

**Mound near Pak**—After proceeding two miles further by the road I visited an interesting mound situated about six furlongs to the south east amidst fields belonging to Pak. It rises like a steep hillock to a height of over 30 feet above the alluvial plain. Being thickly covered with stones and detritus it might at first sight be mistaken for a natural formation. But its artificial origin was soon proved by the layers of clay full of potsherds disclosed in an eroded ravine. Broken pottery unmistakably ancient both plain and painted was found in abundance all over the slopes and also on terrace like ground extending some 100 yards further to the north and east. The mound proper measures about 100 yards in diameter at its foot. On its top, about 25 yards across remains of an enclosing wall about 3 feet thick could be traced. It was built with small flat stones undressed but carefully set in courses. Erosion due to drainage towards the south had produced a hollow within the enclosed space on the top and here wall portions with masonry of the same type belonging to the inside of a small quadrangular structure were exposed to a height of about 3 feet. A drainage channel had cut through the south eastern edge of the top to a depth of over 5 feet and had bare a well built wall of the same construction. It was from this cutting that the potsherd Pak 1 (Pl. XX) was extracted. Its raised ridges painted black resemble those of decorated ware from the lower layers of Shahr-i-kump. Also on the northern and north western slopes wall foundations with similar masonry recalling that on the Kargushika mound of Nag crop out on a level about 7 feet below the top.

**Painted pottery of Pak Mound**—The abundance of pottery of superior make painted in black either over a fine dark terracotta slip or direct on the red buff or pinkish ground was striking. As the specimens (Pak 213) reproduced in Pl. XX show the patterns include motifs with hachures multiple squares chess

boards Sigmas, etc., familiar from the chalcolithic sites of Zhōb, Lōralai and Sīstān. But in addition there are pieces like Pak 2,12,13, where the curving elements of design introduced are distinctly reminiscent of the style common on Nal pottery. This relationship is supported by the fact that in pieces like Pal. 10,11,13 parts of the design are filled in solid with a second colour, in this case dark purple. This additional colour was applied before firing as all the ware found here was obviously made for ordinary use. Of the grey ware so common at Parōm and Shāhi tump only a few fragments were picked up, as also of an alabaster cup. A few little pieces with dark blue glaze might suggest the possibility of occupation extended into or resumed in, historical times. But judging from their rarity and the character of the masonry on the very top of the mound it is more likely that they belong to imports or date from occasional visits like a small fragment of China which was also picked up here. The same may apply to the small fragment of a black glass bangle showing multicolour applique like the bangle fragment found at Suktagēn dōr.<sup>3</sup> The only find of metal is a needle-like object of copper, Pak 14.41," long, showing some decoration round the middle.

Judging from its size and its ceramic remains the Pak mound is likely to have been formed by prolonged occupation in prehistoric times. I therefore regretted that the difficulty in securing labour in this neighbourhood and regard for the available time would not permit of trial excavation, such as might well repay a future explorer.

**Gate-dap mound**—From the solitary blackish well of Gate where we halted about 3 miles further on the road, I visited on the morning of February 29th the mound known as *Gate-dap* about 1 mile to SSE. It lies amidst occasionally tilled fields close to the dry bed of the Gate kaur and takes its name from it. The mound is about 25 ft high and measures, as the rough sketch plan in Pl. 8 shows, about 120 yards in diameter. At the south western end of its top it bears a modern enclosure with a kind of keep, said to have been built by the grandfather of the present owner of the neighbouring land. The walls are built with stones taken from the debris of early structures on the mound and laid after the fashion now prevailing in Makran, slanting sideways to right and left in alternate rows. Remains of old walls with well laid courses of flat stones like those of the Pak mound crop out at different levels. The corner of such a wall was cleared from a 10 feet level on the south western slope to a depth of about 8 feet. Above it on the slope lay a thick deposit of ashes and refuse, evidently recent.

**Painted pottery of Gate dap**—The potsherds, both plain and painted, which are found in plenty all over the slopes amidst the debris from stone walls, clearly prove occupation of the site during the same prehistoric period as at the Pak mound. The painted ware agrees so closely with that of the latter in design, colouring and shape that reference to the specimens, G.D.I. 8 shown in Pl. XX, may suffice. The resemblance to the painted pottery of Nal

<sup>3</sup> Cf. above p. 61

is striking here too. The fragment G D 1, which retains rim and bottom would permit of the reconstruction of the whole open mouthed jar. That occupation, however, may have continued here longer or been resumed is suggested by more frequent fragments of glazed ware including two pieces in greenish grey and dark red which may be mediæval also by the fragment from the mouth of a pot, G D 16 (Pl. XX) coarsely painted in purple with a design which recalls those found on similar rough ware from certain later sites of Lōralai and Pishin.<sup>1</sup>

**Mound of Segak**—From Gate day a ride of about 3½ miles to SSE brought me to the large mound of Segak situated on the southern Kolwa route. For the most part the bare alluvial ground crossed was found to be laid out into fields with earth embankments to retain water from rain floods. But with the exception of one or two, none of the large plots had been tilled since Kolwa had received but poor rain that winter. For the last half mile before Segak the ground was wholly uncultivated a waste of drift sand and tamarisk scrub. Quite as desolate was also the appearance of the 'village' of Segal. Its half dozen of dilapidated dwellings built with stones from decayed walls occupy the top of a large mound, the whole presenting a typical picture of the poverty and primitive conditions to be found in this 'granary' of Makran. The mound, as the sketch plan Pl. 8, shows measures at its foot close on 800 yards in circumference and is occupied on the western and higher portion of its top by the remains of a small fort. Its completely decayed walls form an irregular pentagon about 60 yards long on the longest side. On the north this ruined circumvallation stands to a height of 39 feet from the foot of the mound. Outside it on the slope to the south an ancient well has been exposed by digging, apparently recent. At a depth of about 6 feet from the surface carefully built walls about 5 feet high can be seen lining a shaft circ. 6·7 feet square. In them courses of large roughly dressed slabs alternate with others of small flat stones. Potsherds strewn the ground to the south for some 120 yards from the foot of the mound.

**Painted pottery at Segak**—What little of painted potsherds was to be found on the slopes of the mound and beyond was all of the same type as at Pak and Gate day. Among the specimens, Seg 1-6 reproduced in Pl. XX, a few with animal figures, including horned mountain sheep and the head of a bull, may be noted. The relief decorated fragment, Seg 5, seems to be part of a stand and of later date. It was curious to note that the modern occupants of the mound know no pottery whatever, having only skins for water and wooden vessels. The same is the case throughout Makran with the vast majority of the people. Local production of pottery appears to be unknown nowadays even in the larger places, except that of a most primitive porous ware for keeping dates in.

**Rōdkin mound**—We camped that evening at Rōdkin about 4 miles to the north east of Gat. Next morning I first visited its mound situated less

<sup>1</sup> See *N. Baluchis on Tour* pp. 57, 61, 1, 74, 87, et

than a mile south of the road. It measures about 140 yards at its foot from east to west and some 80 yards across. Its top which is about 25 feet high, had, as is the case with almost all ancient mounds of Kolwa, served as a place of safety in modern times. The same had probably been the case earlier also since troubles had but rarely ceased in Makran after the Baluch occupation. A modern wall built with stones from the debris covering the mound encloses an area of some 33 by 40 yards on the top. Within it erosion had exposed the top courses of a well built ancient wall. This was cleared during the day by the few men who could be collected in the neighbourhood to a depth of some 6 feet without reaching the foundation. The masonry consisted of courses of large roughly dressed sandstone slabs up to 20"×12"×10" alternating with triple courses of small flat stones about 3" to 4" in height, all carefully set in mud plaster. Towards the southern end this wall (Fig 39) showed a small opening, about 14 wide, which had its top closed by overlapping courses and apparently served as a window. The painted potsherds found plentifully on the slopes mostly showed decoration of the Nāl type, as seen in the specimens Rud 12 (Pl XX), some blue glazed fragments point to later occupation. The small fragment of a dark clay ornament is of interest on account of the delicately painted enamelled surface and deserves expert examination.

**Mound of 'Old Balōr'**—From Rūdhan I proceeded to the south east in order to visit the mound known as Old Balōr and situated on the southern route. The ride of some 6 miles led first past embanked fields abandoned for a long time and then across a bare expanse of clay with scattered tamarisk bushes marking approach to the western fringe of the barren Kap. Finally crossing a belt of thick tamarisk growth amidst drift sand we found the mound. It is about 20 feet high and about 80 yards in diameter at its foot. The top is crowned with remains of ruined walls and towers evidently modern. It also bears a small mosque with walls of sun dried bricks which wind-erosion is undercutting. Potsherds mostly plain and of no ancient type lie thick on the slopes and around the foot of the mound. The painted fragments do not show patterns of the Nāl type, but mostly designs coarsely executed in black on red ground and bearing a late prehistoric look, as seen in the specimens Bal 23 (Pl XX). A comparatively late date of prehistoric occupation is suggested also by two terracotta relief fragments. One, Bal 4 (Pl XX) apparently belonging to a lid, shows on either side of its top what may be taken for a ram's head with eyes and mouth marked by small holes. the other seems to represent the snout of a pig, almost natural size. A terracotta fragment of just the same shape but better preserved was found at the Spet-damb of Jhan. There also the painted pottery indicates late prehistoric occupation.\*

**Ashāl mound**—Finally we made our way back due north across a bare clay flat forming part of the 'Kap' and reached the mound of *Ashāl* close to the south of the road. It measures some 90 yards in diameter and rises to a height of about 25 feet. Here, too, a modern walled enclosure about 40 yards

\* See below p 125.

square crowns the top. All the fragments of painted pottery found on the slopes and top showed patterns characteristic of the N 1 type as seen on the specimens Ash 15 (Pl XX). Among the unpainted ware which also was of early appearance there were some pieces of fine grey clay. Of distinctly later pottery only one blue glazed fragment was found. From here a drive of eleven miles brought us past the fields of Drindar to that night's camp near the mound and Ziarat of Madak Kalāt.

### SECTION II—FROM MADAK KALĀT TO GUSHĀNAK

Mound of Madak Kalāt—The top of the conspicuous large mound of Madak Kalāt (Fig 33) some 50 feet high bears the ruins of a fort which in modern times had served as the stronghold of the Kandah chiefs in their struggle against the Naushirwanis. Continuous occupation seems to have overlaid here a prehistoric mound with thin deposits of later periods down to modern times. The crumbling walls and towers of the fort are built with undressed stones which are likely to have largely been taken from older structures. But no early masonry remains such as found on the previously described mounds of Kolwa could be traced on the surface. Most of the potsherds found on the slopes and the ground below are of plain coarse ware. Among the painted ware only comparatively few pieces showed geometrical patterns of the early chalcolithic type executed in black over red ground. The majority consisted of fragments of later pottery coarsely decorated with designs in brown or purple over a buff slip as seen in Mad 1 (Pl XX). Glazed pieces amongst them some with arabesque ornamentation manifestly medieval were frequent. Late too are an iron arrow head and numerous fragments of coloured glass bangles picked up here.

Sahar Kalāt—*Solar Kalāt* which I visited next at a distance of about 4½ miles to the north east proved an isolated and steep rocky ridge occupied on its narrow crest by a small modern fort. This was held until a couple of generations ago by the Kandah chiefs. The position is a strong one by nature and commands the caravan route from the harbour of Qumra to Panygur which here enters the hills northward. The scarcity of potsherds of any kind shows that occupation was limited here to times of trouble.

Mound of Hor Kalāt—Passing across stony flood beds of the Sahar Kaur and then through close jungle of old tamarisks with occasional clearings for cultivation we returned to the road. Following this for about 2½ miles eastward the flat-topped mound known as *Hor Kalāt* was reached. The roughly built enclosure and habitations on its top had been occupied in recent times by local Naushirwan landowners including Balōch Khan a chief leader in the rebellion of 1903. Owing to fresh trouble which the latest occupant had given the place was burned down four years ago under the Political Agent's order. The mound measures at its foot some 120 yards from east to west and about half that across and rises to about 20 feet. That it dates back to chalcolithic times was clearly proved by plentiful painted fragments of the N 1 type which could be picked up on the slopes. Among the specimens Hor 1 is shown in



Pl XX two Hor 13 with figures of bulls claim some interest. It deserves to be noted that on a number of fragments a dark purple colour is added to fill certain portions of the pattern otherwise executed in black. No later painted ware could be found here.

Mound of Jaren.—It was different at *Jaren* a haralet some 7 miles farther where a smaller mound about 60 yards in diameter was examined less than a mile to the south east of the road. Here too the top of the mound at a height of about 25 feet bears a modern enclosure of rough stone walls. The fairly plentiful debris of painted pottery found on the slopes includes fragments with patterns of the Nal style (Jar 1 Pl XX) as well as some black on red ware which may be older. A later date may be ascribed to pieces of coarse body with designs roughly painted in dark pink or brown over a buff ground and perhaps also to some black on red pieces showing voluted scrolls (Jar 2 Pl XX) such as met with before at Zayak.


Zik mound.—March 4th was a day of interesting survey work but made trying by a violent gale which following the short dust storms of the preceding few days blew with increasing strength until nightfall and then developed into a cutting Gurich. The mound of *Zik* at which we camped 6 miles to the east of Jaren was the largest so far seen in Kolwa. As shown by the rough sketch plan (Pl 8) it stretches for about 300 yards from NE to SW and measures where widest close on 200 yards. Its height about 20 feet along the eastern portion rises to about 30 feet towards the west. There rough stone walls built with materials evidently from earlier structures enclose an area measuring within about 30 by 46 yards. Inside this are to be seen ruined quarters constructed with mud bricks. They stand on a terrace (Fig 36) raised with large roughly dressed slabs of stone which have been taken from ancient walls and show sizes up to 2½ feet in length. Lines of such walls crop out on the surface at different points of the slopes. *Zik kalat* is known to have been tenanted by Jadgal Mirwan and Naushirwan families who successively fought over and held the land in the neighbouring part of Kolwa.

Polychrome painted pottery.—Plentiful painted pottery (for specimens, see Zik 11 Pl XXI) found all over the mound proves that the occupation of the site goes back to the Chalcolithic period. Most of it exhibits characteristic features of the Nal type. In the unbricated pattern of Zik 1 in the design with a bull Zik 6 in Zik 7 showing part of a fish also in Zik 8 the use of a dark purple in addition to black outlines over buff ground renders the decoration polychrome. Some pieces like Zik 2 and Zik 9 from a large thick vessel of which other fragments were found may represent an earlier type. The leaves on Zik 5 recall a motif frequent on the painted pottery of Dabarkot<sup>1</sup>. Lanks with the deeper layers of Shah tump are furnished by two fragmentary bull figurines (see Zik 11) and a few pieces of fine plain grey ware. No glazed ware was found on the surface except two potsherds both of which look modern. Remains of ancient stone walls in the shape of lines of massive masonry cropping out on


<sup>1</sup> Cf. V. Balch and To R. XIV. XV. There is seen also a D 50 D 51 and 30 an ornamentation similar to that of Zik 9.




TO ON N O N O T RO B V



I T P



IC RO D P V NO SOUTH I



GIU P D C V C R C OU



the surface, could be traced at more than one place of the slopes, especially towards the east. The impression conveyed by these remains and the great size of the mound was that Zik Kalat marked the position of an important prehistoric settlement. It would deserve prolonged investigation thereafter.

March towards Malar.—In the vicinity of Zik there starts a low and much decayed chain of rocky ridges striking from south west to north east across the watershed which divides the damageless portion of Kolwa from the one draining towards the Mashkat river. To the south of this chain lies the Marrih depression liable to inundation and affording fair grazing, the road skirts it by keeping to the southern foot of the hills. No mounds were known to Nub Tay Muhammad on this side nearer than Gushanak. So I decided to let the camp proceed by the road to the vicinity of the latter, while I myself turned to the north east towards Malar, an area with scattered cultivation near which mounds as well as Gabar bands were reported. These were the first of which information had reached me since entering Malran and this fact together with the abundance of such old embankments in Jhalawan which we were now approaching made me specially eager to examine them.

'Gabar bands' near Malār.—We came upon these first two Gabar bands after a ride of close on 7 miles up a wide scrub covered valley crossed by numerous drainage beds. The Gabar bands descend from the northern foot of the above mentioned low hill chain at a point about 1½ miles to the NE of the height marked with 2428 feet on the map. They consist of dams rising to about 4 feet above the ground and faced westwards with a massive wall of large rough stones, behind this a sloping bank of earth and gravel adjoins on the east. The first band was clearly traceable for about 40 yards from where it starts in continuation of a low rocky ridge running from south to north. The second dam of just the same construction and bearing was found about 300 yards further to the east and could be followed for some 100 yards. Both bands end abruptly above a shallow trough in which drainage from the plateau collects on its course towards Zik. Between the two bands extends a fairly level area of clay overlaid by thin gravelly detritus but showing also some low banks of bare clay curiously like miniature 'Yardings' in the Taklamakan or Lop desert. Here and there scattered pieces of very coarse pottery looking as if hand made could be picked up within the enclosed area. No trace could be found of any transverse dam such as could have served to retain and bank up rain water descending the slope from south to north. Nor were such transverse dams as might be needed to form cultivation terraces found between the Gabar bands met further north.

Purpose of Gabar bands.—There can be no doubt whatsoever that these dams and other similar ones subsequently passed near the southern slopes of the same hill chain were constructed with a view to facilitating cultivation. Where transverse embankments in conjunction with such bands follow the

---

A mound was said to exist at Chambor, a village on the southern Indian route and like that of Segah to be occupied by Ishabations. As the distance to it from our Zik camp was over 8 miles I could not spare time to visit it.

line of the slope as is the case at various Gabar bands of Mashkan to be described below the purpose of securing adequate watering for the terraces thus formed is quite clear. Where such transverse dams are absent as here it appears to me highly probable that the object of the builders was to control the drainage descending the slopes to assure its uniform distribution over the lower ground and to prevent its being prematurely lost in deep cut flood channels. In other localities to be mentioned further on Gabar bands were constructed with the unmistakable object of forming reservoirs where water would be stored in order to irrigate the land lower down during dry periods of the year. Elsewhere Gabar bands may have been intended to promote the deposition of fine detritus on rocky soil thereby rendering otherwise barren ground fit for cultivation as has been rightly suggested by Mr. Hughes Buller in an instructive note dealing with some of the Gabar bands of Jhalawan<sup>3</sup>.

Study of Gabar bands.—The subject is a very interesting one from both the antiquarian and geographical points of view. It deserves to be systematically investigated if possible with the assistance of a competent irrigation engineer and on the basis of adequate meteorological data concerning the local rainfall. No such special study could be attempted in the course of my tour. I shall therefore have to restrict myself here to the record of what I was able actually to observe at the different Gabar bands met on my routes leaving the study of the interesting general questions raised to some competent enquirer of the future.

Small circular mound.—Within about 8 feet of the point where the track to Malar passes the westernmost of these 'Gabar bands' there stands a small circular mound about 9 feet in diameter and about 5 feet high built with rough stones outside and enclosing a core of earth. Large stones lie on its top. At first the little structure suggested a burial cairn but it looked too well preserved to suggest great antiquity and certainly no other similar structures could be found anywhere near. Nor did I come across them at other Gabar bands though told of their existence elsewhere. Popular belief I was told takes them to mark places where criminals were buried alive. There was neither time nor labour available to open this little structure. But one exactly similar found by the side of the road from Khozdar to Wadh and searched proved to hold nothing but earth and rubble. Possibly these small mounds may have marked boundaries as was stated by my informants at Wadh.

Turning from here to the north we met half a mile further on three more dams of the same type all running east to west and ending by the bank of a drainage bed which descends from the rugged hill range to the north. These dams stood to a somewhat greater height and were separated from each other by distances of from about 100 to 120 yards. The earth ramps of the second and third dams face north and south respectively.

Kallag mound.—About two miles to the north of this point beyond a wide belt of flood beds there rises the mound known as *Kallag* from a hamlet once situated near it. It occupies a natural terrace of detritus between two

<sup>3</sup> Cf. *Jhalawan Gazetteer* 1901, pl. 53 and Mr. Hughes Buller's paper 'Gabar bands in Baluchistan' there quoted from *Report of the Archaeological Survey of India* 1904-5, pp. 193-201.

beds which meet close to the west of it and measures some 100 yards along its southern foot. On the north side its top stands to a height of about 40 feet with terraced like portions extending on a level of 20-30 feet to the east and south. On the western portion of the top the remains of massively built stone walls can be traced. Masonry with regular courses of large roughly dressed slabs crops out on the surface for about 50 yards on the south and 40 yards on the west the corner between the two lines being clearly discernible. By the side of plentiful plain pottery mostly of a coarse kind but little of painted potsherds could be found on the surface and those only of small size. Among them patterns both of the simpler geometrical type familiar from the chalcolithic sites of North Baluchistan and of the Nil type can be recognized. One fragment shows the peculiar mat-marking in relief on the outside which, as far as my observations in Baluchistan go is to be found only at the earliest of chalcolithic sites. But obviously a mound of this height is likely to mark a site of very prolonged occupation. No indication was found of such occupation having extended into historical times.

Mound of Cheri Malar—A ride of close on three miles eastwards across a desolate waste brought us to Cheri Malar one of the three small hamlets counted as belonging to Malai. This area of scattered cultivation lies on the flat watershed between the basin of Kolwa proper and the tract draining towards the Mashkai river the map showing for the central hamlet of Malar a height of 2241 feet. The mound known as *Kamar band* is situated about half a mile to the east of Cheri Malar and measures at its foot about 110 yards from east to west and roughly half that across where widest. It rises very gently to a height of 20 feet on the top. At the south eastern foot of the mound remains of a wall 4 feet thick built with large rough slabs of sandstone could be traced on the surface for 10 yards another wall crops out a little higher on the slope above. Here, too the plentiful potsherds found on the slopes were almost all of plain coarse ware and the few painted fragments showed only simple bands. But as on two pieces an additional colour a dark purple is used besides black as frequently on pottery of the Nil type occupation down to later chalcolithic times may be assumed.

Chahi damb mound—A second and more extensive mound lies half a mile further to the east amidst fields it is known as *Chahi damb* or else as the mound of Dil Murad from the collection of wretched palm-leaf huts which are found on its top. Its foot on the east measures some 120 yards on the south about 100 yards. Though only 15 feet or so high the mound is of interest, as it bears in several places remains of walls of considerable length and solidity. On the northern side of the top a wall 7½ feet thick can be traced for 25 yards on the surface. The rough slabs composing it measure up to 3 × 1 0" × 9". Foundations of a massive square structure rise near the north eastern end of this wall. At the other end of the wall too structural remains with walls 4 feet thick are exposed. Here the roughly dressed slabs show sizes up to 3 by 1½ feet. The few painted potsherds which could be found here exhibit only very simple geometrical designs. A small fragment of fine grey ware showing a painted

scroll in black deserves notice and so also a piece of good red ware with parallel sharp-edged ridges such as were found on pottery from the lower strata of Shām tūmp. Both point to occupation from an early period. Judging from the similarity of the surface finds at the Kallag and Malar mounds there can be little doubt about their marking sites inhabited simultaneously. Their size and close vicinity clearly indicate that the Malar area with its expanse of potentially fertile alluvial soil maintained a comparatively dense population at that early period.

Remains of Singī kalāt—A site very different in character was revealed when after following for  $2\frac{1}{2}$  miles a deep cut flood bed which drains the Malar plateau to the south-east we arrived at Singī kalāt the stone castle. Not far from the point where this bed cuts into the low hill cham which as already mentioned stretches south of the plateau, there is found a remarkable natural fastness. As the sketch plan in Pl. 8 shows it is formed by two precipitous ridges of bare rock which meet on the north-east at a narrow neck and thence descend like the two sides of an isosceles triangle to the left bank of the deep cut flood bed. The two ridges one facing approximately north, the other south-east fall away outside their crests with vertical and in places overhanging cliffs of sandstone steep detritus slopes below these run down into narrow eroded gorges. On the inside the two ridges dip at an angle of over  $30^\circ$  into a small trough. The lower end of the base of the triangle is closed by a ruined wall of some 140 yards in length. It is built along a rocky ledge to which an alluvial terrace slopes up gently from the left bank of the torrent bed; this is here close on 60 yards wide. The ridges attain their greatest height near the apex of the triangle and here a neck some 125 feet above the torrent bed was defended by another and much shorter wall. This owing to the steepness of the slopes on both sides has badly decayed. The walls are built with large undressed slabs of sandstone quarried here on the spot, as were perhaps also the stones used in the construction of the massive walls at the Malar mounds.

Ruins within fastness—The crest and inner slope of the northern ridge are covered with the ruined walls of single roomed dwellings built with rough slabs up to 3 feet or so in length and over 1 foot high. In one of these ruins the walls still stand to a height of 5 feet. No clay or mortar is found between the slabs but small flat chips of stone were used roughly to fill interstices and equalize courses. On the inside of the south-eastern ridge too there are remains of ruined dwellings clinging to the slope just like those I found on the even steeper slopes of Raja Gira's castle above Udgirim in Swat. Within the wall at the base of the triangle there is found a well about 5 feet in diameter now filled with debris but still showing stone lining at its mouth.

Where the foot of the northern ridge descends towards the junction of the gorge with the flood bed the natural line of defence provided by its cliffs is continued by a wall. This is decayed on the slope but below where it flanks the alluvial terrace it is remarkably massive and well preserved for a length of 52 feet (Fig. 3). It stands there to a height of 12 feet above the present bottom of the Nullah and is no less than 13 feet thick. Its western end is protected by a kind of semi-circular bastion which projects 6 feet beyond the outer face of the

wall and measures 10 feet in diameter. The ground level is here likely to have been considerably raised by alluvium. The great thickness of this wall as well as the special strengthening provided at its end are probably to be accounted for by the fact that the wall here was intended not merely to guard approach to the alluvial ground below the base of the hill fastness but also to protect it from erosion by floods.

**Purpose of hill fastness**—From the natural strength of the position of Singkalat its distance from arable ground and the close occupation of the interior by ruined dwellings it may be safely concluded that the fastness was meant to afford safety to a large number of people during times of trouble. Only systematic clearing could show how far back the construction of the defences and dwellings dates. Among the painted pottery fragments of which a fair quantity was picked up notwithstanding the trouble caused by the sand storm blowing at the time, some pieces with geometrical patterns in black on red ground look early Chalcolithic. The majority with roughly executed designs in pink or purple over buff ground seem to belong to late prehistoric ware. It is curious to observe that a few of the latter pieces show on the inside the impression of textile materials obviously from the surface of moulds.

**'Gahar bands' south of hill chain**—A ride of some two miles due south through much eroded hills took us across the hill chain to the motor track skirting the foot of the latter. On passing along this for about 2½ miles north-eastwards to where the camp had been placed by the side of a water hole, I noticed a succession of half a dozen of 'Gahar bands' all descending at right angles to the strike of the hill chain. They could only have served to control the drainage and to distribute it uniformly over the alluvium of the glacia. This is no longer cultivable now as the uncontrolled drainage gathers in numerous deep cut Nullahs which unite in a still deeper flood bed. This carries the water away towards the Mashkai river without affording a chance for its use on the glacia.

**Rocky hill of Gushanak**—The storm blowing all day developed during the night into a violent cutting Gurich which nearly brought our tents down. The bitter cold of the morning following after the heat of the weeks spent in the Kej valley and Kolwa made one realize the trying nature of the Malran climate. Marching about 3 miles SSW across fields left untilled owing to the years' deficient rainfall I visited that morning *Gushanak* one of the chief villages of Kolwa. It is situated on the southern caravan route and counts some fifty permanently occupied huts. It lies at the foot of a steep conical hill which is about 150 feet high and conspicuous in its complete isolation. The rocky slopes of the hill make access to the small plateau on the top distinctly difficult on the north side they are altogether impracticable. The top must have at all periods provided a very strong defensive position, and the fortified quarters built there by the great uncle of the pre-late Mirwan Sirdar of Gushanak and now in ruin prove that it served as a place of safety down to recent times. The walls comprise masonry both of undressed stones set in mud and of sundried bricks.



Painted pottery on Gushanak hill—No ancient structural remains could be traced. But plentiful fragments of painted pottery, found on the top as well as on the slopes of the hill prove occupation since prehistoric times. As seen from the specimens reproduced in Pl XXII, different types of painted design are represented among them. Simple geometrical motifs black on red as in Gush 2, 3, are rarer than those more elaborate ones of Gush 1, 2 executed in brown on buff ground. The small fragment Gush 4 of superior fabric stands by itself showing a horse with rider, a subject not otherwise known to me among chalcolithic or later ware. Decoration of the Nal type, in polychrome execution, is found only on two fragments. In Gush 5 the pattern is painted in a brownish purple over a light terracotta slip. The broad band of purple above shows a very fine polish which is found elsewhere also on one or two pieces from this site.

### SECTION III—THE MOUND OF KULHI

After regaining our camping place we proceeded by the road to the mound reported near the cultivated plots of Kulhi. For a mile or so we passed along the foot of the last outlier of the low hill chain crossed the day before from Malat and there I noticed decayed 'Gabar bands' descending over the fertile alluvial slope. Between a few of them low transverse dams could be made out obviously intended to hold up the drainage for watering terraced fields.

Position of Kulhi mound—After about three miles the road brought us opposite to the mound of Kulhi. It is just in continuation of the line in which that chain of hillocks trends away to the south west. This position combined with the size and appearance of the mound might at first sight have caused doubt as to the artificial origin of the mound, so closely is its surface throughout covered with stones and what could easily be mistaken for mere detritus. Yet closer inspection soon showed lines of walls cropping out in numerous places all over the mound and on different levels. This together with the plentiful potsherds strewn the slopes made it certain that it was accumulation of debris which accounted for the height and extent of the mound. With a length of close on 400 yards from north to south and a maximum width of some 330 yards the *Kulhi damb* rising to 30 feet in height, is by far the largest of all the Kolwa mounds. The abundant use made of stone building material all of which must have been brought from a distance—none of it is obtainable anywhere nearer than two miles—also pointed to a site of importance perhaps the chief prehistoric settlement of Kolwa. The comparative vicinity of Gushanak held out hope of securing local labour without too great delay. So after a preliminary examination of the site I decided to spare time here for some test excavations.

Configuration of mound—The Kulhi mound (Fig 37) as the sketch plan Pl 9 shows is except at its southern extremity closely adjoined by cultivation. This is likely to have raised the ground level around the mound by the deposit

of alluvium and thus to have covered up traces of early occupation beyond its present foot. This is proved by the survival of a small area with remains of walls, potsherds and debris at a distance of some 120 yards beyond the north western foot of the mound (see sketch plan Pl 9). It has remained untilled for some reason and is separated by an earth embankment from the adjacent fields which lie on a higher level. The northern portion of the mound which is the higher one rising to a height of 30 feet, bears on its plateau like top a decayed quadrangular enclosure measuring about 60 by 50 yards. It is built with stones of small size and in its extant height 4.5 feet shows nowhere such careful masonry with regular courses as the ancient walls brought to light by excavation. That it is a small fortification of later though not of modern date can scarcely be doubted. Outside its wall lines of ancient structures are exposed at numerous points on this high portion of the mound. In the sketch plan, Pl 9 only those were marked which could be fixed by the plane table. A large crater like depression found outside the northern face of the enclosure probably marks the position of an ancient well. A smaller and perhaps more recent well is found at the south eastern foot of the mound.

Later burial cairns.—Evidence that the mound had in its northern portion assumed its present appearance already in pre Muhammadan times is supplied by the presence of some small cairns in the shape of stone circles to be found in at least two groups outside the enclosure. They were burial cairns of the same type as first seen at Moghulghundar Gatta etc. On opening four of them at the point marked III on the sketch plan we found within the circles loose earth and, mixed with this small fragments of calcined bones some ashes and pieces of plain pottery. These cairns were on the same level as the remains of walls marking small ruined structures within a few yards of them. On clearing these it was found that these wall remains rose only 1 or 1½ feet above the roughly flagged floor of small rooms one measuring 6 feet square with a little recess by its entrance. The higher portions of the walls must have completely crumbled away before the burial deposits were made. This complete decay is explained by the very friable nature of the shaly stone material in the walls and by the debris lying exposed to erosion on the top of the mound.


Southern portion of mound.—The southern and lower portion of the mound is covered at elevations from 15 to 25 feet with low heaps of stone debris from decayed structures. Lines of walls built with regular courses of roughly dressed slabs emerge on the surface in numerous places. Where these lines of walls are sufficiently clear to be measured and indicate the presence of buildings of some size, they have been specially marked to scale in the sketch plan. Where the debris obscures the outlines of the structures underneath the latter are marked only by symbols. Surrounded by these hillocks of debris there lies a shallow depression in the centre of the southern portion of the mound. It probably marks a locality within the site which for some reason remained more or less clear of buildings. The drainage collecting in this depression after rainfall accounts for the presence there of some old trees and of scrub. The same is observed within the enclosure on the northern portion of the mound.

Abundance of painted potsherds on surface—Potsherds, plain and painted strewn the slopes throughout but are particularly plentiful on low terraces below those little hillocks where structural remains are exposed. The greater ease with which denudation proceeds on ground clear of ruined structures may explain this or else those terraces may have once been occupied by ancient rubbish heaps. The painted potsherds picked up on the surface bear mostly a very early look, their simple geometrical patterns often recalling chalcolithic ware of Zhob and Sistan. Designs executed in black over red ground greatly prevail but others in brown, pink or purple over buff are found also. The specimens Kul 113 reproduced in Pl. XXI XXII XXIII illustrate the most characteristic types of decoration. Among the motifs may be specially noted rows of adjoining heart shapes (Kul 5), triangles divided by Sigmas (11), fringed bands (12), vandykes solid or hachured (6). Of animal figures there are found rows of large horned mountain sheep (4), the well drawn hind part of a bull (13). Pieces decorated with sharp parallel ridges (3) were found also in the lower strata of Shahi tump and at Kolwa sites previously described. The fragment from the bottom of a large dish (1) shows a stamped wave pattern of elegant design.

Terracotta figurines on surface—The links which these first finds of decorated ceramic ware from the surface suggested were fully confirmed by a number of terracotta figurines also collected there. Fragments of humped bulls, plain or painted, of which Kul 14 (Pl. XXII) is a specimen closely correspond to those so plentifully found low down at Shahi tump. In the roughly executed female bust Kul 15 (Pl. XXII) it is easy to recognize a representation of the figure of the goddess already familiar from the chalcolithic sites of Zhob and Loralai as well as in a superior form from Mohenjodaro.

Trial excavations started—Over night arrangements were made to collect labourers and by the morning of March 5th it became possible to start trial excavations with the help of a small contingent of men and boys mainly brought from Gushanal by the local Mirwan landowner. In the course of our work at the site which extended up to March 11th this number gradually increased to a little over a hundred of course without being accompanied by a corresponding increase of efficiency, the men of Kolwa being known for their general slackness. The remains I selected for the first clearing were those of a small isolated structure of which the walls forming a rectangle could be traced on the surface on the south eastern side of the mound at a level of about 15 feet. Its position is marked with I in the sketch plan. Fig. 38 shows the ruin after partial excavation as seen from the north.


Walls of structure I—Trenches dug along all the four sides laid bare the outside walls of a building measuring 31' 3" on its longer sides approximately facing north and south and 19' 6" on the shorter ones. These walls 2 feet thick are built with regular courses of roughly dressed slabs. The height of the courses varies as shown by the diagram in Pl. 9 which reproduces the masonry in a portion of the east wall. Here and also in the outer face of the south wall one course set about 12 feet from the ground is composed of slabs of a harder stone, apparently sandstone 1' 4" high whereas the material used




0 0 0 0 0 0 0 0 0 0



0 0 0 0 0 0 0 0 0 0



0 0 0 0 0 0 0 0 0 0



0 0 0 0 0 0 0 0 0 0



throughout the walls elsewhere is shale. This has invariably weathered badly and the decay of this friable stone as well as of the mud plaster thickly used between the courses accounts mainly for the composition of the mound. In clearing the trenches along the outside walls of the structure it was found that the debris outside their faces consisted for the most part of pieces of shale varying from small flakes to large slabs which had fallen from the superstructure.

**Finds in trenches outside walls**—Before proceeding to describe the observations and finds made within the small building, I may conveniently record what the preceding clearing of the trenches along the outside walls brought to light. These trenches around the east south and west wall struck a flooring composed of large roughly fitted flags of shale and about 4 feet wide. As shown by the section on the line CD (Pl. 9), this flooring or pavement lies on a level about 1½ feet below that of the floor level found within the rooms but only approximately determined. On the west side the enclosing wall was found to rise 7 feet above the level of this pavement. On the east the wall survived only to a height of 4½ feet no doubt owing to increased exposure on the declivity of the slope. Along the north side we found no pavement but as seen from the ground plan of I, a series of walls of varying thickness separating small rooms and recesses in 1 and II.

**Later walls added**—That these dividing walls starting from the northern face of the building are later additions and of different date is proved by their starting on varying levels. Evidently they were built on to the structure after debris had begun to accumulate around it. Their masonry is of the same type as in the walls of I but they rest in each case on debris from fallen portions of the wall behind. The two walls jutting out between 1 and II are placed at a slight angle against the north wall of I. The purpose of the small space *a* enclosed by them and of the still smaller one *c* at the north eastern corner is uncertain. The thought suggests itself that they may have served for storing grain like similar walled recesses found in ruins of Buddhist times in the Peshawar and Swat valleys. Some support to this suggestion is afforded by a hollow grinding stone, of the type seen in Figs 41, 42, which was found in the recess *a*. From the recess communicating with *b* two steps formed by large flag stones led up to what appears to have been a cross wall on a higher level.

**Body buried to south**—Later additions to the building were traced also at its south western corner. There was found a thin wall continuing the south wall from a level well above the pavement, and a rough recess formed by three large undressed slabs placed against that wall at a level of 4 feet above the pavement. Two lay at right angles to the wall at a distance of a foot from each other and a third across their ends. The purpose of the rough recess thus formed could not be determined. The burial of a body found opposite to the SW corner at a distance of about 3 feet and at a depth of 4 feet from the present surface level must have taken place when debris had already accumulated to a considerable height around the building. The head which was badly damaged while the trench was being cut lay approximately towards the north. The knees were drawn up and the arms bent towards the head.

Potsherds excavated outside I.—From the debris cleared by the excavation of the trenches a great quantity of potsherds both plain and painted was recovered. Judging from the place in which they were found it is safe to assume that most if not all of these fragments belonged to vessels actually in use while the building was occupied. The close agreement in fabric and decoration with the pottery from the interior of the building fully confirms this. Another relevant observation is that there is no difference in either ware or decorative style between the ceramic materials at whatever depth they were found in the several sections i vi. This clearly points to prolonged use of the same types of pottery. The abundant plain ware has mostly a strong body of well levigated reddish or light terracotta clay. Only a single fragment of dark grey ware was found while in the subsequently cut trench Kul V such ware was frequently met with. There were numerous perforated pieces and others showing relief decoration with sharp-ridged ribbing as seen in figs 41, 42 and common in the deeper layers of Shih-tump.

Painted pottery.—A striking feature of the pottery remains here brought to light is the great abundance and uniformly superior quality of the painted fragments. Their patterns are always executed in black over a light terracotta or buff ground. But in addition a dark red colour is often introduced in horizontal bands separating different zones of decoration. As the specimens reproduced in Pl. XXI show the motifs used are of a very varied character. By the side of simple geometrical motifs including hachured vandykes leafshapes simple or 'feathered' festoons etc (Kul I 12, 47, u 1 m 1 iv 1, v 1) there are found often combined with them stylized representations of plants and animals. In I 13 m 2, iv 2 we recognize conventionally treated trees, while by the short horizontally placed zigzags which appear by the side, above or below animal figures (I 126, iv 4, vi 1) grass or scrub seems to be symbolized. Among animal figures the most frequent are rows of large horned beasts shown in movement and probably representing mountain sheep or ibex (I 126, iv 3-4). In I vi 7 we may have a bull, with elongated neck as seen on the complete jar I viii 1 (see below). The strange big horned creature (I 16) with curved legs might possibly be mistaken for a large insect did its disproportionately small head not show a resemblance to that of the bull in I viii 1.

Decorative motifs and shapes.—There is much in the style of this painted pottery as far as the geometrical motifs are concerned to recall the decoration of chalcolithic ware from the North Baluchistan sites and Sistan. But the introduction of plant and animal forms and of an additional colour constitute a marked distinction. The same holds good as regards the funeral painted ware of Shih-tump. Very curious is the total absence of those curving and interlacing motifs which are characteristic of the painted ornamentation of the Nal type. Yet we find a distinct approach to the latter in the shape of the jars found more or less complete in the rooms vii, viii and also that suggested by the straight-walled fragment I m 2. On the other hand the very small bases of fragmentary cups such as I v 3, vi 1 are distinctly reminiscent of the shapes common at the Zhōb sites and also at Suktagan-dor.

**Terracotta figurines and miscellaneous objects.**—Among ceramic finds there remain still to be mentioned six terracotta figurines of bulls exactly resembling those from Shahr-i Kump and those brought to light in great number from the trench Kul V. Other small objects found in I vi are a copper nail (?) I 13 a with loop Pl XXII a bone needle some beads of stone including lapis lazuli a couple of fragments of bone bangles. Among a few small glass fragments it is interesting to find three pieces of glass bangles showing coloured decoration in relief or inlay. Like similar fragmentary bangles found at Suktigendur and Shahr-i Kump they are manifestly imports from a far more advanced region. Here their antiquity is attested by the depth at which they were found.

**Finds in room I vii.**—The trenches along the outside walls of the building had nowhere shown an entrance. So excavation had to be started from above. Walls dividing the interior into rooms could be traced on the surface. The first of these to be cleared was I vii occupying the south western corner (Fig 40). Here two large pots measuring respectively 22 and 24 inches in height and 22 and 18 inches in diameter where widest were found in the NE corner at about 3 feet below the surface. They evidently had been placed there to hold water. On about the same level there lay two more vessels of coarse plain ware.

A foot or so lower down there turned up the large piece of a vessel decorated with wave lines in relief shown in Fig 41. On a level of about 5 feet from the surface two painted jars were recovered I vii 4 & (Pl XLIII). One, I vii 4, with slightly concave sides is decorated below the shoulder with a row of large horned mountain sheep while the broad zone lower down shows two nondescript animals in movement as if stalking between branching trees. The painted surface has somewhat suffered by abrasion. The same is the case with the other I vii 5 the motif of hachured triangles alternately below and above a horizontal line and of hachured half ovals in the empty spaces between is one found also on the Shahr-i Kump funerary ware. On a level about 3 inches below these jars there was struck a thin layer composed of small stones in which no potsherds or other objects were found and which hence may be taken for the original rough flooring of this room. Its bottom lay about 1½ feet above the level marked by the pavement outside. As the walls show no opening anywhere it is certain that this like the other cellar-like apartments must have been entered from above probably by means of a wooden ladder. Remains of charred timber were found about a foot above the resumed floor and a small projecting ledge on the western wall at about the same height.

**Objects found in room I viii.**—The room I viii adjoining eastwards yielded a series of interesting finds. A large flat dish of strong red ware painted on the inside with a bold pattern of contiguous discs was found broken into many pieces at about 4 feet from the surface also part of another large vessel decorated with raised wave lines (Fig 42). A massive trough shaped grinding stone 1' 4" long 1' 4" wide and 11" high from the flat bottom and a flat stone roller 1' 3" by 1' 6" and 1½" thick shown in the same figure illustrate a method of grinding corn which Amir Taj Muhammad believed was still in use on the Oman coast. At a depth of 5½ feet and about 2 feet from the east wall there



lay on the top a large broken bowl and close to it a high perforated jar, also broken, I viii 3 (Pl XXV, also seen in Fig 42), and two small painted jars, I viii 1 2 (Pl XXIII, XXV), both damaged in antiquity. One, I viii 1, 5 high, shows on its slightly concave side two humped bulls in spirited movement separated by stylized trees. The decoration is painted in brown over a light buff ground. The other I viii 2, originally about 4" high, is made of fine grey clay over which the decoration is painted in dark brown. This has over most parts badly faded through damp. Its wall shows below a row of large horned animals (Ibex?) and above a band of balusters.

Find of bead necklace.—Within this jar there were discovered under a layer of ashcs and charred wood twenty seven elongated carefully made beads, measuring up to one inch in length, twenty one are of pinkish or white agate and the rest of a black stone. It is evident that they all formed part of a necklace which was hidden here on purpose amidst kitchen utensils left behind as useless. All round the wide bowl or cauldron above which these jars lay the earth was reddened by fire right up to the wall. A couple of broken figurines of bulls was also found in this room, and one in vii. A flooring made of large unhewn slabs lay on a level about a foot above the outside pavement.

Rooms I x, x.—The clearing of the remaining portion of the interior showed that the room viii communicated in the NW corner with the one adjoining on the north and marked x, by a passage, 3 feet wide. This passage was blocked by heavy debris of stones, as was the case also with the room x. The dividing wall was leaning over at an angle towards the passage. The room x was cleared to the floor level without any finds being made. The north western part of the interior proved to contain two small apartments a thin wall dividing I x a from I x b. The latter, measuring 7' 6" by 5' 10", was found empty. In the other I x a, two stone built platforms 2' 8" wide and standing 2½ feet above the floor, line the north and south walls. From the northern one a stone step leads down to the narrow space left on the floor, the platform itself being approached by two very narrow steps from above it in the north western corner. Their position suggests that the floor of the upper storey which the building no doubt, once comprised stood approximately at a level of 7 feet above the floor of the lower one. Apart from a coarsely made jar 1' 3" high and 10" in diameter at the bottom which stood near the west wall at the foot of the southern platform, the only object found was the fine grinder of reddish marble, I x 1 (Pl XXIII) which also lay near the wall on the same platform. It is 8" high and 4" in diameter at its foot. Its shape and smooth surface attest superior workmanship.

Arrangement of structure I.—The ruin I as now described, provides some observations of a general interest. The accommodation offered by it conveys some idea as to the conditions in which the better class of the people settled in Kolwa at the time were living. The close agreement in type between the painted pottery left behind in the house by its last inhabitants with that found in deep layers outside it and on the surface of the mound adds to the chronological value of the indicia derived from the presence of similar painted ware.




FIG. 1. LARGE PIECE OF DEBRIS, STONES AND BRICKS OF DEBRIS  
LOCATED IN ONE TUNNELING I AM KUTTI MOUND



FIG. 2. FRAGMENTS OF DEBRIS, STONES AND BRICKS, LOCATED IN  
TUNNELING I AM KUTTI MOUND



elsewhere. It obviously prevailed during a prolonged period. The absence of any entrance to the lower floor of the house suggests conditions when special regard had to be paid to safety. Probably the dwelling was entered by a door in the upper floor approached by a ladder which could be easily removed in case of necessity. An exactly corresponding arrangement is seen in many of the dwellings at ruined sites of the Peshawar and Swat valleys dating from the Buddhist period. Finally the way in which that necklace from I vii was hidden seems to indicate that the last inhabitants left the dwelling at a time of some sudden emergency which is likely to have affected the whole site.

Trenches II-IV.—A shallow trench carried along the wall of a badly decayed structure Kul II a little to the north of I and on slightly higher ground yielded only small pieces of painted pottery and some broken bull figurines. A clay spindle whorl found here II 1 is shown in Pl. XXII. In another experimental trench Kul IV which was dug on the eastern side of the mound on a low level without striking structural remains the pottery both plain and painted proved of the same type as at I (for a specimen see IV 1 Pl. XXII). Besides a small copper fragment and much broken bull figurines there was found here a piece of a bangle made of very dark glass and ornamented with fine relief spirals in different colours.

Pottery finds in Trench V.—More profitable and interesting proved the cutting of trench V made on the north-eastern slope of the mound when towards the latter end of my stay the available labour had increased. It was carried in nine sections each about 8 feet wide and 12 feet long from a level of 10 feet to that of the small plateau occupied by the quadrangular enclosure of later date. Throughout these sections and at all the depths reached potsherds both plain and painted were found in abundance. Among the plain pottery there are numerous fragments of cups showing the small bases characteristic of chalcolithic ware of this kind found at the Zhob sites and Sitagen-dor (see V vi 2 vi 7 vi 5 a Pl. XXIII). The painted pieces in black patterns and colouring show so close an agreement with the painted ware found at ruin I that reference to the selected specimens reproduced in Pl. XXII and XXIII may suffice (Kul V vi 1 vi 3 vi 13 vi 12 ix 13). It will be seen that in some of these the brushwork approaches in fineness that shown by many of the patterns on the chalcolithic pottery of Surjunga. The dark red slip found in V vi 2 as well as in several other pieces and the triangles touching each other in V vi 3 vi 1 as in Stan chalcolithic patterns may be specially noted, so also the Egyptian lotus motif in Kul V ix 3. It is of interest also that in the highest section ix a fair number of fragments of fine grey ware unpainted were found, most of them small open bowls like V ix 5.

Figurines of bulls and goddess.—A striking result of the excavation effected at V was the abundance of terracotta figurines, bright to light especially in the lowest sections. A total of 66 figurines of humped bulls, out of these 31 in the first section at the lower end of the trench and 14 in the

second were counted. Specimens of them damaged like practically all others are seen in Pl XXIII. The frequency and the type of these bull figurines constitutes a close link between the Kuli site and the early strata of Shahi tuip. But of still greater interest perhaps is the fact that there came to light here also five small terracotta figurines of the goddess of which rare specimens had been found at the chalcolithic sites of Pernan ghundai, Kaudam and Dabarkot.<sup>2</sup> Three of them V12 (Pl XXII) v14a v11 are badly broken but V113 (Pl XXII) is practically intact except for the tip of the nose right down to the waist below which it ends as do all these figurines from the previously named sites. What imparts particular interest to this representation is the suckling babe shown here at the breasts of the figure. This strikingly confirms the view previously advanced that these figurines represent a divinity of fertility the mother goddess of many ancient Eastern cults. The treatment of the face almost bird-like with the eyes set sideways, is distinctly archaic even more so perhaps than at the Zhou sites. On the other hand the treatment of the hair is a little less primitive. In the lowest section 1 there lay the fine jar 20 inches high and decorated with bold relief bands seen in Fig 42. It had lost part of its wall in antiquity. Of other objects found in V only a curved piece of very thin gold plate, from section ix, calls for special mention. It is about an inch long and shows traces of ornamentation on the edge.

Clearing of apartment Vx.—In following up a wall which had been laid bare by the side of the trench in section viii and ix we came upon remains of quarters on the edge of the level ground above. Here an apartment Vx measuring 13 by 12 feet was cleared. A projecting wall 2' 6" thick divided it into two parts of slightly different width as seen in the sketch Pl 9. This and the outer walls still standing to heights from 4 to 5 feet showed everywhere solid masonry of roughly dressed slabs 3' 7" high except on the eastern side. There this stone masonry reaches only to about 1 foot from the floor then follows a solid layer 2 feet high of debris mixed with what looked like burnt plaster and above this again some thin courses of inferior masonry. This layer of solidified rubble extends further eastwards into section ix. It hence has occurred to me as the most likely explanation that the structure to which the apartment x belonged had at one time been destroyed by fire. The east wall had fallen and when the structure was restored the layer of debris which the conflagration had hardened was allowed to remain and was built over. Marks of fire were visible all along the inside of the walls of the apartment up to about 2 feet from the floor remains of white plaster still adhering in places. It deserves to be noted that the entrance to this apartment lay at a corner just as the passage between I vii and Ix. Evidently the builders were not equal to at a corner. I regret that want of time did not allow the excavation at V to be continued further on the plateau.

<sup>2</sup> See B. B. & n. To r. Pl. IX, XII, XVI.

Absence of stone implements and Nal type pottery.—Concerning the site as a whole two observations remain to be noted which though negative, deserve attention. The first is the curious fact that neither on the surface nor in the course of excavation did we find a single stone implement. This may be due either to chance or to the character of the soil being here composed mainly of stone debris and not permitting small stone 'blades,' etc. to be recognized as readily as at other chalcolithic sites where it consists of clay. The second observation relates to the total absence among the hundreds of painted potsheerds at the Kulh mound of a single fragment showing the peculiarities of decorative pattern colouring or shape of the 'Nal type' pottery. On the other hand I have had already occasion to point out the distinct links between the ceramic remains of Kulh and those from the lower strata of Shahu ramp as well as those from the undoubtedly early chalcolithic sites of Zhob and Loralai. At *Shahu ramp pottery of the Nal type was found only on the top of the mound amidst the burial deposits which obviously belong to times much later than those during which the site was occupied by the living.* I am hence led to assume, tentatively for the present that the Kulh site was abandoned before the ceramic style of Nal came into use. The fact that potsheerds of the latter type could be picked up again and again at most of the smaller Kolwa mounds helps to strengthen this chronological inference based on the complete absence of Nal ware at Kulh.

Full evidence regarding the conclusions just indicated can be hoped for only from extensive and systematic excavations at the Kulh mound. They would claim labours extending over months, if not seasons, and a much larger number of diggers than could be gathered locally at short notice. The site is certainly the largest known to me in Makran and in view of what it has yielded on a first rapid reconnaissance, it is likely to reward with valuable results any future archaeological explorer commanding adequate time and resources.

---

## CHAPTER VIII. ANCIENT REMAINS BETWEEN KOLWA AND JHAU

### SECTION I.—RUINED MOUNDS OF BAZDAD AND AWARAN

The open valley trough which stretches from the flat watershed west of Kulh down to Awaran is for administrative purposes included in Kolwa and thus reckoned as belonging to Makran. But its drainage flows into the Mashkan river, the westernmost feeder of the Hingol and is the valley of the Mashkan river with the exception of the comparatively small area occupied by the village of Awaran geographically as well as politically forms part of Bhakwan. The account of the sites surveyed down to Awaran may conveniently be included in this chapter.

Mound of Bazdad Lalat.—The first of these sites known as *Bazdad Lalat* is situated about 8 miles to the north-west of the Kulh mound and was

visited by me on March 9th from the latter. The route led across an open and potentially fertile plain cultivated only in patches with the help of flood water from the branching beds of the Wahahkaur which descends from the Central Makran Range in the north west. This drainage might even now suffice for more cultivation than is carried on here very indifferently by tenants of the Brahui Bizanzai Sirdar of Nal. This is proved by the many groups of large jungle trees passed between the scattered fields and the thick scrub which has overrun the latter in places.

The mound of Bazdad kalat rises to a height of about 25 feet and is occupied on its top by a ruined fort built with sun-dried bricks which was held by the Bizanzai chiefs since about the beginning of the 19th century and abandoned towards its last quarter. The mound measures at its foot about 110 yards from east to west and cire 90 yards across. Ancient pottery debris lies plentifully on its slopes. Among the painted pieces collected those of early type decorated as at Kulhi with geometrical patterns or more rarely with plant and animal forms (see the specimens Baz 15, Pl XXIV) are the great majority. The patterns are painted in black on a dark terracotta ground or red slip. But several fragments exhibit decorative motifs characteristic of the Nal type (see Baz 68) white and red colours easily effaced having been used to fill the black outlined designs. It may be concluded from this that the occupation of this site continued longer than that of the Kulhi mound. Of pottery of historical times not a single fragment was found.

Tract of Āwaran.—On March 12th I moved my camp some 18 miles down to the rest-house of Āwaran situated on the left bank of the Mashkai river at an elevation of about 1750 feet where the direct overland line of the Indo-European telegraph running from Karachi to Panjgur and Kurman passes. Below this point known as Rekm the Mashkai river enters a succession of narrow tortuous gorges. These continue down to its junction in the south with the Nal river the main feeder of the Hingol and nowhere leave room for cultivation. To the north conditions are different. There from a point about 11 miles above the rest-house the course of the Mashkai river which holds water in places throughout the year lies in an open valley. This measures about 6 miles from north to south and some 4 miles across where widest. Parts of this area are tilled by a group of small villages collectively known as Āwaran and counting some 1100 people largely semi-nomadic. Cultivation is carried on with the help of the flood water which is brought down after rainfall in the hills by the Mashkai river and by the Doraskaur a tributary of it from the north west. The meeting of the two rivers appears to have given its name to Āwaran.

Mound of Āwaran Nābat.—That the area of Āwaran has been occupied by settlements of some size from early times is proved by the series of mounds I was able to examine in the course of a long days ride on March 13th they brought with them proved helpful in searching the sites visited for ceramic and other remains. The first and most conspicuous of the mounds is the one

which rises not far from the left bank of the main Mashkai river bed at the central hamlet of Awaran where the modest headquarters of the Kolwa Niabat are placed. The mound about 30 feet high is crowned by the fairly extensive and well preserved ruins of a fort. This is said to have been destroyed some forty years ago when the local Murwan chiefs retook it from the Bizanjan Sardar of Nil. The high walls of the fort are built below with water worn stones from the river bed and above with mud bricks. The mound itself occupies the north eastern end of a natural ridge about 20 feet high which gradually falls away towards the south west. The debris accumulations from dwellings built with rubble and mud extend along the foot of the ridge for about 250 yards from NE to SW and some 170 yards across where it is widest. The easier slope of the mound towards the south western end of the ridge seems to have been occupied down to late times and there near a small Muhammadan cemetery walls crop out amidst the debris.

Pottery of Awaran mound.—Judging from the plentiful painted pottery found all over the mound the site favoured by its position appears to have been occupied during prolonged prehistoric periods down to later times. As the specimens seen in Pl. XXIV show there are found numerous fragments with simple geometrical patterns painted in black over dark red ground with or without slip as at the Kulli mound (Aw 13). There are also frequent pieces showing decoration of the Nal type (Aw 47) in which besides black outlines additional colours usually a light cream and deep carmine are used over the buff or terracotta ground. In a fair number of pieces of superior make (Aw 812) the decorative motifs are neatly painted in reddish brown over a light terracotta slip or whole bands of the same colour applied in a manner almost suggesting polish. A few fragments of red ware show rows of curving hooks (Aw 13) as often seen at sites of northern Makran like Zayak and Besima. Some glazed fragments prove occupation down probably to mediæval times.

Kambar damb.—Proceeding due north across the cultivated area of Labach hamlet which is served by flood channels of the Doraski and Mashkai the site of *Kambar-damb* was reached near the foot-hills dividing the two rivers. There a long stretched narrow ridge running parallel to a western branch of the Mashkai is thickly covered with large water worn stones and ancient pottery debris for a total distance of some 380 yards. The ridge in its lower strata consists of an alluvial clay deposit over which a thick layer of boulders has been spread by water action. Owing to its isolation the ridge offers a naturally strong defensive position and the big blocks of stone ready at hand have been used to provide its southern extremity which rises to about 50 feet in height with a rough and now badly decayed circumvallation. This extends for about 60 yards along the top of the ridge and measures about as much across where widest. Beyond the wall which separates this little fortification from the northern portion of the ridge the latter stretches on a lower level some 250 yards farther. Its flat terrace like top here less encumbered with boulders and about 90 yards wide is like the fortified portion of the ridge covered with plentiful potsherds marking ancient occupation.



**Painted pottery at Kambar damb**—Among the numerous painted pieces the most frequent show geometrical patterns in black on red ground. They are rather more coarsely and freely executed than at Kullh (see Kamb 13 Pl XXV, Kamb 58 Pl XXIV) and combined with voluted scrolls (Kamb 17) which are not to be found there. In addition there were picked up a few fragments Kamb 911 Pl XXIV with motifs neatly executed in dark brown over light terracotta in the manner noted above at the Awaran mound. On the whole the occupation of Kambar damb appears to date somewhat later than that of the Kullh mound but not to come down so far as the period of the Nal type ware neither of this nor of any later pottery did we find fragments.

**Firoz Khan damb**—From here we proceeded to the north east crossed the Mashkar river near to the point where a temporary band serves to distribute its flood water into rough inundation canals and after about  $2\frac{1}{2}$  miles reached the conspicuous mound which is known as *Firoz Khan damb* after the chief who last held the ruined fort crowning its top. All round it there spreads a desolate waste of bare clay cut up into a maze of little furrows and terraces by shallow flood channels descending from the steeply eroded hill chain to the north west. This ground not unlike a Yardang area in the Lop desert bears a thin layer of plain potsherds on the surface for about two furlongs from the foot of the mound. The mound which is perfectly isolated rises to a maximum height of about 50 feet. As it is manifestly throughout of artificial origin the stones on its slopes most of them waterworn but not as large as on the Kambar damb ridge must belong to the debris of decayed structures. The mound measures about 320 yards from east to west along its northern foot and some 110 yards across where widest. On the terrace like southern portion of the mound which has a height of about 25 feet remains of walls roughly built with stones and mud can be traced.

**Remains within ruined fort**—The fort which occupies the highest portion of the mound measures about 40 yards from SE to NW. Its rough circumvallation is built with stones set slanting to right and left in alternate rows. The much decayed state of this enclosure bears out the local report of its having been abandoned some six generations ago. The mound right up to the top crowned by this ruined fort is composed of ancient debris. Thus apart from the painted pottery found there is proved also by a curious discovery. In a fissure which erosion has produced in the soil within the enclosure there could be seen remains of old walls built with regular courses of flat stones and evidently belonging to the corner of a square structure. From the debris exposed by their side a large pot of thick coarse ware measuring 12 in diameter and 9 in high was extracted. Its vertical walls right up to the slightly inverted lips round the mouth, 10 in wide are perforated exactly in the same manner as in the vessels of this kind found at Sul-tagen dor Shahi tump and elsewhere. The plentiful ashes and remains of charcoal found within conclusively showed that such vessels must have served as braziers or for cooking.

Most of the painted potsherds found on the mound belong as the specimens Tir 14 (Pl XXV) and Fir 56 (Pl XXIV) show to the same boldly patterned

ware as prevails at Kambar damb. But here too there were a few pieces of superior make with reddish brown design over light terracotta as seen on Fir 6 (Pl XXIV). None of the fine red and black ware so common at Kulh was picked up nor a single fragment decorated in the Nāl style. On the other hand renewed, though probably not prolonged occupation in historical times is attested by glazed pottery fragments some of old look some mediæval. These were particularly frequent on a low portion of the mound towards the south.

Pottery of Sohren damb.—The small site known as *Sohren damb* the red mound which was reached about a mile to the east offered an observation that helps to strengthen reliance on the chronological indications afforded by pottery materials from the surface of sites. Here at Sohren damb we found a flat patch of ground about 120 yards across thickly covered with potsherds. Among these glazed fragments of mediæval look, with a great variety of designs chiefly in different shades of brown green and yellow (for specimens see Soh 1 7 Pl XXIV) were abundant while unglazed painted ware was conspicuously absent. The glazed pottery comprises two kinds, both represented among the glazed Persian ware which was found on my third Central Asian journey at a site near Sarbisha above the Sistan basin. According to Mr R. L. Hobson Keeper of Ceramics British Museum who has described these latter finds the type with green glaze and incised ornament, like Soh 7, recalls Persian pottery of the ninth to tenth centuries while the other type (Soh 1 6), here dressed with a light yellowish slip and decorated in brown black and green resembles the Samari and pottery of the twelfth to fourteenth centuries. The plain piece with incised ornament Soh 8, obviously coeval also claims some interest. Beads little pieces of gold and other metals were said to be occasionally found at this ground after rain. Not far from it to the south there still scattered patches of cultivation belonging to the hamlet of Pirandur.

Kambaro damb of Bedi.—The last site of Āwaran visited occupies a winding clay ridge rising above the hamlet of Bedi about 2 miles to the north east of Āwaran proper. It is known as *Kambaro damb* and extends for about 350 yards. This ridge rises at its eastern end to a height of about 40 feet and for the most part appears to consist of natural deposits. Its top and slopes are thickly covered with potsherds and stones. The painted pieces collected were not numerous and showed all coarse patterns of the same type as found at the site of Kambar damb above Labach. Fragments roughly incised with comb drawn lines were frequent also a few pieces of red and dark grey ware with sharp-edged ribbing were found. As glazed ware was totally absent the site would appear to have been abandoned since prehistoric times.

Larger population in prehistoric times.—The number and comparatively large size of the mounds found in the limited area within which the character of the ground about Āwaran is ever likely to have permitted of cultivation deserves attention all the more because with the single exception of Sohren-damb their ceramic remains clearly point to their having been occupied during approximately

the same prehistoric periods. From this the conclusion may safely be drawn that the area then supported a much larger population than could possibly maintain itself there now. Considering the position of Awaran local agricultural resources can alone come into account here. These again are necessarily dependent in the main on climatic conditions affecting the available supply of water. Hence here as in the case of Kolwa archaeological evidence clearly points to a change of climatic conditions in the direction of 'desiccation' having taken place since prehistoric times. We shall see below that the observations made in the Jhalawan valleys adjoining to the east closely agree with this inference.

### SECTION II—THE SITES OF NUNDARA AND JHAU

Information suggesting the existence of prehistoric sites in the Jhalawan hills to the south east of Mashkan had been first received by me from Mr. Gabler, Superintendent of the Indo-European Telegraph Department. On our meeting at Gwadar he had mentioned having noticed two mounds close to the telegraph line where it crosses the valley of Jhan on its way from Las Bela to Awaran. He subsequently very kindly arranged for specimens of potsherds from these to be transmitted to me through the guards along the telegraph line, and these duly reached me while still at work near Turbat. These specimens large enough but all plain could furnish no definite clue to the age of the site. I could not pay my visit to Jhan while moving from Mashkan to Las Bela by the route which passes there for the advance of the season and regard for the tasks still awaiting me northward had already while at work in Kolwa obliged me to abandon the intention of extending my survey so far south. But when in the course of my enquiries at Awaran I learned of old mounds also in the Nundara valley through which the route to Jhan passes there was sufficient inducement to make the diversion in question.

Remains of *Gat barit*.—So on the morning of March 14th we left the lorries and whatever of *impedimenta* could be spared behind at Awaran and set out with camels for Nundara. Moving through low foothills first to the north-east and then up the narrow Fish valley so called from the abundant growth of dwarf palms in its torrent bed we reached the Gat pass after about 10 miles. The descent from it eastwards led in a gorge winding between steep cliffs of shale and known as *Gat barit*. There the track after a mile passes a curious ruin built on a low rocky ridge at a point where the bottom of the gorge slightly widens. It consists of a row of large enclosures each measuring about 24 feet square inside within walls of unmistakably ancient lock. They are from 4½ to 5 feet thick and built with rough slabs which the nature of the rock available allowed to be quarried on the spot and to be used with a minimum of dressing. The walls now stand only to a height of 3 or 4 feet and judging from the absence of debris inside do not appear to have ever been much higher. Entrances, about 3-4" wide are traceable in each room on the side facing the track. As in the case of 'Gabar-bands' no plaster or earth has been used in the masonry.

inequalities in the height of slabs being adjusted by small flat pieces of stone inserted between the courses. No potsherds could be found either within the enclosures or on the slopes below. The purpose of the structure would remain even more puzzling but for the presence of a perennial spring about three quarters of a mile further down the gorge. The ruin occupies the nearest spot where there is room for a structure of any kind. Nowhere else is water to be found between the Mashkai river and Nundara. Hence the idea suggests itself that the place was chosen for accommodating a watch post to control traffic on a route possessing some importance as the most direct connexion between Las Bela on the one side and Makran and western Jhalawan on the other. A post of this kind to levy transit dues is now found above the point where the route coming from Mashkai and Nundara debouches into the valley of Jhau.

Valley of Nundara.—About a mile below the spring the ravine debouches into the Nundara valley. This here some three miles wide bears a thoroughly desolate look for beyond a few small patches of cultivation dependent on any flood water that may descend in the ravine from the Gat pass the whole of the flat bottom of the valley is a waste slightly salt encrusted and covered with tamarisk jungle and scrub. Cultivation is not possible on this ground nor anywhere else lower down in the valley wide and open as it is for miles for as Musa Khan Mirwari of Muungah who owns land higher up in Nundara and who accompanied me from Awaran explained the water carried in the Nundara flood bed descends so far only in exceptional years and then loses itself and evaporates on this scrubby waste.

Site of Tikri dam.—On approaching the opposite side of the valley to the south east and within less than half a mile of the foot of the hills separating Nundara from Jhau a large mound was reached for which the name of *Tikri dam* was given to me. It rises not far from a small patch of cultivation to which a flood bed along the eastern scarp of the valley carries water. Its highest portion rises to over 50 feet, but owing to the thick debris of stones from decayed structures it was not possible to make sure whether the whole mound is of artificial origin or whether natural deposits of alluvium underlie at the bottom. The main axis of the mound stretches approximately from east to west. For a distance of about 150 yards the mound throws off a terrace like outlier to the south west at a much reduced height. The foot of the mound proper along the south side measures a little over 200 yards while the circuit of its top is about 490 yards. Fig 45 shows the western portion of the mound as seen from the south west.

Ruined walls and pottery remains.—About the middle of the mound two large ravines run down to its foot one to the SE and the other to the NW. They measure circ 170 and 130 yards respectively, in length and have laid bare a central mass of ruined walls at different levels. These walls and others exposed on the top as seen in Fig 43 show rough masonry of exactly the same type as I shall have occasion to describe further on at Shah dam the other ancient site of Nundara. Abundant broken pottery covers the slopes of the main mound and also its lower extension to the south west. But painted pieces were

comparatively rare on the surface. As the specimens reproduced in Pl XXIV Tlk N 1 b show both the earlier geometrical patterns as well as those of the Nal type are represented among them. The prevalence of pieces with light red body and additional colours of buff white or purple used either as a slip or for filling the black outlines is noticeable.


Our camp had in accordance with Musa Khan's direction been sent to Karam Shah damb some 6 miles further up the valley to the north east as the nearest place where water and habitations could be found. This prevented prolonged examination of Tikh damb at the time and after my first survey of the Shah damb next day I decided upon the latter site as the one more suited for trial excavation. It was hence to Shah damb that I devoted on my return from Jhau such time as could be spared for Nundara. Nevertheless I believe that the mound of Tikh damb would well deserve future exploration.

Deficiency of water.—What was seen on our way up the level bottom of the valley strengthened the impression received before of the present conditions of Nundara. The amount of water received by the valley now a days is manifestly far too small to account for the former existence of fairly large settlements such as the mounds of Tikh damb and Shah damb indicate. Nor can the change be satisfactorily explained by the curious bifurcation at the head of the valley through which the Darach kaur the main supplier of drainage for Nundara sends a part of its flood water into the Nal river which feeds Jhau for a barrage intended to prevent that diversion was according to local tradition still serving its purpose until two or three generations ago and could be restored now also if the necessary labour could be raised from the fifty or sixty families who constitute the whole population of Nundara.

Karam Shah damb.—The Karam Shah damb below which our camp stood proved when examined in the morning of comparatively late origin. It is composed entirely of whitish clay from the decomposed walls of mud structures. It is about 30 feet high its top 36 yards across and crowned by decayed mud walls of a little fort which is supposed to have been abandoned seven generations ago. What little of painted pottery could be found was either of coarse probably late prehistoric ware or else poorly glazed. With this must be classed also the fragment Kar N 1 (Pl XXIV) showing a band of relief hachures not seen by me elsewhere.

Ride to Shah damb Nundara.—From here we rode to the north east first for half a mile past scattered patches of cultivation and then for two miles farther across an absolutely bare clay plateau cut up by a maze of small eroded ravines. Then we arrived at the imposing mound of *Shah damb* by the right bank of the main flood bed of the valley. The examination of both its structural remains and its abundant pottery kept me occupied for half the day and proved so interesting that I decided to return to *this site* from Jhau and to devote to it what time could then still conveniently be spared. My account of the observations there made may therefore be left for the next section.

March to Jhau valley.—The march thence resumed to the south east towards Jhau brought us after crossing a succession of steep ridges by a track imprac-



0


0



0



1





licable in places for mounted men into the winding gorge of the Maki laur. There we struck the caravan route which leaves Nundara a little to the north of Tikn damb. Following it down for some 11 miles we emerged on the wide trough traversed by the Nal river. Across this valley of Jhau fully eight miles broad a fine vista opened towards the bold hill range which divides Jhalawan from Las Bēla. Still further away to the south it allowed us to sight far away the high massif of Dhrum. Round it the rivers of Nal and Mashlāi here united into the Hingol have cut their way to the sea. Looking across this great plain as it lay before us under a slight veil of dust shimmering in the light of the setting sun it was difficult to realize that all this southern portion of the Jhau tract is now a waste abandoned to thin tamarisk growth and scrub. Moving eastwards for another four miles we halted after nightfall by the first huts of Jhau where water was obtainable from a well.

**Spet damb of Jhau**—On the morning of March 16th we crossed the main flood bed of the Nal river now quite dry to the ESE and after about a mile found ourselves at the foot of the mound known as *Spet damb*. It rises to a height of about 30 feet amidst abandoned old fields and small clay plateaus furrowed by erosion. Its length on the top from WSW to ENE is some 110 yards and its maximum width there about 70 yards. Numerous nullahs deeply cut into the slopes show that the mound is composed wholly of debris deposits. The layers exposed disclose rubble from decayed dwellings embedded in clay but no walls of stone masonry.

**Painted pottery**—Among the pottery debris painted pieces were found in plenty. As the specimens Spet J 18 Pl XXVI show most of them with boldly executed patterns black on red or buff ground closely resemble the painted ware prevailing at the Awaran sites of Kambar damb and Firoz Khan damb. Voluted scrolls and rayed discs as seen on Spet J 124 are frequently used motifs. Not a single piece decorated in the Nal style was found here but a few fragments of glazed ware plain green or blue suggest occupation down to or re occupation in early historical times. To these has probably to be ascribed also the globular jar with its small spout apparently placed sideways Spet J 12 (Pl XXVI) which recalls shapes found at Jiwanri and the Moghul ghundai cemetery. Late too is the handle fragment Spet J 9 with incised hachures. Two small terracotta figurines (Pl XXVI) are of interest. Spet J 10 represents an animal difficult to determine. Spet J 11 probably from a lid shows a double ram's head, and has its exact counterpart in Bal 4 (Pl XX) from the Balor site. The painted pottery, too from the latter shows resemblance in decorative style to that of Spet damb.<sup>1</sup>

**Sakh damb of Jhau**—Of decidedly older appearance are the remains on the large mound appropriately known as *Sakh damb* the Black Mound found about half a mile to the east. It rises over an area of bare clay cut up by many small ravines and is situated about a quarter of a mile from the right bank of a branch bed of the Nal river. As the sketch plan Pl 10 shows the

<sup>1</sup> See above p. 110



mound is a large one stretching at its foot approximately 470 yards from north to south and some 280 yards across where widest. It is almost entirely covered with the debris of stones now weathered black from masonry of the same type as found at the Kuli mound. Remains of walls of structures large and small crop out on the surface at many points of the top and slopes.

**Structural remains exposed**—The central portion of the mound, forming a small flat-topped ridge, rises to a height of cire 50 feet over the ground around. But natural clay terraces exposed at the southern foot of the mound prove that the mound rests on an alluvial plateau which stands to a height at least of 10 to 12 feet above the present level of the surrounding area. Originally at the time of first occupation the relative height of the plateau may have been greater. The central ridge is divided by a Nullah from the northern portion of the mound. The top of this forms a kind of rim nearly as high as the central plateau. At the south-western foot of this rim remains of a massive wall built with slabs up to 3' feet long and over a foot high are exposed. Along the central plateau a curving wall of similar massive construction about 4½ feet thick, can be traced embedded in the ground for over 100 yards from NW to SE. It ends above the steep slope flanking the above mentioned Nullah on the south. This wall can manifestly have served only a defensive purpose.

**Painted pottery, figurines etc**—The painted pottery comparatively scanty, as seen from the specimens (Shah 14 Pl XXV 5 7 10, Pl XXVI) shows an unmistakable resemblance throughout to the type prevailing at the Kuli site. Only in one small fragment (Shah 11) can some similarity to the pattern of the Nal ware be possibly recognized. The animal figure in Shah 5 has its exact pendant on the jars and fragments found in Kul 1. The early occupation of Shah-damb is confirmed by other finds also. Among them are pieces of cups or bowls (Shah 8) showing the disproportionately small base familiar from the earliest of our Chalcolithic sites. Then we have over half a dozen terracotta figurines of bulls all broken exactly of the same type as found at Shahi tump and Kuli. Also clay bangles and small fragments of worked copper. Of plain pottery with impressed patterns Shah 9 (Pl XXVI) is a characteristic specimen, closely resembling with its imbricated design the fragment Kul 1 (Pl XXI) from Kuli. From all these indications it appears safe to conclude that this mound was occupied about the same Chalcolithic period as the Kuli site. It would certainly have offered tempting ground for trial excavations if it had been possible to spare time for the purpose. Systematic exploration would, owing to the great size of the mound be likely to claim months.

**Second Spet-damb of Jhau**—After crossing the branch bed of the Nal river known as Shank and proceeding a little less than a mile to the east I visited a second mound also known as *Spet-damb*. Close to it the telegraph line to Las Bela passes over old fields long abandoned, and overgrown in places by jungle trees of considerable size. The mound is comparatively small, measuring at its foot from SW to NE 105 yards, including a terrace-like extension on the south. Its top at a height of about 40 feet had been levelled by the grandfather of the present Bizanjan chief of Nal who had intended to build a fort there. It

measures about 48 yards in diameter. The mound wholly artificial is composed of whitish clay from decomposed mud walls with some rubble interspersed. Potsherds, ashes etc. are to be found throughout the exposed layers. The comparative lateness of the period during which this mound was formed and its occupation down to mediæval times is proved by the ceramic fragments found on the top and slopes. These comprise plenty of glazed fragments both plain and decorated in a style similar to the one seen on the glazed ware from the Sohren damb of Āwaran and from Sarbisha.<sup>2</sup> The painted potsberds (for specimens Spet II 1 3 see Pl. XXV XXVI) are all decorated with the free and rather coarse brush work, black over light red or buff ground found on the later prehistoric ware from Kambai damb and other mounds of Āwaran. Among them are two stylized representations of birds. Spet II 2 (Pl. XXVI) showing a duck the other Spet II 1 (Pl. XXV) some other aquatic bird.

Character of Jhau sites.—The presence of these three mounds so close together clearly proves that the chief settlement in that southern portion of the Nal river valley now known as Jhau must have stood on this ground from early prehistoric times. Its position here can be adequately accounted for partly by the great width of what once was arable ground and partly by the topographical fact that the most direct route from Las Bela to Machkai and the eastern parts of Makran passes along the line marked by the mounds. There can be no doubt about Shah damb marking the site of the oldest settlement and the second Spet damb the one occupied latest.

Information about these mounds had reached Masson who briefly notes 'the site of an ancient city in Jhau which tradition affirms to be that of a city founded by Alexander'.<sup>3</sup> No such tradition was heard of by me on the spot. Masson's suggestion that this city might be the Alexandria founded amongst the Orizæ cannot be reconciled with what we know of the route followed by Alexander through the territory of the Orizæ.

Cultivation at Lanjar.—At present the area of permanent occupation in this part has shifted considerably further up the valley. Leaving the second Spet damb we rode north across a dreary bare plain of clay showing here and there first marks of old cultivation and further on still more desolate ground furrowed by erosion trenches. Then after about five miles having crossed the upper course of the Shank branch, I found myself on the eastern edge of the narrow but comparatively well cultivated belt of ground known as Lanjar. It is now a day's the chief permanent settlement of Jhau. The last Census statistics show a population of 718 souls a number considerably in excess of that of the whole Nundara valley. The fields of Lanjar stretch along the right bank of the eastern main river bed on gently rising terraced ground and enjoy the great advantage of fairly regular watering from inundation canals. The change of scenery to properly tilled fields with crops of barley ripening and cultivators' mud built huts interspersed between them was striking.

<sup>1</sup> Cf. above p. 121.

<sup>2</sup> See Masson's *Journa. in Kalat* pp. 388-93.

Remains of Adasta-damb—A circuitous path winding between the terraced fields brought us after about two miles' going north westwards to the mound known as *Adasta-damb*. It occupies a small island situated between inundation channels a little below the point, a kind of *su-bushā*, or 'head of the waters', as it would be called in Turkestan, where three or four channels start from the western main branch of the Nāl river. Low terraces and ridges, thickly covered with much weathered building stones and with potsherds, extend over an area about 190 yards long from north to south and at its upper end about 70 yards across. On the north east and east faces walls built with roughly dressed slabs are exposed, as seen in Fig 46 at heights from 8 to 20 feet above the river-bed. These walls belong to separate structures more or less aligned but not forming a circumvallation. The debris layers beneath them are full of potsherds. The walls are built with regular courses of slabs, mostly small and fairly uniform in height. Where the river branch, quite dry at the time of my visit, bends round the north eastern corner to skirt the eastern flank of the site, it appears to have carried off structural remains. Painted potsherds could be found only below the ruined structures on the north side and in no great number. They show simple geometrical patterns executed in broad brush work similar to that found at the later prehistoric sites of Āwarān.

Return to Nūndara—Adasta damb lies close to the foot of the gravel glacis of the hill range to the west. As we made our way back along this to our camping place mat huts were passed at intervals temporarily occupied by those who in years of sufficient rainfall are able to cultivate patches of ground along the river bed below Lanjār. The contrast between these few scattered nomadic abodes and the picture which the little town marked by the Sīāh damb mound must have once presented was striking. The only other 'damb' of which I could learn within the Jhaū tract itself was said to be situated at Pēlār, in a small side valley over 40 miles up the Nāl river. A visit to it would have left no time for the intended excavations at the Sīāh damb of Nūndara. So on March 17th I returned there by a somewhat changed route across the barren hills and with the help of a small posse of diggers collected beforehand was able to start work there the same day.

#### SECTION III—THE RUINS OF SĪĀH DAMB, NUNDARA

The site of Sīāh damb in Nūndara to which our work from March 17th to 21st was devoted occupies an elevated portion of a bare clay plateau which stretches along the right bank of the wide flood bed of the Nūndara valley. Its ruins extend over a roughly oblong area which as the sketch plan Pl II shows, measures about 220 yards from north to south and circ 180 yards across. To the south east there adjoins a narrow belt of low ground which is reached by flood water from the river-bed and for a distance of about a quarter of a mile is normally under cultivation, as seen in Fig 44. The plateau portion, bearing the ruins on the south east and east, falls away very steeply to the shingle and




Fig. 17. BASE PART OF SOUTH DAM NUNDARA WITH FLOOD MUD IN LOW



Fig. 18. WATER OF NUNDARA ABOUT 1000 FT ABOVE BASE OF SOUTH DAM NUNDARA




Fig. 19. THE NW END, THROUGH NORTH OF THE NW END OF SOUTH DAM NUNDARA



Fig. 20. WATER OF NUNDARA ON EAST SIDE OF SOUTH DAM NUNDARA



sand filled river bed. The cliffs here edging the once occupied plateau top are, as the photograph Fig 47 shows quite wall like for the most part rising from about 10 feet to close on 40 feet above the level of the river bed. From a close examination of these cliffs it is seen that the debris of stone built dwellings on the top rests on layers of horizontally stratified clay deposits obviously alluvial. These are about 25 feet high near the southern end of the east face and thence slope down to 10 feet beyond the northern one.

**Area of ancient occupation**—The central portion of the site reaches a height of 52 feet above the river bed and thence descends with easier slopes to the unoccupied portions of the clay plateau on the north and west. As the sketch plan Pl II shows the area of ancient occupation is bounded on these sides by small erosion trenches. The whole of the ground thus circumscribed is covered with ruined walls of structures built with roughly dressed slabs and with the debris of their stone masonry. Remains of such walls are to be seen everywhere lining the top of the cliffs of the east face (Fig 48-50). They are exposed equally clearly by the side of the Nullahs which erosion has cut into the slopes especially on the south east and west (Fig 51-53). Reference to these photographs will best illustrate the construction of these walls which in places still stand to 4 or 5 feet above ground. They are built with roughly dressed slabs of shale of various sizes and heights. They measure in places up to 34 feet or so in length and up to 8-10 inches in height but are mostly much smaller. Stones of fairly uniform height were used in order to secure an approach to regular courses anyhow for the wall faces the courses themselves varying greatly in height as seen e.g. in Fig 52-54. The courses were set in thin layers of mud small stones being but rarely used to redress inequalities or to fill interstices.

**Structural remains**—Where remains of walls from larger structures still stand well above the ground they have been shown roughly to scale in the sketch plan. Where they are more or less buried in debris an indication by symbols had to suffice. But from the appearance of the surface which is everywhere thickly covered with stones originally forming part of the masonry it may be safely assumed that the whole of the plateau portion described was at one time or another occupied by structures of the same type. That these were often built upon the ruins of decayed ones is made highly probable by the appearance which the 'culture stratum' exposed above the natural clay layers on the cliffs of the east face presents as in Fig 50. Elsewhere a succession of foundation levels is seen in the ravines particularly in the one running from the ruins excavated to the south east (Fig 51).

**Pier-like wall on E face**—At the north eastern corner of the once occupied area a massive stone built wall projecting from the natural clay cliff (Fig 49) attracts attention from the first. It rises to a height of 17 feet above the gravel of the river bed towards which it projects like a pier or buttress. Its surviving portion is about 9 feet thick and is built partly with masonry of rough stone slabs as already described and partly with rubble compacted like concrete and very hard. On the top there survives a wall like mass of clay 2 feet high in this position it can only be accounted for as having belonged to some small

structure built with stamped clay or mud bricks. The most likely explanation of the pier like wall below is that it was intended to protect the eastern face of the plateau top and the structures built above it from being carried away by the erosive action of floods in the river bed. This solid remnant of ancient masonry has certainly well served this purpose up to the present.

Potsherds in layer of alluvium.—Another interesting observation was made on the vertical face of the clay cliff which extends northward immediately beyond this pier. There can clearly be seen a kind of culture stratum interposed between pure alluvial deposit. It starts quite close to the pier from a level circ 7 feet below the top of the cliff and shows there a thickness of circ 19 to 24 inches. Thence thinning out it sinks down gradually to a level of about 12 feet at a distance of 16 yards from the pier and then disappears at the foot of the terrace. In this stratum easily distinguished by its darker colour, there are found besides potsherds small stones pebbles and what looked to me like the produce of decomposed refuse. Most of the potsherds cleared from it in a cutting at a point about 9-10 feet below the plateau top were of coarse plain ware some looking as if they were hand made. But in the end we found there also three fragments of painted pottery with geometrical patterns in black on red. The latter raise a question to which I can see at present no satisfactory answer. The unpainted fragments of coarse ware might have been ascribed to a much earlier prehistoric settlement existing at the foot of the mound and separated from the ruins above by a long period during which floods of the river deposited heavy alluvium covering that foot and greatly raising the level of the plateau around. But the association of painted fragments of the same type as those found plentifully among the ruins suggests their having been washed down during the occupation of the site and since then buried under alluvium. If this assumption is right the absence of such painted ware in the upper layers of clay close to the top of the pier and to the debris covered area of which it marks the corner seems difficult to account for.

Printed potsherds from surface.—Before I proceed to describe the results of the excavations it was possible to carry out at some of the ruined structures it will be convenient to review the ceramic remains collected from the surface of the site. For the sake of brevity it will be referred to further on merely as *Nandara*. These remains were entirely restricted to the elevated portion of the plateau within the limits above indicated, but were there to be found in great plenty. The abundance of painted potsherds makes the fact still more interesting that with comparatively few exceptions they all exhibit the characteristic features of the *Nal* type both as regards the designs and the polychrome treatment of patterns. The representative selection of specimens, reproduced in Pl. XXX, XXXVI will help to illustrate this. Only in a few pieces, like Nos 10, 12, 13, 27, 37 do we find simple geometrical patterns executed in black over buff or red ground. In the vast majority indications of a style closely allied to that of the *Nal* pottery are met with such as elaborate ornamentation of the designs and additional colouring in yellowish white and a very dark red or purple. In the fragments Nos 7, 11, 17, 20, 21, 22 which show




Fig. 33. RUINED STRUCTURE - II (V) SCAR OVER NUNDARA FROM SOUTH EAST



Fig. 34. RUINS OF STRUCTURES ABOVE TSL. RAVINE, SCAR OVER NUNDARA, 500 YDS. FROM SOUTH



Fig. 35. INTERIOR OF STRUCTURE II, SCAR OVER NUNDARA, BEFORE EXCAVATION




Fig. 36. STRUCTURE I, SCAR OVER NUNDARA AFTER EXCAVATION





parts of animal figures the subject and treatment are quite distinct from those seen in the corresponding class of painted pottery found at Kulh. The same applies to the representation of plants as seen in Nun 18.

Decoration and shapes of ceramic remains—As in patterns and colourings so the great majority of the painted pottery from this Nundara site differs also in the superiority of its fabric from the late prehistoric ware found at the Awarin and Jhau mounds. On the other hand a few fragments like Nun 42 show the simple hook ornament often met with at sites further north in Jhalawan and Kharin which are probably of later occupation. The broken state of all painted pottery from the surface makes it difficult to say more of shapes than that very many of the fragments appear to have belonged to open bowls like the partially preserved one Nun 15 (Pl. XXV) or else to large pots like Nun 12. But the negative fact deserves notice that not a single piece belonging to the class of small based cups so common at the early Makran and Zhob sites was found here. On the other hand there must be noted also the total absence of pieces with handles or ears such as would indicate a later period. The exact purpose of the fragmentary pottery object Nun 16 (Pl. XXV) is uncertain. The only recognizable copper object found is the piece of a decorated bracelet Nun 5a (Pl. XXVII).

Absence of terracotta figures—Special importance must be attached to the fact that not a single of these terracotta figures of bulls which were so plentifully found at Shahi tump, Kulh and Mehri also at the Shahdamb of Jhau, all sites devoid of Nal type pottery was to be found here either on the surface or in the ruins excavated. From this it seems reasonable to conclude that the cult with which these figures and those of the goddess were probably associated no longer prevailed at the period when painted pottery of the Nal type was in use. For that the latter belongs to a period later than that characterized by painted pottery with simple geometrical patterns in black on red appears to be proved by direct stratigraphic evidence at the sites of Shahi tump and Mehri.<sup>1</sup> In this connexion attention may be called also to the absence of stone implements at the Nundara site which similarly points to its occupation dating later than that of early chalcolithic sites like Suktager der Shahi tump and the Zhob sites.

Ruined cella I—Owing to the very limited number of labourers to be secured within the valley excavation was confined to a group of small ruined structures of which the walls could be seen rising above the ground by the side of the deep cut Nullah descending to the south east (Fig. 51). Two of them I and II small approximately square cellas attracted my attention from the first by pillar like masonry of oblong shape rising near their centre. They lay as the sketch plan 11.11 shows in the same axis only a little narrow lane dividing them. Their corners were roughly orientated. The structure I which was less deeply embedded in debris and which Fig. 54 shows after excavation proved about 15 feet square. It was enclosed on three sides by walls of coarse masonry and on the fourth to the south west by what appears to have been

<sup>1</sup> See below pp. 167 sq.

one of mud bricks. This wall was found badly decayed. Approximately near the centre rose a block of masonry 6' 4" by 5' 5" built with slabs more carefully dressed than elsewhere to a height of 9 feet above a rough stone flooring. Owing to the facing slabs having fallen off at different places this block presented the appearance of being irregularly stepped.

Earlier structural remains built over—A very curious and at first a very puzzling feature in this structure was a cross wall 1' 8" wide and 2' 3" high which came to light joining the central pillar to the NW and SE enclosing walls. This wall rested on the rough flooring of stone already mentioned. That it was the remnant of an earlier structure which had been built over became clear when a cutting was made down the north east side of the pillar. For about 3 feet from the top it proved to be built throughout with stone masonry. Below this followed sun-dried brick work faced with slabs down to a level approximately identical with the top of what remained of the connecting wall towards the NW and SE walls. From there down to the stone lined floor the masonry consisted again of stone slabs. It was thus ascertained that in building up the pillar from the floor level of an earlier building use had been made of what remained of a wall running from SE to NW which became embedded in the later masonry. The floor of the later structure was then raised so as to be flush with the top of the connecting wall. This explains why distinct remains of a plastered mud flooring had been struck in the north corner on a level exactly corresponding to the top of what was left of the old wall. No deposit of any kind as I was first tempted to expect was found within the cleared portion of the interior of the pillar. Only a few small fragments of pottery were found which had become mixed up with the mud plaster used between the courses of masonry. Little fragments of bones which do not appear to be human but to belong to some small animal lay scattered on the earlier flooring.

Central pillar—I am unable to offer any satisfactory explanation as to the purpose which the central pillar or pier was intended to serve. It was found with similar dimensions in the structure II (Fig. 52). It could be traced also on the surface in three more small structures VI-VIII which are marked in the sketch plan Pl. 11 but remained unopened. It seems difficult to believe that so massive a block of masonry was needed to permit a space of only 14-15 feet to be spanned with beams for the purpose of a roof or an upper floor. The fact that in the rooms III-V to the east of I and II no such pillars were found speaks against this assumption. It must also be taken into account that owing to the insertion of these pillars the space available for habitation within the rooms became limited to mere passages. If then such rooms were unsuited for occupation what else could have been their purpose? For the present I must leave the question unanswered.

The same uncertainty remains also about the significance of four large boulders roughly globular in shape which were found close to the walls of I either above or quite near to the surface. One of them is seen in Fig. 54. Could they have served some decorative purpose on a structure which was not an ordinary dwelling place?

Painted potsherds found in I—Adjoining the decayed south eastern wall of I through which the entrance must be assumed to have lain there were cleared the poorly preserved foundations of walls enclosing a room II which measured 17 by 9 feet. Here was found a considerable number of painted potsherds. As the specimens Num 113 reproduced in Pl. XXV show there are represented among them pieces with simple geometrical patterns in black on red as well as others of the Nal type the latter greatly prevailing. An unusual pattern is seen in 15 and the stylized figure of an Ibex in 14 (both in Pl. XXVII). A few fragments painted in black on red ground turned up in I 1 is also the terracotta head of some animal figure.

Structure II—The structure II immediately to the SE of I proved to be built on a level about 5 feet lower than I. As the sketch plan Pl. II shows it consists of a main room 14' 4" square inside and two small apartments by its side. That the main room was entered from the NE could be seen from an opening on that side blocked by fallen masonry whereas elsewhere the wall still stood to a height of about 11 feet. There was a similar indication also of a doorway leading into the small room II n. II m was merely a small closet or storage place without any entrance being traceable on its sides. In II, the central pier (Fig. 55) proved just as also in I 1 to have been built over an earlier wall of which the continuation still remained as far as the SW wall. A cutting made on the NE side of the central pier showed that at its foot there was embedded the end of that earlier wall. It had been enlarged to the required size partly by mud bricks and partly by additional stone masonry. The surviving height of the earlier wall was 2' 4" and on the same level as its top there were found on the NE side of the pillar remains of a stone edging to a later floor.

Sun dried bricks in wall of structure II.—On digging below this level on the same side it was found that the masonry of the enclosing NE wall near the eastern corner rested on an earlier wall of sun dried bricks standing approximately to the level of the later floor. The bricks of which seven courses remained measured 21"×10"×4". This size agrees closely enough with that of the sun dried bricks of the wall found between sections VII and VIII on the top of the *Shahi* tump mound. This furnishes a valuable confirmation of the relatively late age assumed for the remains of the deposits there. There is close similarity too to the size of the mud bricks excavated by Mr. Hargreaves at the burial ground of the Sohrdamb Nal or 21"×9"×3½" and 23"×9"×3½". The agreement is of special interest in view of the prevalence of the Nal type of pottery at the site. The face of the bricks showed clear signs of having been exposed to fire. It was in keeping with this that in the ground below the stone edging of the floor mentioned above there was found a thick layer consisting of ashes and burnt earth. Mixed with them were small potsherds and white plaster evidently fallen from a higher portion of the wall which had once stood there. Among the potsherds excavated here and the more numerous ones found in II n the majority show patterns of the Nal type and the

rest simple geometrical designs in black. This fully agrees with the observations made regarding the painted pottery exposed on the surface. The only other object found was a small knife-like fragment of bone, neatly polished.

Clearing of dwellings III-V.—To the east of I, II and beyond an eroded Nullah formed in what probably had been an ancient lane, stone walls exposed to different heights above the ground indicated a complex of ruined quarters (see Fig 51). Of these the dwellings III-V, as marked in the sketch plan, Pl. II, were cleared. The room III, measuring 16 by 12 feet, had its entrance, 3 feet wide, opening towards the lane from the SW. corner. There was a fire-place built up with roughly laid stones against the north wall to a height of about  $1\frac{1}{2}$  feet. The room IV adjoining to the east was somewhat larger, measuring 18 by 15 feet. In the dwelling V further to the south two rooms were excavated. In the smaller one the wall towards the lane showed a small opening high up at the south-western corner, evidently meant to admit light and air. The numerous fragments of painted pottery found in these quarters are almost all of the Nāl type, as seen from the specimens reproduced in Pl. XXVII. In Nun. IV. 1, 2, we have fragmentary representations of beasts with long tails curled up on their backs and suggesting leopards or panthers.

Conclusions as to dating.—Limited as the extent of the excavation work done during my three and a half days' stay at this Nūndara site necessarily was, its results suffice to prove that when its occupation ceased painted pottery of the Nāl type was still in regular use. Concurrently with this, black-on-red ware with simpler geometrical motifs was also manufactured. Judging from the fact that only these two types of decorated pottery were found at the mound and taking into account that the deep-cut ravines on its slopes are bound to have brought to the surface debris also from the lowest layers, it seems safe to conclude that the period marked here by ware of the Nāl type was a prolonged one. The stratigraphic evidence furnished by exploration at the mounds of Shāhī-tump and Mehī leaves no doubt about this period being later than that from which the main deposits of those two sites date. The evidence of such early chalcolithic sites as Suktagēn dōr, Perāno-ghundar, Nazarābād, etc., points in the same direction. For the site of Kulh an earlier period of occupation seems to me also very probable while most of the deposits at the mounds of Āwarān are likely to belong to later prehistoric times.

## CHAPTER IX.—RUINED SITES OF MASHKAI

### SECTION 1.—GABAR-BANDS AND MOUNDS ON THE LOWER MASHKAI RIVER

By the afternoon of March 21st we had regained the Āwarān rest house and on the following morning we started with the lorries on the long journey northward up the Mashkai valley. It meant a welcome, if only gradual, change from the heat which in the barren low valleys to the south had made work in the open more and more trying during the greater part of the day. Owing



110 C TR L RGO I D D  
A C TO



I S T I T III D T T



to the difficulties of the road the lories had to be kept lightly laden and all *impedimenta* which could be spared for a time sent along on camels

Route up Mashkai valley—Above the open trough of Āwaraṇ the Mashkai river's course lies through a succession of narrow and utterly bare gorges right up to the point where a small area of cultivation is passed near the hamlet of Mungah kalat. All along this stretch of ground some 24 miles by the motor track from where this leaves the Āwaraṇ trough the slopes are so abrupt and rocky that no chance of cultivation is likely to have offered here even during prehistoric times. Anyhow no signs of once cultivated ground could be sighted from the road. Thus after crossing and recrossing the river bed winds among side Nullahs divided by narrow saddles

Ruined enclosures—It was near one of these saddles known as *Dedari* and about 9 miles farther up that a small enclosure was passed built with undressed slabs of freestone and resembling the enclosures seen near the spring of Gat bant above Nundara. The broken walls standing to a height of only 3 feet enclose a square of about 20 feet. A few plain potsherds of coarse make were found within. A similar enclosure 27 feet square inside was passed 2 miles onward and a third of the same dimension  $1\frac{1}{2}$  mile further on. At the last the entrance 4 feet wide was recognizable on the south. Among some potsherds of coarse ware found here one showed an indented relief band. As the road for the most part follows an earlier camel track it seems likely that these enclosures may mark the position of old watch posts or perhaps halting places

First Gabar bands met—Somewhat more open ground was reached about 4 miles below the modern watch post of Mungah chauki and here a series of 'Gabar band' walls were first met stretching down from the slope on the east and across a small peneplain. Judging from their direction they could only have served to control rain floods coming down the hill side and to direct it to what cultivation terraces may once have existed below. Curiously enough one of these walls crosses a torrent bed, some 15 feet deep and runs up the opposite rocky slope in exactly the same direction from east to west. It seems difficult to account for this continuation otherwise than by assuming that when this band was constructed the Nullah was only a shallow drainage channel and the ground above the wall now cut up by erosion into little ridges and terraces, capable of cultivation. Can all this change of surface be the result of diminished rainfall and consequently increased denudation and erosion? Near the lowest of these Gabar bands I noticed a small ruined enclosure and near it a little circular mound faced with heaped up rough stones just as the one seen near the 'Gabar bands' first met on the way to Malar.<sup>1</sup>

Beyond Mungah chauki the bottom of the valley opens out to a width of over a mile. There amidst scrubby jungle small patches of cultivation are met with at intervals. Like most of the arable ground higher up in the valley they receive irrigation from black water i.e. channels conducting water from spring

<sup>1</sup> See above p. 114



and perennial pools to be found here and there in the river bed. Two miles beyond where the road near Mungali chauli crosses the river there completely dry. I noticed once more a succession of 'bands' stretching across the bare stony peneplain. Some run down the slope from the broken hills others across the peneplain as if meant to hold up flood water. Patches of bare alluvium near them show that by such means a fertile surface layer of soil could still be produced here.

**Sohr damb of Tank**—Then on reaching the point where the Tank river issuing from the hill range to the west joins the Mashkai I visited the site known as *Sohr damb*. In the angle formed by the two rivers and about half a mile to the north of the road there rises the remnant of a high alluvial terrace to a height of about 120 feet above the bed of the Tank river. Below it extend well watered wheat fields. The terrace is eroded into steep cliffs on its north eastern face and on its top bears remains of very rough walls built with large water worn stones and evidently belonging to a ruined circumvallation. No structural remains are traceable within the fortified area which judging from the scantiness of potsherds is likely to have served only as a temporary place of refuge. Among the painted pottery pieces with coarsely executed geometrical patterns in pink or red over buff ground prevail. Like the fragment Sohr, I (Pl XXVII) bearing a voluted and notched relief ornament these pieces recall ware from the great Dabar kot mound belonging perhaps to early historical times.

**Ughar damb**—After regaining the road about a mile from where we had left it we passed for two miles over a small plain stretching between the right bank of the Mashkai river and a chain of low ridges to the west. It is crossed in many places by Gabar bands and is known by the name of *Ughar*. Owing to the vicinity of the river bed it bears plentiful scrub and tree growth. A small portion of this plain was under cultivation until recent times from a Karez now abandoned. Where this passes at the foot of a hillock known as *Ughar damb* we pitched camp.

**Gabar-bands south of Ughar**—On examination next morning this hillock formed of conglomerate and about 120 feet high, proved to be covered on its top with remains of rubble built dwellings. Among the very scanty pottery found here are two small fragments of painted ware like that found on *Sohr damb*. The ground which stretches to the south from *Ughar damb* between the road and the low swelling ridges lining the valley bottom on the west proved of distinct interest on account of the extensive bands here traced (Pl 13). For about a quarter of a mile a stone faced embankment can be followed along the eastern foot of a ridge apparently intended to catch the rain water from the latter and guide it towards a flat patch of clayey ground lying in a recess of that ridge. This patch about 200 yards in diameter was certainly suited for tillage. A continuation of the same band now broken seems to have closed the narrow bed through which the drainage from this flat ground now escapes towards the river.

Beyond this bed a continuous embankment some 410 yards in length runs to the south west, keeping at a distance varying from 40 to about 100 yards from the slope of the low ridge. The stone walled front of this *band* facing eastwards shows a height up to 10 feet in places. The rampart behind measures up to 18 yards across at its foot. Where the end of the *band* approaches a small projection of the ridge it is broken by a Nullah. Big boulders lying in line across the bed probably mark the position of a weir.

At a point about 300 yards from the north eastern head of this great embankment there diverges another *band* to the south and after some 190 yards turns sharply to the north west towards a small outlier of the ridge. Near the corner of the embankment a patch of raised ground is strewn with fragments of pottery among them are glazed and decorated pieces indicating early mediæval occupation. Proceeding from here along the road to the south west smaller *bands* could be seen striking across the low lying scrubby ground eastwards.

Then after some 200 yards the north eastern end of an outlying low ridge was struck which on its top bears the remains of rubble built dwellings for cire 110 yards to the south west. They are likely to have been occupied by those who once tilled the clayey flat towards the river bed. On this flat low stone lined banks dividing fields could be faintly made out and cultivation may have been practised here again in more recent times. But the *Gabar bands* at the foot of the ridges above the road as described and those so abundantly found farther up the valley manifestly go back to an early period when climatic conditions were more favourable and the tract could support a much larger population. Otherwise it would be difficult to account for the heavy amount of labour which the construction of so many and such massive embankments within a comparatively small area must have involved.

*Gabar bands above Ughar*—Even more impressive was the extent of the *Gabar bands* met after we had crossed the Mashkai river bed to the left bank close to our Ughar camp. The road thence leads up the wide alluvial fan of a large flood bed which descends into the valley from the hill range to the east. Thus here culminates in rugged peaks close on 7000 feet. The fan, fully half a mile across from east to west is covered with a network of embankments on both sides of the road. Specially instructive was the examination of two very massive ones reached  $1\frac{1}{2}$  miles down from camp. They descend the slope parallel to each other with a uniform distance of cire 16 yards between and are clearly intended to contain and guide a flood channel coming from the hills to the east. Their stone faced sides are both turned to the north. The southern of the two, *bands* preserved in places to a height of 7 feet, at its lower end serves as part of the enclosures which bound three successive cultivation terraces. Each of these contains a flat space of arable soil about 120 yards square in the case of the middle terrace and cire 120 by 80 yards in that of the one below it. The topmost enclosure is of triangular shape and bounded below at its base by an embankment of which the walled face still rises to 12 feet in height.

For fully a mile further up the wide alluvial peneplain is traversed by bands descending the slopes both on the east and west and by others running crosswise between them. The labour of thus winning arable land from otherwise sterile boulder strewn ground must have been enormous. Half a mile before reaching the point about 6 miles above our Ughar camp from where the reported mounds of Malasband were to be visited the road took us across a wide torrent bed which after rain must carry an abundant supply of water to the area just described. All this now runs to waste.

**Site of Malasband**—The remains of the *Malasband* site are situated among low alluvial ridges which line the left bank of the Mashkai river about two miles below the fort and small hamlet of Gwarjak. At the latter starts the narrow but well cultivated strip of ground which stretches up the river banks for some 30 miles to beyond Jebri. At Malasband there is found on the left bank of the river a belt of ground from half to about three quarters of a mile wide which between the above mentioned low ridges is at times reached by exceptional floods from the river and at others receives a certain amount of subsoil water. This accounts for the ample growth of trees and scrub over it.

Approaching it from the road we found plentiful pottery debris strewn patches of bare clayey or stony ground. Most of the potsherds were of plain coarse ware but there were also fragments of glazed pottery of a type indicating occupation down to mediaeval times. The dam first visited proved a small natural hillock about 50 feet high apparently composed of rubble deposits from the river and covered with water worn stones. No definite evidence of ancient occupation was traceable on its steep slopes. But on searching a low clay terrace at its south western foot there were found in one place two pieces from painted pottery bowls showing much effaced decoration in the Nal style (Mali Pl XXVII). A little digging done there brought to light a small fragment of worked alabaster and a few minute bone beads. Together with some other fragments of painted pottery all affected by the dampness of the soil they prove that occupation here goes back to the chalcolithic period.

**Mazena dam**—From here a tramp of about three quarters of a mile to the north across a belt of alluvial clay with plentiful scrub brought us to the southern end of the *Mazena dam* (the Big Mound). This is a long stretched natural ridge thickly covered with debris of unhewn stones and striking like the other ridges parallel to the river. Its maximum height is about 40 feet. It extends from NE to SW for a distance of about 600 yards and has its greatest width of circ 240 yards towards its south western end. Along the comparatively narrow crest of the ridge there can be traced the remains of structures with roughly built walls of unhewn stone evidently brought from the river bed. One or two of these ruins, with thick walls just showing above the surface appear to have been of large size. At the north-eastern end of the Mazena-dam and along most of the lower slope facing the river there can be traced remains of a massive circumvallation about 6 feet thick built with big unhewn boulders. In places it still stands to a height of from 3 to 9 feet.

Pottery remains—On either side of this circumvallation painted potsherds could be picked up amidst more plentiful plain ware, while along the crest pottery was distinctly scanty. Among the painted pottery the majority show simple geometrical patterns in black over red (see Maz 1 Pl XXVII) some also similar motifs on buff ground. To an early chalcolithic period point the disproportionately small bases of two cups one of them of dark grey clay, resembling those so frequent at the Zhob sites. There were picked up on the surface two small broken terracotta figurines of bulls (Maz 2 Pl XXVII), also fragments of thick perforated ware and of a chipped chert core. All these agree with the assumption of occupation in early chalcolithic times. The presence of potsherds decorated in various ways with parallel incised lines may be noticed. The same types of pottery were found also on a continuation of the ridge to the north east separated from the circumvallated area by a small drainage bed and extending for about 380 yards in the same direction. This portion of the ridge is lower and its top being fairly flat allows the remains of dwellings to be more readily recognized.

Sohren dumb—At the opposite end too the remains of Mazena daml have an extension on the somewhat higher ridge appropriately known as *Sohren dumb* the Red Mound. A narrow gap separates the two. The nearest part on of this ridge is covered with potsherds of plain but manifestly ancient red ware for a distance of about 50 yards as measured at its foot.

There can be no doubt that the Mazena dumb marks the position of a considerable settlement. Its lands probably included the extensive area covered with Gabar-bands in the direction of Ughar as well as the riverine belt now abandoned to scrubby jungle. Systematic exploration such as the site obviously deserves would owing to its great extent claim protracted labours. Given adequate time it would offer no special difficulties since a fair number of diggers could be collected from the villages higher up the valley.

Burial Cairns near Gwarjak—Information received about certain large pots having been unearthed by villagers of Gwarjak some seven years before at a place known as *Lak Landaqi Shan* induced me to cross the river and to visit the mouth of a small gully, debouching towards it about one mile to the west of Mazena dumb. Here the villagers had been led by an accidental discovery to dig up some thirty earthen vessels containing ashes with fragments of human bones which they cleared and took home for domestic use. As in the following year a number of deaths had occurred among them they carried the pots back, burned them afresh and established a *Zi rat* at the spot and duly sacrificed there a number of goats, two fowls and a cow to appease the spirits.

On the stony slope both below and above the new *Zi rat* a humble enclosure with a few ragged staffs there were seen small scattered stone heaps roughly circular, similar to those first found at Moghul ghurjai. A number were manifestly undisturbed. From below one little burial cairn quite close to the holes marking previously dug up deposits there was unearthed the large coarsely made jar, apparently handmade seen in Fig 10. It contained small calcined fragments of human bones and ashes also two charred date

stones probably meant to represent a funerary provision of food. It measured 15 inches in height and 14 inches where widest. Below another cairn to the south west of the Ziarat were found fragments of calcined human bones and pieces of coarse red pottery showing a whitish surface. A few yards below this another burial deposit comprised two smaller pots of coarse ware both containing fragments of calcined bones. One was 10" high, 12" wide and 7" across the mouth the other showed corresponding measurements of 12" 10" and 8" respectively. In the latter was found also a small fragment of copper.

These finds sufficed to prove that the burial customs observed here corresponded partly to those followed at the chalcolithic sites of Zhub and Suktagen-dor and partly to those noted at the later cemeteries of Tiwanni Zangnan and elsewhere in the Kej valley. Judging from the way in which the deposits were marked by cairns and from the place in which they were found far away from any ancient habitations it appears likely that they date from the same period as those later cemeteries.

## SECTION II—THE MOUNDS OF GAJAR AND SHAHDINZAI

On the morning of March 24th I left Malasband for Gajar, the headquarters of the Niabat and chief village of Mashkai some 13 miles up the valley, where my men were anxious to celebrate the great Id marking the close of the Ramazan fast. The strenuous work in the field and the increasing heat had added much to the trials of this month since our departure from Turbat. On our drive up the valley it was a feast for my eyes to catch sight again and again of the fresh green of the wheat fields which line the river bank in an almost unbroken stretch from above Gwarjak. Most of this cultivation is carried on with the help of irrigation from springs in the river bed. In addition the wide *thalweg* with its alluvial flats by the river affords room for Khushkai land dependent on rain floods in the river bed and side torrents. That such cultivation could be considerably extended in the main Mashkai valley given a larger and less indolent population was the conviction of Allahdad Khan the capable Naib of the subdivision who gave us a hearty welcome at the fort and rest house of Gajar. The cooler air to be found here at an elevation of about 3200 feet was refreshing.

**Kalaro damb**—The following day was used for the examination of the three dams reported at Gajar. The first visited is known as *Kalaro damb* and rises above the right bank of the river about 1½ miles below the fort of Gajar. It seems a natural ridge composed mainly of rubble deposits from the river, the marks of ancient occupation are confined here to potsherds strewning the slopes. Among them painted pieces are scanty but these all show patterns painted in black on terracotta or buff and closely corresponding to the type prevailing at the Kulli site. Contemporary occupation is hence probable.

**Men damb**—The mound known as *Men-damb* about 1½ miles to the north east of Gajar and a quarter of a mile from the right bank of the main river bed,

proved a site of greater interest. It takes its name from the small hamlet of Men about the same short distance to the south of it. At first sight the mound owing to the masses of loose stones such as might be found in the river bed, suggests a natural origin. But the fact of its rising in complete isolation above the flat bottom of the valley, and the observation made at a point about 50 yards from the southern foot of the mound make it appear highly probable that by far the greatest portion of the mound is built up with debris accumulations from ruined structures. At the point just referred to the edge of the pottery strewn terrace like area which fringes the mound proper has been cut into by a channel conducting the water of a Karēz. There above a natural bank of clay 10 feet high remains of walls built with water worn stones and mud are clearly exposed to a height of several feet. There is good reason to assume that the mound proper which rises to a maximum height of circ 35 feet above the top level of the terrace mentioned is composed of similar structural remains. The maximum length of the mound including the low pottery strewn terraces is about 190 yards from east to west and its width about 100 yards. The top of the mound partly occupied by a modern enclosure measures 75 yards from NW to SE and 50 yards across where widest.

**Painted pottery and figurines.**—The fragments of painted pottery collected on the surface show close affinity in patterns and colour to the painted ware of the sites of Kulli and Sāh damb Jhau. This observation is fully borne out by pieces like Men 1 (Pl XXVII) with the same incised decoration as found at both those sites and still more by numerous terracotta figurines of bulls like Men 23 (Pl XXVII). The latter specimen shows perforations through the hump and thighs. Finally we have striking evidence of that affinity also in the very archaic head of the goddess Men 4 (Pl XXVII). The Men mound in view of its early date would invite excavation especially as the village of Gajar which together with the hamlets near by counts over 400 people could readily supply the needful labour.

**Gajar mound.**—The third 'damb' of Gajar is a small mound (Fig 59) rising a few hundred yards to the south of the present fort containing the Naib's quarters. Its top was occupied until quite recent times by a now destroyed fort of the local Mirwan chiefs. Its walls are built with rough stones set aslant to right and left in alternate rows and thus prove their modern construction. The mound at its foot is composed of a natural terrace of clay up to a height of circ 10 feet. Above this rise layers of debris containing the remains of massive rubble built walls to a height of circ 20 feet. That the terrace was occupied in prehistoric times is indicated by fragments of painted pottery found at its foot but they are too few to permit of any closer determination of the type.

**Gajar-dambs absent above Gajar.**—On the morning of March 26th I left pleasant Gajar accompanied by Sirdar Rustam Khan of Jabin in order to survey the other and larger damsbs reported up the valley. The road led well above the left bank of the river and passed for the most part khushk la.

cultivation up to where the bold Laki hill (4 200 feet on the map) projects into the wide bottom of the valley. At its foot I noticed two small cairns and old Muhammadan graves. While moving up the wide open trough of the valley across the numerous shallow flood channels which descend from the high range on the east I could not help being struck by the total absence of Gabar bands which below Gwarjak had been so conspicuous a feature in the valley. It was the same all the way further up the Mashkai Valley as far as our route led through it. The fact though a negative one seems to call for an explanation. The one which has occurred to me as the simplest in view of the particular physical conditions of this limited area, is the following:

Embankments such as I have described in the eastern part of Kolwa and in the Mashkai valley below Gwarjak, would be useful for controlling the drainage and depositing fertile soil only where ground potentially arable but beyond the reach of regular irrigation is approached closely by hill sides of comparatively limited extent and drainage. Where large valleys gathering big volumes of drainage debouch on to a wide plain or where the mouths of such valleys lie miles away from ground with fertile soil and a slope sufficiently easy to be terraced embankments of the type such as those early builders of Gabar bands could construct would not prove sufficiently strong to meet the onrush of flood water and to turn it to good use. Or else the vagaries of the torrents ever raising their beds by the masses of boulders and detritus carried down and then obliged to seek fresh channels would after a time render the laboriously constructed dams useless.

**Mound of Nokjo Shāhdīnzai**—About 11 miles above Gajar the road passes two small palm girt oases situated within a mile of each other and distinguished as *Nokjo Shāhdīnzai* and *Nokjo Gazozai*. They both obtain irrigation from Karēzes fed by the subsoil drainage of a wide side valley which descends from the range to the east. Judging from the available supply of water the area of cultivation could here be considerably extended and support a population beyond the 600 souls located at the two villages in 1920. Close to the western edge of Nokjo Shāhdīnzai village ensconced amidst clumps of date palms, there rises a conspicuous mound (Fig 58). Its extreme southern foot is skirted by the channel in which the water of the Karez is carried down to fields near the river. Ancient pottery is to be found in plenty for about a quarter of a mile before reaching the mound from the road. The mound rises to a height of about 36 feet and measures about 300 yards at its foot from north to south. At its broader western end its width is approximately the same. Its top is level for about 70 by 50 yards and crowned by a ruined fort which was occupied until recent times. The walls are built with large uncut stones obviously taken from the debris of earlier structures.

**Types of painted pottery**—Painted potsherds are found in abundance all over the slopes and also on the top of the mound proving prolonged occupation during prehistoric times. The specimens reproduced in Pl. XXVII illustrate the varied types of patterns. Very numerous are pieces like Shah 3412 showing




FIG. 37 SOUTH WEST CORNER OF MURIEL DAM, WITH PIERCE II IN FOREGROUND, BEHIND CITY ARCADE




FIG. 38 FORT DAM AT LANSING, MICHIGAN, AND THE CITY ARCADE




FIG. 39 MOUND OF SHALLOON, WITH BURIAL CAIRN IN FOREGROUND



FIG. 40 CATHART FOR THE BURIAL CAIRN AT VAN KANADON, MICHIGAN, AND THE CITY ARCADE





simple geometrical motifs also hachured leaves and scrolls neatly executed in black over a fine dark red slip. Other more elaborate patterns which are painted in black over terracotta or buff and sometimes comprise also animal figures as on Shah 26713 belong to the type which prevails at the Kuli site. There too the impressed ornament of Shah 8 has its exact counterpart. To a somewhat later period I am inclined to ascribe pieces of less careful execution like Shah 9 with a voluted scroll ornament and others like Shah 511 where painted ornament is combined with relief decoration. The absence of polychrome painting, including that characteristic of the Nal type deserves particularly to be noted.

A significant indication is supplied by the numerous fragments of bull figurines all badly broken and by a figurine of the goddess, now headless but showing the characteristic base below the waist Shah 1. These clearly point to close relation in time and civilization between those who occupied this site for a prolonged period and the population which has left its relics behind in the lower strata of Shahu tump and at the large sites of Kuli, Sahdamb, Jhau and Mehi (see below). Fragments of clay bangles were found but no stone implements.

**Burial cairns**—Below the south eastern foot of the mound and beyond the edge of the pottery strewn ground there could be seen some roughly formed stone enclosures as shown by Fig. 38 in the foreground. A few measured approximately 5 by 4 feet, others less. In one opened there were found below only 5 to 6 inches of earth part of a skull apparently of a child with other bone fragments. By its side stood an open flat bowl, 8 inches wide at its mouth and a small jar measuring about 4 inches in height and across its bulging sides. Both vessels contained ashes and were of plain very coarse ware. In an adjoining enclosure only a few bone fragments were found. There can be no doubt about these burial deposits belonging as at Jiwani, Zimni, etc. to a later period.

**Move to Mehi**—The same day a short move 6 miles further up the valley brought us to the Damb of Mehi situated at the north western foot of the precipitous rocky hill which the map marks with the height of 4717 feet. On the first rapid survey of the site the finds on the surface proved so interesting that after inspecting also the two small 'damb's' reported at the village of Jehri 1½ miles beyond and described further on I had the camp pitched in a palm grove to the north of the Mehi damb with a view to trial excavations.

Jehri village is the last permanently inhabited place in the north of the Mashlani valley and enjoys the benefit of several karezes fed by subsoil drainage from the river bed. Among the seminomadic households who cultivate the extensive *Khmshkoba* fields of Mehi with help of flood water from the river it was possible rapidly to collect labour and the two Sindis of Jehri offered willing help. So by the morning of March 27th work could be started at the Mehi damb with some 30 diggers a respectable number for these parts.

## SECTION III—REMAINS OF THE MEHI SITE

The mound of Mehi rises between the foot of the precipitous cliffs of the Mehi hill and a stretch of fields to the north and west. As the sketch plan Pl 12 shows its maximum extent from NE to SW is about 360 yards and its greatest width in the opposite direction about 330 yards. The highest portion of the mound, a kind of modest acropolis rises to 50 feet above the field level. It is heavily encumbered with fallen walls of rough stones. Both to the north and west it drops down very steeply to torrent beds which descend from the hills towards the river. Floods in those beds have in more than one place laid bare ancient walls and debris layers. To the east and south the mound shows easier slopes and terraces all encumbered with the debris of decayed stone walls. Here and there the rough masonry of such walls is still traceable standing to a height of 2 or 3 feet above the surface. All over these terraces and also over the top are scattered late enclosures of heaped up stones which appear to have served as shelter for flocks or for the location of mat huts.

Remains of walls exposed.—Walls built with large unhewn stones and lacking regular courses crop out in places from the debris also on the northern and north eastern slopes of the mound. The interstices in their very rough masonry are filled with earth and small stones. At one point the cutting of a deep bed partly artificial has exposed remains of a massive wall overlain by debris. In this bed flood water from the hill sides to the north of the Mehi hill is conducted round the mound and thus prevented from breaking the embankments protecting the neighbouring fields. Some 25 yards higher up in this cutting the mound shows a vertical face to a level of c. 16 feet above the bottom of the Nullah. Here one of the labourers declared some years before to have noticed a hollow in which complete pots were exposed. The debris mixed with potsherds which was believed to have hidden the hollow was cleared but without revealing the spot. In the course of it the following stratification was observed: at the bottom 3 feet of rubble and earth next 4 feet of rough stone masonry and on the top of this again clay and small pieces of rubble.

Abundance of potsherds.—All over the mound plain potsheids of superior red ware and also painted pottery fragments could be found. But from the first the great abundance of the latter attracted attention to the terrace like top of a small spur jutting out to the south west at a height of about 30 feet. Unfortunately hollows on the flat surface clearly indicated that this area had been disturbed in recent years and from Sirdar Rustam Khan I soon learned that Jehu villagers had dug up pots here for use in their homes. They were said to have been of large size and plain but only one of these could subsequently be secured for inspection. The painted pottery of which a great quantity was collected here on the surface and of which characteristic specimens (Mehi 112) are reproduced in Pl XXVII showed very close resemblance in patterns colour and material to that found at the sites of Kulh, Shahdamb, Nau and Shahdambai. The numerous pieces with simple geometrical patterns carefully painted in black on a dark red slip like Mehi 3 6 9 10 12 strikingly

recalled also the early chalcolithic ware of the Zhuh and Lorala sites. Other more elaborate patterns in black over red terracotta or buff slip with animal and plant forms like Mehi 12 & 14 have their exact counterparts among the painted pottery of the Kulh site. Only on two small fragments, Mehi 15 & 16 were to be found motifs and ground colours cream white and a deep purple which are peculiar to painted pottery of the Nil type. On the other hand the piece Mehi 13 shows the mat-marked treatment of the surface which is frequent at early chalcolithic sites. Mehi 17 (Pl XXX) an intact cup of plain red ware found on the surface evidently comes from a disturbed burial deposit.

Figurines of bull and 'goddess'—Full confirmation of the indications derived from the pottery on the surface was furnished by a dozen or so of bull figurines which were found there. They were all broken. Of three representations of the goddess little more survived than the lower portions of the bust. Everything combined to show from the start that the terrace over which painted potsherds lay so thickly was covered with remains of a period approximately corresponding to that during which chalcolithic sites so widely separated as Pénano ghundai and Kulh had been occupied. The excavation effected over this area, marked II III in the sketch plan brought to light plentiful relics of interest and finally cleared the question as to how its deposits had been formed.

Trial trench I cut.—In view of the disturbance these deposits had suffered through the villagers' previous diggings it seems advisable first to give an account of the evidence which the cutting of a trial trench I yielded. This was carried from a level about 10 feet above the foot of the mound over a distance of some 75 feet up the slope to the western edge of the excavated area on the top of the terrace. The width of the trench was 6 feet and the average depth reached in its nine sections about the same. Throughout the ground here proved to have remained undisturbed. The observations and finds made throughout from the lowest section I 9 to the uppermost I 1, justify the conclusion that the slope of this outlying portion of the mound is here covered by a thick layer of debris in which the remains of cremated human bodies were buried during a period approximately coeval with the prehistoric occupation of the mound. This custom of disposing of the dead after burning agrees in essentials with that observed at the early chalcolithic sites of Zhuh as well as Suktager dor. But while at these sites large pots were used for the deposit of the ashes and bones from completely cremated bodies, the remains found in different sections of I indicate that besides this other and more perfunctory methods were in use here.

Human remains in I 8, 9.—Thus in I 9 large fragments of calcined human bones were covered with a large broken bowl and amidst them lay the small painted jar I 91 (Pl XXVIII) broken in antiquity and containing earth mixed with ashes. There was nothing to indicate that the fragmentary cups, dishes, small bowls and miscellaneous potsherds found close by of which specimens are seen in Pl XXVIII had any connexion with these remains. Nor can this reasonably be assumed of the bull figurines which here as in all other sections as well as

throughout II and III turned up in great numbers. Almost as frequent as these were throughout the figures of the goddess, the varying representations of which will be discussed further on. The head of one with grotesque bird-like face I 97 a (Pl XXXI) was found in I 9 besides the torso of another showing well modelled breasts. Whether the figurine I 96 (Pl XXVIII) is meant to represent a ram or some other animal with curved horns is doubtful.

In I 8 a large pot broken in antiquity, was found at a depth of 4 feet. It held small bone fragments and ashes besides the broken high base from a large cup or bowl. The pot was kept in position by stones fixed around its foot. In the same section but on a level about one foot lower there lay six skulls in a heap over calcined bones. The skulls were all small, some looking like those of children, yet some of the mixed bones cleared were manifestly those of adults. Under one of the small skulls to the left lay a child's copper bracelet I 82 (Pl XXXI). All around the earth was permeated with charred fragments and ashes suggesting that cremation had taken place on the spot and the remains of the bodies been subsequently collected there. Under another skull to the right lay a broken pottery cup like I 95 (Pl XXVIII).

Finds in sections I 5 7.—The sections I 5 7 yielded no definite burial remains but numerous small cups and jars all damaged. Specimens of them are seen in Pl XXVIII. Whether painted or plain they all closely resemble in shape those found within cinerary vessels at Periano glundur.<sup>1</sup> In those from I 6 small bones and ashes could be recognized. The small dish I 62, the high base of a painted bowl I 63 and the fragmentary little bowl of black stone I 64 with an incised geometrical pattern deserve notice. The quaint beast of which the head is preserved on the large painted potsherd I 72 closely recalls the similar design of a bull found at Kuli (see Pl XXI Kul I 16).

Burial deposits in section I 4.—In I 4 a burial deposit was again unearthed in the shape of the large urn filled with earth, bone fragments and ashes. A broken saucer-like piece of pottery covered its mouth. In the same section was found a small jar I 41 holding bone fragments. The broken high beaker, I 42 with its disproportionately small base recalls by its shape some of the funerary ware from Shahi tump. That it had served for ordinary use is not subject to doubt in view of its strong well finished make. Among the miscellaneous pottery fragments found here mention may be made of the piece I 43 from a small pot of very fine grey clay which on its wall is provided with an ear. Here too was found one of the very few painted potsherds from this site in which an additional colour, a very dark purple, is used besides black on buff ground. Two more fragments of this kind turned up in I 2.

Ceramic finds in I 1 3.—Section I 3 also yielded numbers of fragments from small cups among them I 31 notable for its elegant base. Both in I 1 and I 2 broken bull figurines lay close together in small heaps. The same was the case in the topmost section I 1 and there some of the neatest examples of the local potter's work were found but all damaged. Such are the tall elegant vases,

<sup>1</sup> See *N. E. Ind. Sta. Tour* Pl. VII & VIII.

I 129, with a fine red slip the little painted saucer I 11 the painted bases of bowls I 145 We have pieces from flat dishes painted on the inside in I 168 and from the wall of a large painted bowl in I 17

Clearing of area II—III—As already stated the topmost section of the trench I adjoined the edge of the debris covered flat area on the top of the south western terrace of the mound This area was completely cleared and proved to be covered with a layer comprising earth and small stones mixed with broken pottery, ashes and burial deposits to an average depth of about 2½ feet The extent of this area was approximately 120 feet from north east to south west and close on 40 feet across No structural remains whatever were met with in the course of the excavation This was carried on along the longer axis of the area but from opposite sides marked II and III respectively Consecutive sections were indicated on both sides merely for the sake of facilitating determination of the find spots of individual objects

Area used as burial place—The general character of the objects was very uniform throughout as far as remains of painted pottery and terracotta figurines were concerned Consequently it will be best to review them *en masse* after noting first those special finds which throw light on the use made of this area as a burial ground Observation extending over the whole area showed that for over one foot from the surface the soil was mostly loose This indicated the approximate depth to which the ground had been generally disturbed by the villagers digging for pots etc Below this level the ground was harder and full of small rubble which might have been deposited from completely decomposed mud structures Below the depth of circ 3½ feet the layer containing plentiful pottery debris etc ceased completely and our excavation was therefore not carried lower down Owing to the total absence of recognizable structural remains above this limit it was not possible to determine with any certainty whether the layer thickly permeated with potsherds had been deposited during a period of protracted occupation of this area before it came to serve as a kind of cemetery or whether this accumulation of pottery debris was due to use made of the plot as a waste space for depositing rubbish In any case it is important to note that the painted pottery and terracotta figurines uniformly found throughout the layer show exactly the same types as the corresponding finds from trench I, already described and from the cutting IV made on the slope of the highest portion of the mound to the NE of II III (see below)

Copper objects deposited below bones—It may be a result of the preceding disturbance of the top portion of the ground that no human remains or ashes were noticed until in section II 2 there was found at a depth of 2 feet a small collection of calcined bones Below them lay the large mirror II 21 a and decorated harpin II 22 a both of copper and reproduced in Pl XXXII also the fragment of a small bottle The mirror 3" in diameter has an elegant handle and the harpin 6" long a large neatly worked head This burial deposit is of special interest because the find having been made in ground obviously undisturbed definitely proves that cremated remains were sometimes buried without having been placed first in cinerary pots, as was the case with the burials of I 4

III 10 etc and at the Zhob sites. It also makes it clear that the potsherds and fragmentary bowls and cups found in the same section near by did not form part of the deposits as they would in this case not have been found scattered on varying levels.

**Burial deposit in III 6**—It was different with the instructive burial deposit unearthed in III 6. Here at a depth of 2<sup>1</sup> feet and overlain by a mass of pottery debris there were first found three large conical cups of uniform size (III 6 2 Pl XXX) stuck together and embedded amidst plentiful ashes and remains of charred wood. Within the middle cup lay the small copper bowl III 6 4 (Pl XXXII). Close to the cups were found the thin copper disc probably used as a mirror III 6 5 (Pl XXXII) and two copper bangles III 6 6 7 with the fragment of a third. A small neatly decorated bone stud or seal III 6 18 (Pl XXXI) was also found here.

Close behind these objects and on the same level there was found a partially burnt skull lying in a broken condition amidst ashes and fragments of charred wood with which were mixed small bone fragments. On the top of these lay three terracotta figurines of the goddess' of the usual type also a copper hairpin, III 6 9 (Pl XXXII) 4½" long with a lapis lazuli bead stuck on its head. Below the skull and bone fragments there was a layer of burnt earth and ashes about one foot thick. Everything pointed to the body having been cremated at this spot and the cups and other objects having subsequently been placed near what remained of it. It was of interest to observe that several small fragments of painted pottery were also contained in the earth mixed up with ashes. From this it may safely be concluded that the ground was already covered with potsherds at the time when the cremation and burial took place.

**Cinerary urns**—By the side of such simple burial on the spot of remains of cremated bodies their deposit in cinerary urns was also practised. This became evident from finds made in sections III 10 11 adjoining the topmost portion of the trench I. In III 10 there came to light under 1½ feet of earth and pottery debris a large urn. It measured 22 in height 24 in width and 18½" across its mouth. The base was only 5½" in diameter. It contained near the bottom a cremated and broken skull together with a small bronze bangle. Above this lay ashes and on the top loose earth with small bone fragments. A second cinerary urn of small size found under only one foot of earth held below bone fragments including parts of a child's skull together with ashes and above amidst earth some fragments of small pots and of a bull figurine. Whether these were placed there on purpose or only accidentally is uncertain.

**Contents of cinerary urn in III 5**—In section III 5 and not far from the skull and funerary deposits III 6 1 10 there was discovered a third cinerary vase under 2½ feet of earth and pottery debris. It measured 15½ in height 18" in width and 13 across the mouth. Its contents were a large stone with smaller ones embedded in earth around it next a layer of earth with ashes and fragments of charred wood and pottery including a painted potsherd. In the same layer were small pieces of calcined human bones with the lower portion of a figurine of the goddess among them. Then followed another layer of earth

and on the top a large stone nearly closing the mouth. Though the deposit of bones was here scanty care had been taken to protect them. The contents of the intact cinerary vessels now described dispose of the surmise which had at first occurred to me that many of the small bowls and jars found in a fragmentary state in II and III might have originally been contained within large cinerary vessels as at Perimoghundai and subsequently thrown out and broken when the villagers were digging out and removing such pots.

Shapes of pottery from II-III.—Of the many pieces of pottery found in II and III which on account of their decoration or shape are of interest I have endeavoured in Pl. XXIX-XXX to reproduce representative specimens. They comprise further illustrations of the types which have already been noted when reviewing the pottery finds from the surface. Hence briefest references to characteristic pieces will suffice. The large goblet III 613 9" in diameter and 8½ high found broken but nearly complete is a fine example of the potter's craft. It belonged to the same burial deposit in III 6 which yielded the triple set of large conical cups III 623. Painted bases of high tizzis or goblets are illustrated by II 74 and III 21.

Specimens of the prevailing types of small cups and jars either with diminutive bases or else with flat feet are seen in II 52, 101, III 151, 31, 424, 112 and III 41, 111. Little flat saucer-like cups like II 21, 71 are very frequent. They may have served for lamps. Specimens of painted bowls, with fairly straight walls and wide mouths are III 13, 435, II 31. To similar bowls are likely to have belonged III 612, II 11a, 42, 3. Painted decoration inside is shown by the fragments of cups III 73, II 63. The two pieces II 22a, 1 both broken look as if they had served as top portions of lids. The saucer or dish II 20 shows a painted pattern very common in similar pieces of varying size. Another pattern is seen in II 10. III 32 is apparently the haft of a flat dish or pan.

Painted decoration of pottery.—Turning to the types of painted decoration we find those usual on the outside of large vessels illustrated by the pieces II 12, 40, 82, III 26, 51. Animal figures frequently found on the outside of both large and small vessels are bulls (see III 11, 48, 81) and large horned mountain sheep or goats (II 423). A bird (lark?) is shown outside on II 12a. Inside open dishes or bowls are seen well drawn fishes (II 17, 81, III 15, 34, 16), large horned mountain sheep (III 131) or bulls (III 17). On the outside of smaller cups, bowls or jars geometrical patterns are most frequent. They are composed of straight-lined figures often hachured within simple scroll, zig-zags or hooks. Plant motifs as on II 10, 40, III 51a, 614 are far rarer. In the great majority of pieces the painted decoration is executed in black over a red or dark terracotta slip. A fine red slip is found often also on unpainted vessels like III 62, 3, 13. Otherwise the buff terracotta ground colour of clay is left on the surface of both painted and unpainted ware (e.g. III 111, 13, 20). It is important to note that among the hundreds of painted fragments I could find here only three on which a second colour, a very dark red, has been used as a band in addition to black over a light terracotta ground (II 11, 92). Many



with curved lines and other characteristics of the Nal type are conspicuous by their absence

Carved stone fragments, figurines —Of decorated pottery apart from the painted ones we have a few pieces ornamented like II 44, with an incised or impressed pattern showing a cleverly designed circular swirl or wave line. In each case this impressed motif is found in the centre of the inside of a dish or open bowl. Of grey ware only very few pieces, less than half a dozen, were found, all unpainted. Except for one small fragment of an alabaster cup the only examples of stone used for vessels are the neatly worked bowl III 611 and the incised fragments, II 13, III 113, all carved from a fine grained grey stone. The fact that not a single piece with relief decoration was found either here or elsewhere at the site as well as the total absence of handles deserves special notice. Throughout II and III terracotta figurines both of humped bulls and 'goddesses' were found in very great numbers. To these and the other figurines of the same types unearthed reference will be made further on.

Finds in trench IV —In order to test the ground on the higher portion of the mound a trench 10 feet wide, marked IV in the plan was dug up its slope from a point circ. 65 feet distant to the north east of the debris area III. The highest section 1 in this trench reached the top level of the mound. The trench was cut to an average depth of 6 feet and throughout yielded broken pottery exactly resembling in make, decoration and shape that found in II III. But the quantity was comparatively small. Terracotta figurines also turned up in all sections. From the fact that under the heavy mass of rough stones strewn the surface of the slope only loose earth and small rubble were struck in the lower sections up to 2 it may be concluded that the structures the debris of which is embedded in the mound were mostly built with sun dried bricks, stamped clay and small stones set in mud. The absence of stone masonry of the kind which is so abundant at Kuli and the Shah dams of Jhau and Nundara is accounted for by the great hardness of the rock composing the hills about Mehi, apparently limestone, far more difficult to work than the shale prevailing near the former sites.

Structural remains and finds in IV 12 —Only in the topmost sections 1 and 2, were structural remains traceable in the shape of walls of rough stones set in mud. In the corner of section 2 there was found near the wall separating it from section 1 a large flat slab, measuring about 2 by 2½ feet and marking a hearth. The earth was here reddened by fire also the mud bricks which supported the slab. Several terracotta figurines were found in this room, also the small elegantly shaped vase IV 21 (Pl XXX). Section 1 by the side of a small apartment not completely cleared contained a recess about 2½ by 4 feet. The earth filling it showed signs of having been exposed to fire. In it there were found a concave grinding stone and a flat roller, of exactly the same rough type as discovered in the dwelling Kuli I. Here too was found the large painted jar IV 11 (Pl XXX), closely resembling in style and pattern of decoration the jar Kuli III (Pl XXXIII). It had suffered damage along the rim in antiquity and owing to inferior make broke in course of extraction. The painted

decoration too in brown over buff ground is very coarsely executed. The difference of make and decoration from the fine black on red pottery found lower down on the mound and especially in II III is so great as to suggest in conjunction with the position of the room IV 1 on the very top of the mound that this jar belongs to the latest period of prehistoric occupation of the site.

Terracotta figurines abundant.—Some special remarks are still due on the terracotta figurines which were found in such abundance at this site. A representative selection of specimens is shown in Pl XXXI. Excepting a quite insignificant number they all represent either humped bulls or are busts of the 'goddess'. Among the exceptions are two horned rams of which Mehi I 96 is shown in Pl XXVIII and the smaller one Mehi III 82 painted with stripes to represent the fur in Pl XXXI. We have an interesting piece of modelling in Mehi II 2 7a (Pl XXXI) which shows a dog astride the broken rim of what was a bowl or pot. What animal head the coarsely worked fragment Mehi III 6 15, with holes for eyes and ears, was meant to represent is uncertain. Of humped bulls the collection contains no less than 199 specimens (146 from II IV 43 from I and 10 from the surface) varying from less than 2 inches to about 4 inches in length. A still larger number of fragments were too much injured to deserve removal. Not a single piece was found intact which seems to justify the conclusion that these figurines had all been thrown away because they were incomplete and hence unfit for ceremonial use.

Significance of bull figurines.—Considering the numbers of these representations of the humped bull and the uniformity of the type throughout all Chalcolithic sites of Makran and Thalawan it seems difficult not to believe that this animal was like its Indian counterpart the 'Brahmani bull' an object of popular reverence if not of actual worship. If this assumption is right the temptation is obviously great to seek some connexion between that prehistoric worship of the population which occupied the extreme western marches of India before the 'Aryan' invasion of Vedic times and the great role played by Śiva's bull in Indian cult from a very early historical age. There is scarcely any indication of such a cult to be found in the oldest Vedic literature. This might lead us to infer that it was an inheritance from much earlier times to which the autochthonous population of northern India with its deeply rooted archaic bent has clung notwithstanding the great transformation brought about in its civilization, racial constitution and language by the triumphant invasion of its northern conquerors. But the subject touched upon is too wide and at present still too speculative to be pursued here further in what is meant for a plain record of antiquarian facts.

Figurines of 'goddess'.—Problems quite as interesting are raised by the female figure of which not less than 92 specimens in varying states of preservation were brought to light in the course of our trial excavation at this site. For the sake of convenience I have referred to her as the 'goddess'. I think it may be taken for certain that all the figurines of which Pl XXXI reproduce a score of typical specimens are intended to represent a female for though the breasts so prominent in the pieces less elaborately decked with ornaments,

line III 114 17 I 45 III 51 33 are not shown in others yet the presence of the same elaborate *coiffure* with long tresses is sufficient to mark the sex. Throughout we observe the identical and very archaic treatment of the face which is almost bird like and also where enough of the figurines is preserved the same pose of the hands placed against the breast or waist.

It is important to note that here as in the case of all representations of the goddess found at other sites the figurines whenever their lower portions survive, invariably end below the waist in a flat base. This proves that all of them were meant to be set up presumably on some stand or platform. Variety is introduced mainly in the treatment of the hair dress and of the ornaments around breast and neck. Obviously the ancient modeller found it easier to work on such details in the flat. Particularly ornate jewellery is shown *eg* by III 617 71 53 22 II 10 2a. No indications of dress are attempted for the folds sometimes seen on the arms as on III 22 51 are probably meant to represent armlets. Just as in the case of the humped bulls all figurines of the goddess were damaged in antiquity often lacking the head arms or lower portion of body. Curiously enough the only almost perfect specimen III 616 only slightly damaged in the face is one of those found on the burial deposit of ashes and bones described above.

Representation of mother goddess —I have already before given expression to the surmise that these figurines of which rare but closely corresponding specimens had been found also at the chalcolithic sites of Zhob may have been meant to represent a female divinity of fertility the mother goddess whose worship meets us in widely distant parts of Asia and Europe throughout historical times. The fact that we have found her at the Kulh site shown once with a babe in her arms may lend support to this conjecture.<sup>3</sup> But the close connexion which in early mythological belief often appears between that mother goddess and the goddess of the earth ought not to be left out of sight. Whether the fact of the body of our goddess being shown in all these numerous figurines only down to below the waist offers a clue pointing in the latter direction I do not venture to assert for certain. But it is certainly curious that we meet with a corresponding representation of the Earth goddess emerging from the ground with the upper portion of the body also in Buddhist and Hellenistic iconography.<sup>4</sup>

Period of civilization represented at Meh:—Limited as the extent of the excavation work done at the Meh mound was its results suffice to prove that the civilization of which the remains have come to light there belongs to the same period and presumably also race as the remains traced at the sites of Kulh Sirhadamb of Jhau and Shahdinzai and in the deeper strata of Shah tump. A close relation to the chalcolithic sites of Zhob is also evident. The fact that not a single stone implement was found either at Meh or at Kulh together with the more developed style of the painted pottery seems to suggest

<sup>3</sup> See V Bal. *h. d. a. T.* Pl IX XIV

<sup>4</sup> Cf. above p 16 Pl XXII

<sup>4</sup> Cf. Fowler *La t. du Gandhara* Vol I pp 307 seq

that the occupation of these sites dates later than that of Shahu tump and the Zhob sites. On the other hand the distinct rarity of potsherds showing the characteristic decorative features of the Nal type points to a period preceding the spread of polychrome ware of the latter type.

Burial customs.—The evidence furnished by the burial deposits is also instructive. The practice of placing ashes and remains of bones from completely cremated bodies in cinerary vessels is identical with that observed at the chalcolithic sites of Zhob and Sulzigen dor. On the other hand the custom of leaving remains of partially burned corpses deposited together with personal relics at the place of cremation differs from that practice and may well mark a step towards complete interment such as is found at the later burials on the top of the Shahu tump mound and at the burial ground explored by Mr Hargreaves at Nal.

---

#### SECTION IV—REMAINS EXAMINED IN UPPER MASHKAI GRESHAK AND NAL

On the morning of March 30 I started from Melu up the Mashkai valley. On my first arrival I had already taken occasion to inspect the two dams reported at Jehri village. This itself as stated before lies only 1½ miles above Melu amidst Kirez irrigated fields. One of the dams proved a small mound, only about 16 feet high occupied on its top by the ruined fort of the Jehri Sindars which an earthquake was said to have destroyed some thirty six years ago. The circumvallation of mud bricks measures inside about 40 yards. Of the few painted potsherds I picked up at the foot of the mound one shows polychrome decoration distinctly of the Nal type and thus suffices to prove prehistoric occupation.

Prehistoric mound near Jehri.—The second dam situated about 3 furlongs to the east of the ruined fort by the side of the *Karachi* flood bed looked at first like a small natural hillock so thickly is it covered with rough stones. But remains of very primitive walls built with large unhewn blocks are laid bare where the torrent has cut into the mound at its southern foot and these prove its artificial origin. The mound measures about 120 yards along its foot from east to west and cire 50 yards across. Its maximum height is about 20 feet. Lanes of fallen walls could just be made out among the confused stone heaps on the top but not a single potsherd was to be seen there. Subsequently, however I came upon two fragments of plain and very coarse ware apparently hand made between the foot of the mound and a small outlier to the west. Small stone blades undoubtedly worked turned up too and a short search allowed us to collect over a dozen more all showing signs of use from the slopes of the mound. Together with the chert cores also found there these little stone implements seem to indicate that the spot which is now well away from water was occupied in neolithic times.

Here I may mention that a fine large jar which was brought to me at Melu was said to have been found in a field near Jehri. It is 3½ feet high and 1½

three finely designed handles below its lip. One of these bears a small flat disc as if intended for a drinking cup to be placed there. The vessel is certainly of a date much later than the pottery of Melu.

**Damb of Runjān**—About 3 miles above Jebri cultivation here all Khushkaba stops on both banks of the river bed which further up is entirely dry except after rain floods. On the left bank along which the road led only a few ruined Gabar bands could be seen. But on the large alluvial fan of the Gajeli kaur which descends on the opposite side of the valley dark lines of stone marking ancient embankments showed up over a considerable distance. The damb of *Runjān* which I visited on the western bank of the Mashkai bed after covering about 9 miles from Melu has a length of about 220 yards from north to south with a width less than half that. Its maximum height is about 20 feet. What painted pottery could be seen on its slopes was too scanty to permit of any definite determination of type but some resembled the Melu ware.

**Suneri damb**—No cultivation was met as we rode for  $5\frac{1}{2}$  miles further up the valley along the stony glacis of the hills. Desolate too was the look of the ground at *Suneri* where a dozen of semi-nomadic families carry on precarious cultivation on the chance of flood water being received from the side valley of Mai bibu or the Mashkai bed. No water for humans or flocks can otherwise be found nearer than three miles off at a spring below the Jauri pass towards Greshak. Yet here we found the *Suneri-damb* a conspicuous mound rising at the mouth of the Mai bibu valley. It measures about 230 yards from east to west and some 100 yards across. Its height is about 25 feet. The whitish clay from decayed mud dwellings is exposed over much of the upper portion of the mound, rubble and large unhewn stones cover the slopes elsewhere.

**Types of decorated pottery**—That the site had been occupied for a long period from early down to historical times was clearly shown by the fairly plentiful painted pottery. Most of it is coarse as also the plain ware. By the side of a few pieces with poorly executed patterns of the Nal type the specimens collected (see Sun 15 Pl XXXIII) frequently show motifs with voluted scrolls, rayed discs and half circles—these resemble the decoration prevailing on the painted pottery of Zayuk, Spet damb of Jhau and also Jiwanm. That occupation continued into the early historical period is proved by some ribbed and green glazed pieces also a fragment of good red ware with polished bands. This comparatively late dating is confirmed by finds of a handle and a spout such as seen at Zangan and Jiwanm as well as by relief decorated coarse pottery of a type common at Dabar kut. Yet on the other end of the time scale we find some scrapers of chert with distinct marks of usage as well as cores from which such artifacts were produced. The chief interest of the *Suneri* mound lies in the fact of its being now so far removed from any perennial supply of water. This in the case of so large a settlement as the size of the mound indicates seems clearly to point to a change in climatic conditions since the time of its early occupation.

**Visit to Gwan**—Not having learned of any dams' higher up on Mashkai we turned from *Suneri* eastwards and after crossing the wide Mashkai river bed

regained the motor track by the Jauri spring. Thence the lories carried us through narrow twisting ravines with many ups and downs across the Jain pass into the wide valley of Gwari. Here I visited the same day the damb known as *Gwari kalat* situated about 2 miles SSE from the nearest point on the motor road. All the way we passed abandoned Khushab fields and others recently tilled where the wheat crop had completely withered. No rain had fallen for over half a year and here as well as in the similarly situated tracts of Grashak and Nal the hopeless prospect of a harvest had driven most of the people away to Sind or down towards Lis Bela. At Gwari kalat a small ruined fort crowns the top about 40 yards across of an ancient debris mound c. 25 feet high. The painted pottery found on the slopes comprises the same types as at Sumari damb. Here too scrapers and cores of chert were picked up while decorated glazed potsherds of the same kind as found at the Solan damb of Awaran attested occupation continued down to medieval times.

**Mound of Jawari kalat**—From Gwari a ten miles drive over in open and almost imperceptible watershed quite as desolate in appearance carried us by nightfall well into the broad valley of *Grashak*. There we halted near the hamlet of Jawari and thanks to a fresh Gurch and the increased elevation enjoyed a delightfully cold night. Next morning I visited the mound of *Jawari kalat* close to the little hamlet which with its untilled fields and decayed mud built dwellings strikingly illustrated the plight of this poor ill favoured tract. The mound which a small ruined fort crowns rises to about 20 feet in height and measures at its foot c. 110 yards from east to west and some 70 yards across. The few painted potsherds found here pointed to occupation approximately contemporary with that of Sumari damb.

**Mound of Saka kalat**—A site of greater importance and also greater antiquity is marked by the double humped mound of which the smaller southern knoll bears the ruined fort of *Saka kalat*. It rises over a flat expanse of bare clay about 3 miles to the north of Jawari. The little stronghold measuring inside about 36 by 30 yards is of modern origin having been built by Saka Khan about four or five generations ago. But an inspection of its walls was all the same instructive. They are built with layers of small stones inserted between courses of mud bricks or stamped clay. Assuming construction of the same rough kind in the dwellings of the Mehri site we can easily explain the presence of abundant rubble in the debris which had accumulated from decayed structures at the *mesa* II III of Mehri before it became a dumping ground for broken pottery etc. and a place for depositing remains of cremated bodies.

**Types of painted pottery**—The whole mound has a length of about 280 yards from north to south and at the saddle which divides the northern and longer portion from the southern one is about 170 yards wide. Its maximum height is about 30 feet. Painted pottery is to be found on the slope in fair numbers and its varied types point to occupation at different prehistoric periods. Patterns in black on a dark red slip like Saka 13 (Pl. XXXIII) among which we have the figure of a bull distinctly recall the painted ware of Kulli and Mehri. More numerous are pieces like Saka 4 where hatched motifs or scrolls are shown in

brown over a buff or whitish ground. These motifs are clearly derived from the black on red ware and belong to a later period as is shown also by the coarser execution. That the early occupation of the site goes back to that of the Mehra dam is proved by a fragmentary bull figurine and a small terracotta piece representing the arm of a goddess. I observed no traces of structural remains on the surface but believe all the same that the Sakakalat mound deserves a trial examination. Owing to the absence from Greshak of almost the whole population it would not have been possible at the time to collect adequate labour.

*The Nal tract*—The northern portion of the Greshak tract drains into the flood bed of the Gidar dor which itself is the main feeder of the Nal river eastwards. A drive of 18 miles by a tortuous track through a wildly broken hill chain brought us the same day into the wide trough of Nal from which that river already met by us about Jhau derives its designation. The Nal tract comprises an open stretch of alluvium some six miles across from east to west which the north-eastern feeders of the river have deposited above their junction with the Gidar dor. It is hence one of the main cultivable areas of Jhalawan. At Nal village situated close to the western edge of the area and the seat of the chief Sirdar of the Bizanjan clan a fine spring issues below a rocky spur and together with a single Karuz provides irrigation for a limited patch of ground. But everywhere else cultivation is wholly dependent on rainfall. As this for a succession of years had been very inadequate and since the summer preceding my visit had altogether failed we found most of the arable land untilled and the homesteads in the scattered hamlets with rare exceptions abandoned. Judging from what my stay for two nights at Nal village and a long day's ride extending over the whole length of the tract from north to south allowed me to observe I should have found it difficult to credit it at the time with more than perhaps one-tenth of the population over 2000 which the Census of 1920-1 recorded.

*Previous exploration about Nal*—That Nal must have been a locality of some importance in ancient times is proved by the number of dams to be found at different points. But the largest of these the one known as *Sohr dam* had been the scene of prolonged systematic excavations conducted by Mr H. Hargreaves in May-June 1920 and most of the rest surveyed by the same officer or his assistant K. B. Wasiddin Khan. So I could confine myself to an inspection of the Sohr dam and to a rapid survey of a few minor sites of which no mention is made in Mr Hargreaves' full and very instructive report on his operations at Nal.<sup>1</sup>

*Sohr dam of Nal*—This report makes it unnecessary here to give any general description of the great mound of Sohr dam situated amidst fields close on five miles to the east of Nal village or of the structural remains left at the small but very interesting necropolis which Mr Hargreaves' painstaking exploration has laid bare at the north-western foot of the mound.

Still less can it come within my scope to attempt any analysis of the characteristic style of the painted funerary pottery of which many fine and well preserved specimens were recovered then. A full description of these may be expected in a separate publication under preparation by Mr Hargreaves. Meanwhile the account and illustrations given by Sir John Marshall of the 59 pieces which some amateur digging done here in 1903 had brought to light together with the reproductions of some of Mr Hargreaves finds will suffice for reference."

Painted ware from surface of mound.—But as I had so often occasion in the preceding pages to refer to painted pottery of the Nal type found elsewhere in the course of my surveys it may be useful to note some observations I was able to make on my brief visit to the classic site of its first discovery. In the first place it deserves to be pointed out that as also observed by Mr Hargreaves fragments of painted ware showing the characteristic patterns of the Nal type with curved or polygonal lines executed mostly in dark brown over a light buff or yellowish slip (see for specimens Nal 712 Pl XXXIII) are to be found plentifully over the whole mound. This measures over 330 yards in length. Their close agreement in make and in patterns with the funerary ware from Mr Hargreaves necropolis Area 1 is seen on comparing those specimens with others found lying in the excavated area and illustrated by the specimens Nal 16 (Pl XXXIII). That the fragments of this ware picked up elsewhere on the surface of the mound do but rarely retain clear evidence of polychrome treatment (as in Nal 21) is probably due to the prolonged exposure they have undergone on the surface.

Pottery other than of 'Nal type.—The great abundance of this painted pottery all over the mound is clear proof that it was in extensive domestic use and not confined to funerary purposes and further that it must have been manufactured during a prolonged period. Exactly the same observation applies also to the 'Nal type' pottery found at the Shah damb of Mundara. Fragments of superior body showing simple geometrical motifs on a fine dark red slip, such as Nal 1922 could but very rarely be found low down on the undisturbed eastern and southern slope of the mound. In view of the observations made elsewhere I believe them to belong to the earlier deposits of the site. Pieces like Nal 1819 with coarsely executed patterns in black over terracotta ground or slip may possibly be later than the Nal type pottery. A few pieces of this kind (Nal 17) were however found mixed with fragments of the usual 'Nal type' like Nal 2321 which were extracted from exposed layers of the cutting made by Mr Hargreaves excavation at the southern end of Area 1. From this cutting come also Nal 1314. The former of these fragments is of interest as it shows the well drawn head of a bull, distinctly

<sup>1</sup> For Sir John Marshall's account see 4th vol of *Report of the Archaeological Survey of India* 1904-5, p. 10 Pl XXXIII XXXIV for preliminary illustrations of Mr Hargreaves' finds, see 1 vol of *Report of the Archaeological Survey of India* 1905-6, p. 10 Pl XXXIII.

The Mundara Museum at Quetta contains a few further collections of well preserved funerary ware from the Shah damb. These apparently are part of the plentiful finds made during the extensive excavation there carried out here in 1905 by Officers of the Rawalpindi Pioneer. Other specimens are the result of a more recent excavation.



superior in design to the clumsy representations of humped bulls found on the painted pottery of Kulh and Mehn where the heads have mostly a very queer look suggesting those of a beetle. Finally I may note that the total absence among the potsherds collected on the surface of any glazed or ribbed ware together with the fact of no painted pottery of the Sumer type having come to my notice there strongly supports the assumption of the mound having remained unoccupied since prehistoric times. To the close agreement in the size of the mud bricks cleared by Mr Hargreaves at the Sohr dam<sup>3</sup> and those found at Sialh dam<sup>4</sup> Nundara and on the top of the Shah tump mound I have had already occasion to refer<sup>1</sup>

Shakar Khan damb —A few smaller dambs which were visited by me about Nal do not appear to have been surveyed before. They lie almost all along the western side of the valley. The one shown to me under the name of *Shakar Khan damb* proved a natural hillock situated about a mile to the north east of Nal village. It is about 90 yards long and less across. Along its top rising about 18 feet above the level of the adjacent fields a massive wall foundation 20 yards long could be traced. Former occupation is marked by scanty fragments of coarse pottery as well as by flakes and cores of chert. To the north lie a few Khuskaba fields with a modern earth dam intended to catch for their benefit the drainage from a stretch of low ridges to the west. Parallel to this dam runs a ruined Gabar band which starts from the north eastern foot of the hillock and obviously served the same purpose. Wall foundations built with large boulders can be traced also on a second somewhat higher natural hillock about two furlongs off to the east.

Shari damb —Proceeding 2<sup>1</sup> miles further to the north east along the foot of low outlying ridges the large *Shari damb* was reached. It rises between the wide flood bed of the Ushtar laur on the west and the fields of Shari hamlet eastwards. Its central portion which probably rests on a natural knoll shows a height of about 37 feet. Below this there lie both to the south and north artificial terraces of which the outer edges are built up with walls of large undressed stones to a height of about 15 feet above the level of the fields. The width of the whole mound along the northern terrace is 90 yards and its length by the side of the flood bed about 105 yards. Most of the painted pottery found here shows geometrical patterns of the same type as at Sumeri and Spët-damb. Jhau executed in black or dark purple over a red slip. Voluted scrolls and rayed circlelets as seen in Shari 1 2 Pl XXXIII are prevailing motifs. It was of special interest to note a small 'Gabar band' projecting from the north eastern corner of the mound along the edge of the nearest fields. It is built in exactly the same way as the supporting walls of the terraces of the mound and probably dates from the same late prehistoric period.

When subsequently proceeding from Sohr damb for a mile to the south west I found painted potsherds of the same type also on the small mound of

<sup>3</sup> See loc. cit. pp 68-9  
 (cf. above p 147)

*Lehr* already described by Mr Hargreaves<sup>5</sup> At the small *Hanaidamb* too which I was shown some 2 miles further on in the same direction painted fragments of the Sunem type could be picked up This mound only 10 feet high and some 30 yards across is adjoined by a few huts while most of the once cultivated ground around is now overrun by tamarisk scrub

Plateau of *Hala damb*—A ride of 5 miles continued to the south west over ground of similarly desolate look brought us to the gravel covered alluvial fan of the *Gidar dor* Close to where its wide flood bed is joined by the drainage of the main *Nal* valley there rises on its bank a low plateau known as *Hala damb* This extends for cire 180 yards from north to south with an average width of about 150 yards Its height above the gravel penephim is about 25 feet The whole area is of very unequal surface and is covered with rubble of small stones and in places with rough enclosures formed of large boulders What scanty pottery could be found on the surface is all of very coarse make the few painted pieces showing only plain black bands or simple zigzags The period of occupation could thus not be determined

Hillock outside *Nal* village—On the morning of April 2nd before starting on the journey to *Khodzár* I inspected a small eminence which being about two furlongs from my camping place outside the north eastern edge of *Nal* village had attracted my attention It is obviously a natural hillock half buried by detritus washed down from the hillside to the west That it was once occupied was soon proved by plentiful potsherds found on and around it Most of these were coarse plain ware with a whitish surface reminding me at once of the pottery which we had found at the burial cairns of *Twanm Nasratabad*, etc and also of *Moghulghundai* in *Zhib* The conclusion as to this ground having been occupied in historical times was fully confirmed by fragments of glazed ware some unmistakably mediæval which were also picked up Near the little hillock which measures about 150 yards in length low circular stone heaps only 3-4 feet in diameter manifestly marked burial deposits The two opened contained under a thin layer of earth small fragments of calcined bones and potsherds of the same coarse make with whitish surface just referred to

Considering the importance which must at all times have attached to the fine spring now irrigating the gardens and orchards of the *Bizanzai Sirdár* and his relatives it may safely be assumed that the site of *Nal* village has been occupied since early times But owing to extensive modern refuse mounds around its crowded houses and to the close cultivation no definite evidence could be traced without excavation I may however mention that from the bare ground towards the spring there were brought to me the fragment of a bull figurine and a piece of mat marked pottery both undoubtedly prehistoric

'*Gabar bands*' near *Laghor zard*—The small site of *Laghor ard* which the motor road to *Khodzár* passes about 5½ miles from *Nal* village has already been described by Mr Hargreaves<sup>6</sup> From the foot of the small rock hillock

<sup>5</sup> See *Annual Report A S I 1906*, 61

<sup>6</sup> See loc cit pp. 60-61

which it occupies two lines of 'Gabar bands' strike off at a distance of 310 yards from each other. From the first which the road cuts through three transverse 'bands' diverge at right angles on different levels, forming three successive terraces. The purpose of these stone-faced embankments was here obviously to facilitate the uniform retention of rain water on the terraced plots and the deposition of fertile alluvium on the otherwise rocky soil. No other remains of this kind were passed on the drive over some 32 miles which carried me to Khozdar first through a much broken hill range and then down the open valley drained by the Kahnak river.

## CHAPTER X—ALONG THE CENTRAL VALLEY OF JHALAWÂN AND SARAWÂN

### SECTION 1.—REMAINS OF KHOZDAR AND WADE

The narrow tract of Khozdar on the upper course of the Kulachi river owes such importance as its repeated mention in early Arab historical and geographical records implies far more to its central position than to its size or local resources.<sup>1</sup> In Khozdar the main routes leading from Sind to Mîkran and southern Persia are crossed by the most direct line of communication connecting the south eastern portion of Afghanistan Pishin and Kalat with the sea coast. Khozdar besides enjoys the great advantage of ample irrigation from the Kulachi river. This permits of rice cultivation and at the same time together with the suitable elevation of about 4 000 feet favours fruit growing.

But owing to the confined nature of the valley the area over which the available water can be utilized for cultivation is very limited when compared with the tracts to the west where arable ground is extensive but its produce wholly dependent on a precarious rainfall. This also explains why Khozdar notwithstanding these advantages maintains only a population of a little over a thousand. It is however easy to understand that the existence of this pleasant if modest oasis conveniently situated just at an important cross road, must always have attracted special notice on the part of those whom trade travel or military operations caused to cross the surrounding barren regions.

Site of Gumbat.—With these observations agrees the absence of any large mounds such as are to be found in the far less favoured tracts of Kolwa Jhau or Nil. The site known as the damh of *Gumbat* was the first to which my inspection of reported 'dams' led me on April 3rd. It proved a low hillock situated between the road and the river bed about  $4\frac{1}{2}$  miles above the modern fort of Khozdar. An area measuring about 200 yards from north to south and c. 150 yards across is thickly strewn here with rubble from decayed dwellings. That

it was a place occupied during the Muhammadan period is proved by plentiful glazed potsherds including pieces with polychrome decoration manifestly mediæval. A few fragments of black on red ware seem however to indicate that the locality was inhabited already before probably in late prehistoric times. About 300 yards from the southern end of this debris area stands the ruin of a domed Muhammadan tomb this accounts for the name *Gumbat* applied to the site. The structure forms a square of 28 feet outside and shows four flat pilasters on each side. It is built with hard bricks measuring  $10 \times 7 \times 2$  and carries its dome inside on four arched niches not squinches. This ruin together with the debris of burnt bricks from other structures near by leaves little doubt about this 'Gumbat' being the old building north of Khozdar to which Masson's itinerary refers as likely to have been a mosque.

**Remains at Kand and Kahnak.**—A short distance lower down large springs issue in the river bed which higher up is dry their water is taken off into four canals and serves to irrigate the riverine belt down to the village of Sorgaz. The hamlet of *Kand* is the first on the right bank to receive irrigation. Just above it the extremity of a low ridge bears near the road a Muhammadan graveyard and at its eastern end the decayed walls of a small ruined fort occupied down to the middle of the last century. Judging from the plentiful glazed pottery some with coloured designs which strewn the ground the site appears to have been inhabited in mediæval times. It is obviously the considerable tappa or mound which Masson, in a passage quoted by Mr Hargreaves briefly describes<sup>1</sup>

Turning up the road leading to Nil I visited also the bold rocky ridge situated about  $1\frac{1}{2}$  miles from Khozdar fort and known as *Kahnak* from the river bed which passes its foot. The scanty potsherds found on its top are with the exception of one mediæval glazed piece of coarse ware and of uncertain age. They suggest that the precipitous isolated ridge may have served at times as a safe place of refuge.

**Mound of Chinn.**—Probably the oldest site of Khozdar is marked by the dam known as *Chinn*. It lies on the left bank of the river bed, about a mile to the east of the Khozdar fort close above the pleasant little village of Kard. The mound about 30 feet high stretches for some 200 yards from north to south with a maximum width of about 150 yards. Its top shows small ridges and hollows covered with rough stones evidently the remains of dwellings. Most of the potsherds mixed with this debris are of coarse plain ware. But on the slopes there could be picked up also small fragments of painted pottery showing either the Nil type of decoration as seen in Chinn 1 (Pl XXXIII) or else patterns in black on a dark red slip (Chinn 2) such as are found on the late prehistoric painted pottery from Maltron and Mashlari sites. The curious little fragment Chinn 3 which shows two fox-like animals face to face may judging from the colouring and make belong to the period of the Nil pottery.

<sup>1</sup> See Masson *Journey in Baluchistan* p. 24.

<sup>2</sup> See Nil on p. 131 i p. 43 sq. *Ann. of Report* C. S. I. 1926 p. 24.

Site of *Miri but*—The best known of the 'dams' of Khozdar is the site of *Miri but* on the right bank of the river and about 2 miles to the south east of the Khozdar fort. There a rocky outlier of the hill chain to the south of the Kahnak bed juts out towards the latter's junction with the river. It ends in three rocky hillocks, the easternmost and lowest of these rises abruptly above the reed beds lining here the banks of the river. Some bold rock pinnacles rise on the edge of this hillock, and a little plateau below them bears much decayed remains of a Muhammadan domed tomb built with mud bricks and also of some structure of burnt bricks. On another detached little hillock to the north west confused heaps of burnt bricks probably mark the position of more Muhammadan tombs. Both these kopjes appear to have enjoyed some sanctity in early Muhammadan times and hence been chosen as burial grounds.

Polychrome mediæval pottery—Glazed potsherds, both in plain turquoise blue and polychrome are scattered in plenty over the hillocks. Pl XXXIII reproduces typical specimens (M but 17) of this fine decorated ware which resembles that of the Sohren dam of Awaran and probably is mediæval. In M but 8 a light blue glaze is applied over a relief pattern on the outside. Browns, greens and yellows are the prevailing colours applied for the decoration of the inside of cups and bowls. It is interesting to find this glazed ware associated with painted pottery which shows coarsely drawn geometrical patterns (M but 9) executed in dark red or purple over buff ground. This helps approximately to date this painted ware which has been met with also at certain late sites of Loralai and Pishin. A neatly incised arabesque design is seen in M but 10. Potsherds of the kinds just described are found though more scantily over the slopes of the hillocks and the rocky plateau below them for about 500 yards to the NW of the domed tomb, but no painted pottery of the prehistoric types. That the burnt bricks, if not some of the glazed pottery too, were produced on the spot is shown by the remains of a brick kiln found about 400 yards from the 'Gumbaz' below the edge of the plateau and near a rice field.

Remains above Nullah to West—The rocky plateau bearing the kopjes drops steeply at its western end towards a narrow channel which separates it from the stony glacis of the hill chain beyond. This Nullah contains springs fed by subsoil drainage from the Kahnak bed. In its flood water descending this bed is diverted from the irrigated land along the Khozdar river and conducted towards Urban and other hamlets further down without causing damage. The channel looked to me in places as if artificially cut. Remains of rubble built dwellings can be traced along the scarp of the plateau where it is edged by this Nullah. About the middle of this line is found what looks like the former approach to a place for ablutions or for fetching water. The walls are carefully built with burnt bricks and stand to a height of 2 feet. The two which jut out at right angles to the bank of the channel here 10-12 feet deep are each provided with a pro-

\* This kiln was already noted and by Mr R. A. Gajote of the L.L. topographical Survey who accompanied Mr Hughes in 1903. cf *Jhalawan Co. Hist.* p. 60.

jecting step 2 inches wide. These steps are found only a few inches above what seems the bottom of the channel. The wall complete on the side towards the plateau, is 8 feet long and reached by descending the scarp. The other two walls at right angles to it are broken at about 6 feet from the corners. It is of course possible that these walls belong to some earlier structure built some 8 feet below the level of the rest, but considering their brick material which is the same as found among the ruined tombs towards the other end of the plateau this does not seem likely.

Here I may conveniently mention that on the morning of my departure from Khozdar April 8th there were brought to me a number of glazed potsherds most of them polychrome said to come from *Genu damb* a locality down the left bank of the river. They all resemble the decorated ware of Min but in their patterns, as seen from the specimens Gen 12 Pl XXVIII. The arrangements already made for my visit to Bighwana did not allow me to examine the reported find spot.

Visit to Zidi.—On the morning of April 4th I proceeded down the left bank of the river to where the valley eastwards widens into a large amphitheatre of gently sloping ground. The whole area is known as *Zidi*. Owing to good drainage from the surrounding high hills and to irrigation brought by a canal from the river it supports a comparatively large number of hamlets. Min, the chief village stands in the middle of marshy meadows where three small hillocks, apparently all natural rise close together like islands. Two of them are occupied by dwellings while the third which had been reported to me as a *damb* bears the decayed walls of others supposed to have been abandoned some four generations ago. The hillock rises to about 40 feet and has a diameter of over 120 yards at its foot. No ancient pottery could be traced on its slopes. About a mile to the south there is found a small mound known as *Boluka damb* not far from the Ziarat of Kamal-shah a well known pilgrimage place. The mound rises to about 15 feet above the marshy meadows and rice fields which surround it and extends for circ 150 yards with a width of about 60 yards. It bears the remains probably of no great age of dwellings built with rubble and mud. Among the plentiful plain potsherds of coarse make only one or two small painted pieces could be found these afforded no definite indication as to the period of earlier occupation.

Move to Wadh.—Though Zidi is fully 14 miles from Khozdar fort tracks practicable for motors allowed me to return to Khozdar in time to do from there on the same day the journey of some 45 miles to the centre of the Wadh tract. Wadh lies on a wide plain to the south west where the main feeder of the Porah river flowing down to Las Bela gathers its drainage. The route which passes through it from the side of Khozdar must since early times have been a main line of communication between Kalit Las Bela and the sea. Sir Masson too followed it twice. The route now made practicable for motor as a 'fair weather road' as far as Drakalo passes first up the tortuous valley of the Saman an affluent of the Khozdar river and then enters the open basin at its head known as Wadh.

Enclosures near Wahir—There at a distance of 22 miles from Khozdar I noticed by the side of the road two cairns of the type first seen near Gabar bands on the way to Malar<sup>4</sup> and on the opposite side of the road three circular enclosures. All around stretches for miles a bare waste of stone and gravel without habitations of any kind. The circular enclosures touching each other stretch in a straight line from SE to NW and show each an average diameter of about 14 feet. They are formed by double walls of large rough stones set in two or three courses and about 4 feet apart the space between them being filled with gravel. The walls stand nowhere to a greater height than three feet or so and there is no trace of their ever having carried any superstructure. Each enclosure has its entrance from the south east there being a kind of elliptical passage about 2 yards wide between the first from that side and the second. These enclosures distinctly differ from the roughly laid out circles of single stones which are often seen in these hills and in accordance with a Brihu custom mark places where marriage processions have halted to perform a dance. There is no local tradition about the spot and nothing was observed to afford a clue as to the age of these enclosures. Their arrangement curiously recalled to me that seen at certain megalithic sanctuaries of Malta but this similarity is probably quite illusory. There is nothing megalithic about the blocks of stone, though they are large enough for their transport from the foot of the hills nowhere nearer than a mile or two to have implied trouble. Of the two cairns on the east side of the road both about 10 feet in diameter and 6 feet high one was cleared by us to the ground level. It proved to be faced outside with large undressed stones set without mortar or clay and to be filled inside with rubble and gravel.

Remains on ridge C of Wahir spring—Here I may conveniently record also what I observed at an undoubtedly early site found about three miles further to the west. I could not visit it until April 7th on my return journey. There at a point circ one mile to the east of the spring and main hamlet of Wahir a rocky ridge juts out from the stony glacis of the hills which encircle the plateau on the north. It stretches at its foot for about 380 yards from east to west and measures there 300 yards across. It rises about 35 feet above the level of the glacis at its northern foot. The top of the ridge is fairly level over an area of about 40 by 30 yards. This as well as the slopes which are broken in places by small terraces are covered with stone debris from decayed dwellings and with fragments of decomposed rock. Both on the top and on the lower terraces remains of stone built walls crop out here and there. Among the plentiful potsherds which mingle with the debris painted fragments of several types can clearly be distinguished. By the side of numerous small fragments unmistakably of the Nal type (see Wah 1 Pl XXXIII) there are found less frequent pieces of black on red ware like Wah 3 (see Pl XXXIII). These show equally clearly patterns familiar from Kulh and Melu. Others like Wah 2 seem to belong to pottery of the late prehistoric type. That the ridge was occupied from an early period is suggested by the plentiful chert cores and flakes. One of the

<sup>4</sup> See above p. 114.

latter looks as if used as a primitive arrowhead. No glazed pottery or other objects suggesting occupation during historical times were found. No water is to be found now nearer to the ridge than the above mentioned spring. But permanent drainage from the valley to the NE may have passed once in the bed which skirts the eastern foot of the ridge.

Tract of Wadh—From Wulur there is reached over a low watershed the tract known as *Wadh* and held by the once powerful tribe of the Mengals. It comprises the basin, some 8 miles across where widest in which the head of the Porah river gathers its drainage. Except after heavy rain the torrent beds which feed it are dry and all the cultivation which is limited in extent is 'Khushkaba'. The vagaries of the flood beds descending into the basin are apt to interfere with *Karēzes* for the construction of which the configuration of the ground would otherwise offer facilities. Thus the wide stretch of fertile alluvial soil which was once cultivated around what was the fortified seat of Shaker Khan the leader of the last Mengal rebellion, has become a scrub covered waste for the *Karēz* named after Sirdār Nūr-uddīn Mengal has fallen in owing to a heavy flood some seven years ago.

Site of Panju—It was across this desolate plain that my visit on April 5th to the 'dams' of Wadh first took me. It was carried out under the guidance of Rissaldar Khan Muhammad Mengal, the capable commander of the local Levies and familiar with all localities of the tract. Leaving the rest house near the Levy post and riding for about 3½ miles to the north west we reached the area known as *Panju damb*. It proved the small counterpart of a Turkestani 'Tatı' being overrun by little dunes of drift sand and thickly strewn with potsherds wherever the slightly eroded ground is exposed between them. The area marked by this debris measures about 550 yards from north to south and about 300 yards across. Corrosion by wind driven sand has entirely effaced the patterns on most of the pieces once painted. But on those all small which retain them designs of the late prehistoric type executed in black and purple over red or buff ground are recognizable. The site was said to be searched after storms for beads and other small antiques, but only a small glass bead could be picked up by us.

Ridge of Abdul-but—The Panju damb lies not far from the bed of the Tul river the main feeder of the headwaters of the Porah and proceeding up this bed to the north east quite a series of other small sites was reached. The first, *Abdul but* situated at a distance of about 1½ miles is a rocky ridge rising to a height of about 20 feet. There are scanty traces of rough stone walls together with rare pieces of pottery to be seen along the top which stretches for c. 170 yards from NE to SW. Among the pottery there were found a few painted fragments of the late prehistoric type as well as some of glazed ware. Chert and flint cores and flakes were picked up in abundance. Most of the flakes show clear evidence of prolonged use, and the early occupation of the site is thus proved. Of the several small stone circles found on the top one was opened. It contained small fragments of burned bones obviously a burial deposit of later times.



**Site of Kāshim-damb**—A site of some interest is the *Kāshim-damb*, situated about three quarters of a mile to the north on the right bank of the Tuk. There a natural ridge rises about 20 feet above the flood bed and for a distance of some 190 yards from its southern end bears what looked like foundation walls of rough stone work. Some apparently belonged to structures of some size. At the northern end of the debris strewn portion of the ridge the remains of a wall, 10 feet thick, stretch across the top. It is built with large undressed stones and seems to have served for defence. Among the plentiful potsherds a number show painted patterns of the Nāl type. But far more frequent are fragments of glazed ware (Kash 1, Pl XXXIII), mostly with polychrome patterns of mediæval look. It deserves to be noted that no painted pieces with patterns in black on red or buff of the late prehistoric type could be found here.

**Remains above Sōrak**—Proceeding about  $1\frac{1}{4}$  mile to the ENE and crossing and recrossing the Tuk bed we reached some 'Khushkaba' fields belonging to the hamlet of Sōrak by the side of an abandoned Karēz. Above them rises a very steep ridge which at the southern end of its narrow crest, about 120 feet high, bears ruined stone walls of the roughest kind for a distance of some 50 yards. On the slope to the south a small shoulder is covered with similar remains. What painted potsherds could be found all show black geometrical patterns of 'late prehistoric type' (see Sōrak 1, 2, Pl XXXIII) on red or buff ground. Similar painted ware was to be seen also among the debris of some rubble built dwellings near the fields at the southern foot of the ridge. Neither pottery of the Nāl type nor glazed pieces were found here, but a chert core from which 'blades' had evidently been chipped.

**Other remains of Wadh**—About  $1\frac{1}{4}$  mile to the south west of Sōrak and not far from the left bank of the Tuk bed, there rises a precipitous kopje of bare rock to a height of about 80 feet above the alluvial ground, here showing some cultivation. Its top, about 30 yards in diameter, bears potsherds of glazed and decorated ware, manifestly mediæval, with rare fragments of 'late prehistoric' ware (Jog 1, Pl XXXIII). Riding through a gap in the low hill chain to the south I next visited a small mound situated about half a mile to the ENE of the Wadh rest house. The ground around, now a desolate waste, is crossed by the abandoned Karēz of Sirdar Nuruddin. An area of about 200 by 120 yards shows here potsherds of glazed as well as of coarse black on red ware amidst traces of stone wall foundations. Finally when inspecting a low rocky ridge, half a mile SSE of the Levy post, known as *Haji Abdullah damb* I convinced myself that the only remains to be found on it are the debris of burned bricks from a completely wrecked Muhammadan tomb.

**Route through Riku**—On April 6th my survey was extended from Wadh still under Russaldar Khan Muhammad's guidance, to the Drakalo tract south westwards. This is the last area with some cultivation before reaching the border of Lās Bēla. As far as the hamlet of Drakalo, some 18 miles from Wadh, it was possible to use the motor track which ends there. Where the Porah and the route by its side pass between small rock islands, outliers of the hill range which divides Wadh from a small subsidiary basin known as Riku, I

visited the rocky hill known as *Kar m dad-gathi*. It rises very abruptly above rice fields at its foot irrigated from the Porah. Its top at a height of about 250 feet bears remains of decayed stone walls over an area of about 40 yards in diameter as well as debris of a completely destroyed Muhammadan Gumbaz' built with burned bricks measuring  $9\frac{1}{2}'' \times 6'' \times 2''$ . The scanty pottery found all looked late. The very steep hill had evidently served only as a temporary refuge. A small rocky knoll known as *Kocla b t* about half a mile to the south was also inspected. It is about 30 feet high and scarcely more than 60 yards in diameter. Former occupation is marked only by coarse plain pottery of uncertain character. Another small rocky eminence away to the south east at the foot of the hills through which the Porah has cut its way was pointed out to me under the name of *Hassan damb*. It lay too far off the route and could be clearly recognized through the bushy as a natural formation hence I left it unvisited.

The Drakalo basin.—On the low divide towards the Drakalo basin we passed numerous large rings laid out with stones on the occasion of Brahma marriage processions and known as *chap jagas*. A small cairn close to them about 3 feet high and 7 feet across, proved on examination to contain only stones and earth. My Brahma companions were obviously right in taking it for a *cladak* i.e. a cairn set up according to their custom in commemoration of a person who dies without issue. A drive of seven miles hence across the Drakalo basin which shows very little cultivation but plentiful jungle brought us to its principal hamlet. A small rocky ridge jutting out from the hill above it bears on its narrow top and on its western slope remains of massive walls which look ancient. They are built with large undressed blocks of calcareous sandstone set roughly in courses and survive to a height of 23 feet. The top of the ridge close on 200 feet in height measures about 60 by 18 yards. Among the scanty painted pottery found here some show patterns black on red of late prehistoric type such as found at Suner and Spet-damb. Jhau while two are distinctly of the Nal type.

Hillock of Aidu damb.—About 1½ miles to the south of Drakalo hamlet and near to where the small side valley of Bel r debouches there rises a small conical hillock to a height of about 120 feet. It is known as *Aidu damb* and on its top one 20 yards across is occupied by modern Sangars. On its slopes walls built with large undressed blocks of stone brought from the hills de opposite, support terraces which seem to have been occupied by dwelling. On a terrace to the east the wall foundations of structures of some size could be traced. Among the painted pottery found here the majority show patterns of the 'late prehistoric' type as above noted but a few black on dark red fragments of superior make as well as a fragment of perforated plain ware may well be of earlier origin.

Mounds up Bel r valley.—On proceeding up the Bel r valley clothed with plentiful jungle I was shown first the *Bug Mulan a l-damb* about 2 miles in a direct line to the SSE of Drakalo hamlet. It is a small mound entirely of artificial origin with rubble covering its slope. Its top measures about 20

yards in diameter and stands to a height of circ 12 feet. The painted pot sherds all show black on red patterns of the Sunen and Spet damb type voluted scrolls prevailing. Specimens of the same late prehistoric ware were found also at two nameless mounds visited further to the south west in the Belar valley. The first some 300 yards from the one last mentioned is only 8.9 feet high and measures about 150 yards in diameter at its foot. Here were to be seen also some glazed fragments with polychrome decoration. The second mound which is some 500 yards further away and close to the road rises to about 25 feet and measures at its foot circ 140 by 90 yards. The painted pottery found here shows the same slight variations of late prehistoric ware as at Aidu damb: a specimen with a voluted scroll Belar B 1 is seen in PL XXXIII.

The same day I returned to Wadh and on the following day was back at Khozdar in time for Kahmullah Khan the helpful Deputy Wazir of Southern Jhalawân to make all needful arrangements ahead for my survey of sites on the way to Sorab.

#### SECTION II.—BAGHWANA MOUNDS AND THE GABAR-BANDS OF LAKORIAN

On the morning of April 8th I left Khozdar for the large valley of Baghwana due north. Proceeding up the Khozdar river I was able to inspect an Arabic rock inscription found close to the road about 9 miles from Khozdar fort. It proved to contain the Kalima the Muhammadan confession of faith in Kufic characters and is obviously identical with the one noted in the Gazetteer as having been ascribed by Dr (now Sir) Denison Ross to the 4th or 5th century of the Hijra.

Valley of Baghwana.—About a mile beyond an easy defile gives access to the open valley trough of Baghwana. This stretches mainly from east to west with a length of about 12 miles and a maximum width of over 6 miles. Extensive areas of Khushkaba cultivation account for the considerable number of hamlets scattered over the valley. But owing to successive years of insufficient rainfall most of the embanked fields were untilled and much of the arable ground appeared to have been in that condition for a long time.

All the same the tract of Baghwana as a whole bore a far less desolate look than Nal and Greshak. This may be accounted for partly by the fact that an extensive depression in the centre of the valley known as *Kar* is in years of fair rainfall completely under water and in others retains an adequate amount of subsoil moisture to permit of assured crops being raised all around it. At intervals the depression receives so much damage from the hills surrounding the valley that the water there gathered finds its way into the large flood bed which passes the south western portion of the valley before descending towards

<sup>1</sup> See *Notes on Gazetteer* p. 59

**Khodzdar** This intermittent overflow from the Kar prevents the depression from ever becoming a salt marsh and its area hence unproductive like the Kaps of Makran. The favourable conditions thus secured here present a parallel on a small scale to those which keep the Hamun marshes of Sistan from becoming salt and allow of permanent cultivation being maintained along their shores.

**Mound of Inayat Shah damb**—A considerable number of mounds found to the south and east of the Kar bear evidence to these portions of Baghwana having supported a fairly close settled population in later prehistoric times. The intelligent local guidance provided by Sardar Muhammad Khan of Bajoi, the chief Rind landholder of the tract enabled me to visit them all in the course of a long day's ride. After leaving my camp at the hamlet of Londo near the southern end of the valley I first visited a mound known as *Inayat Shah damb*. It is situated about 1½ miles to the north east of Londo and within half a mile of the hamlet of Nulam. It takes its name from a holy man supposed to have been buried at its southern end. Local tradition believes that Naushirwan, a Jadgal chief from the side of Las Bela, resided on the mound before the conquest of the valley by the Rind tribe. The mound rises by the right bank of the flood bed which enters Baghwana from the north west and carries its drainage towards Khodzdar. It is composed entirely of soft clay from decayed mud brick structures such as now prevail in the tract and rises only to 12 feet or so in height. It measures about 120 by 80 yards. The scarce painted potsherds to be found on the surface all show patterns common to the late prehistoric ware of Sumeri and Spitdamb. Than executed on red or buff ground.

**Mound near Bit**—Another and much more conspicuous mound about a mile further in the same direction is that known by the names of *Sio lamb* or *Bit damb*, the latter designation being taken from the hamlet to the LSE of which it stands. It is of conical shape and rises steeply to a height of 30 feet. Its diameter is about 50 yards at the foot and 18 yards on the top. It is entirely composed of soft earth. The painted pottery here too shows close resemblance to that of Sumeri and Spitdamb. On Bit 1 (Pl XXXIII) appears the hind part of an animal. About a mile to the NE of this I was shown a small damb close to the dwellings of Nativan, a hamlet at the foot of the hills. It stands to a height of only 5 or 6 feet with a diameter of some 20 yards. What little of pottery could be found was all plain.

**Kissu damb**—Riding for about 4 miles to the NW, namely by the side of fields which skirt the Kar depression, we reached the village of Bajoi with Sardar Muhammad Khan's seat and half a mile to the east of it the *Kissu damb*. This stands on rising ground and has a height of about 20 feet and a diameter of circ. 60 yards at its foot. Here too the fairly plentiful pottery all painted showed patterns of the late prehistoric type previously referred to. The fact that the volutes of the scrolls so common in this type at Sumeri etc. appear here and at other mounds of Baghwana reduced to mere clumsy hooks with rounded ends (Kissu 1 Pl XXXIII) seems to point to a later and more careless treatment of this motif.

**Tomb of Mai Masura**—When passing half a mile beyond an extensive Muhammedan graveyard known as *Mai Masura* I was pleasantly surprised to come upon the fine sepulchral monument (Fig 20) of the holy sister in faith who has given her name to the place. The beautifully carved relief slabs of sandstone facing the Maqbara below and the similarly decorated miniature tomb stone which surmounts the whole were the first specimens of sculptural art I had seen since that domed tomb at Gwadar. The Indian decorative motifs of the open lotus, Vajra shaped trefoil, Amalaka, etc. combined with the arabesque tracery show close similarity to those seen at that monument of the late 15th century. Local tradition as communicated by Sirdar Muhammad Khan asserts that the relief panels and the tombstone on the top were carried from Kandahar through the air by a miraculous agency when the holy lady mendicant died in Baghwana, also that the tomb was found at this spot when his Rind ancestors first conquered their lands in Baghwana fourteen generations ago.

**Mounds of Landau and Sangas**—About  $1\frac{1}{4}$  mile to the north east rises the *Landau damb* close to patches of cultivation scattered amidst flood channels. Its height is about 20 feet and the dimensions at its foot about 100 by 80 yards. The top of the mound has been dug into for the rough stone material used in early structures. The painted potsherds on the surface all show patterns of the previously indicated type mostly in coarse execution. From here going half a mile to the north west across a wide flood bed we reached the small *Sangas damb*. It is called after a hamlet situated near a spring at some distance further up the foot of the hill range northward. The mound only about 12 feet high measures about 70 or 80 yards across at its foot. The few painted potsherds were too small to show very definite patterns but seemed all of the 'late prehistoric type'.

**Bari damb**—From here we turned to the west and after passing for about 2 miles above the northern edge of the area cultivated in favourable years arrived at the *Radhanu-damb*. This too is of small size and about 20 feet high. As the top and slopes are mostly occupied by dwellings only a single painted pottery fragment was found this also of the 'late prehistoric type'. A site more important probably than any of the rest is marked by the *Bari damb* situated about a mile to SSE and about the same distance from the main village of Bajoi further south. Its extent is cire 180 yards from east to west and its width where greatest probably not much short of this. At its western end it rises to some 35 feet above the bottom of a flood bed which has cut through its northern slope. This cutting has exposed layers of decayed mud brick work or *pisc* mixed with ashes, animal bones and other refuse. The lower eastern portion of the mound is occupied by dwellings. On the higher western end painted potsherds of the Suneri and Spet damb type (see Bari 1 Pl XXXIII) were numerous, so were also others of which the simple geometrical patterns coarsely executed in purple as well as black recalled the late painted ware found at certain mounds of Loralai and Pishin. Occupation may have continued here longer than elsewhere at the mounds of Baghwana. A well carved stone wheel measuring 11.2" in diameter and provided with a groove along its

edge was shown to me as having been exposed during a recent flood which passed down the cutting on the north slope. A large jar for water also said to have come to light there could not be seen by me as it was locked up in one of the dwellings left unoccupied like the rest by the owners who had migrated as usual to Sind for the cold weather.

Remains above Londo—Finally I examined in the evening the remains on the steep rocky ridge which forms the last offshoot of a hill spur separating the Baghwana valley at its south western extremity from an inlet westwards. The ridge overlooks on the east the hamlet of Londo where our camps stood and is known as *Londo-damb*. Its crest at a height of 68 feet above the alluvial ground on which the hamlet stands, is for a length of circ. 68 yards covered with the debris of rubble built walls. The width of this once occupied ground is about 10 yards. Remains of walls more solidly built are traceable on the slopes lower down to the west and south. Painted pottery lies in plenty both on the top and slopes. Most of it shows patterns of the late prehistoric type in black over red or buff ground. But some of the fragments like Londo 12 (Pl XXXIII) carefully painted in black over a dark red slip show designs which look to me older. With this indication of an early occupation agrees the find of a fragment from a painted bull figurine picked up at the foot of the ridge. The steep rocky ridge must have offered itself from early times as a place easy of defence.

Gabar bands above Mugali—A journey of 48 miles carried me on April 9th through the hills northward from Baghwana up to Sorab. It proved very instructive on account of the Gabar bands crossed by the old route now used as a motor track. Most of them are found on ground which has for ages passed out of cultivation. The first was encountered after leaving behind the side valley of Tutal and entering a defile above the scattered 'Ah shiba' fields of Mugali (Fig 61). The band faced with large blocks of stone stretches here across the bottom of the defile and still stands to a height of 5 to 6 feet on the outer face. In spite of massive construction it has been broken through in several places. These breeches have in recent times been partially filled by a low earthen dam and this is carried from the original eastern end of the Gabar band for about 40 yards farther up to the foot of the rocky hillock which the road skirts. Thus adequate flooding is secured for a large field above. This extension indicates that the level of the ground immediately above the Gabar band has been considerably raised by alluvial deposit since the ancient wall was built. The original purpose of the latter as shown by the configuration of the ground was to form a reservoir from which fields no longer in existence could be irrigated lower down. Such storage of water is no longer practicable as the ground behind is filled up almost to the level of the band and the weak earthen bank in the middle is bound to be swept away each time any rush of water descends the flood bed.

Gabar bands north of Lakorian pass—At a point about 3 miles to the north of the Lakorian pass of the map and close on 25 miles from Londo the road ascends a wide stony plateau between low but steep hills. Here quite a

succession of massive 'Gabar bands' is passed. They run across the plateau from the foot of the hillside on the east and evidently were intended to control and distribute the drainage over the slope instead of its being gathered into ravines and thus lost to cultivation. No trace of the latter is now to be found for miles around. Such fertile alluvium as these bands might have helped to spread over the slope has disappeared long ago. Among the rough stone blocks found in their walls there are some up to the size of  $2\ 8 \times 2\ 6 \times 2\ 2$ " and more.

An ancient barrage—Still more interesting is a large Gabar band, an unmistakably ancient barrage which is met four miles further on and about half a mile to the south of the watershed between the valleys of Lakorian and Anura. There a remarkably massive and for the most part well preserved dam stretches right across the bottom of a narrow valley between the ends of two rocky spurs striking from WSW to ENE. It was undoubtedly built to form a reservoir for purposes of irrigation and planned with distinct engineering skill. The total length of the dam is 348 yards as seen in the sketch plan, Pl. 13. Near its eastern extremity (Fig. 64) it is broken for a distance of 41 yards by the torrent bed descending from the watershed. At the western end where in all probability a sluice gate or some similar contrivance was placed the dam turns at right angles for 15 yards to the south before striking at a slant the foot of the rocky spur upon which its flank rests.

Construction of barrage—At a point 72 yards from the above mentioned angle the dam has been breached for a distance of 20 yards by a minor torrent bed descending from the north west. This breach has been very imperfectly closed by a modern embankment only 34 feet high. This is roughly built up with stones from the ruined section of the dam and meant merely to assure more watering when rain falls to the field now extending over the lowest portion of the ancient reservoir. Some 60 yards farther on the dam forms a re-entrant angle and continues for a distance of 18 yards on a line set 2 yards further back. This section which lies approximately in the middle of the barrage and thus perhaps was exposed to additional pressure has been strengthened by a buttress on either side projecting 2 yards beyond the main face of the dam and 5 yards broad. The two buttresses though built with big blocks of stone like the rest of the dam have now fallen for the most part and at first sight might suggest breaches. Two more ruined buttresses also projecting 2 yards but only 2 yards broad are found at distances of 9 yards and 8 yards respectively further to the east. A portion of the facing wall of the dam has broken down farther on for about 6 yards as shown by the sketch plan and another break was made for the passage of the motor road.

The wall facing the dam to the south stands in places still to height up to 12 feet. As Fig. 63 shows it is built with large rough blocks of stone very carefully set though without mortar or regular courses. The large blocks used show sizes like  $4\ 3 \times 2\ 1$ . Though the hillsides from which they were taken are close by yet the transport and putting into position of such stone blocks

\* Mason's *Journey to Eilat* pp. 69-74, 320. He mentions the Gabar bands of Lakorian as the most remarkable among many in Jhalawan. He assumes them to have been places of defence.




FIG. 63. GADAR BASIN ABOVE MECCA.




FIG. 64. WASTELAND OF GADAR BASIN, ABOVE MECCA.




FIG. 65. SOUTHERN END OF GADAR BASIN, ABOVE MECCA.



FIG. 66. SOUTHERN END OF GADAR BASIN, ABOVE MECCA.





must have claimed great labour and a good deal of skill. The thickness of the stone built dam seems to be about 9 to 10 feet. Its power of resisting the pressure of the stored water was greatly increased by a rampart of earth and stone behind. This slopes down at an angle of about  $25^{\circ}$  and ends within the area of the reservoir on a present level of about 2 feet above the outside foot of the wall.

Extent of reservoir—Some idea of the volume of water which could be stored behind this barrage may be formed from the distance about 240 yards, which separates the top of the wall from the slope of the hillside to the north at the same level. The lowest portion of the area thus turned into a reservoir forms now a flat patch of clayey alluvium which is cultivated after adequate rain has fallen. Above the area once comprised in the reservoir smaller 'Gabar bands' of similar but less massive construction are seen to the north and north west separating terraces which were once under cultivation. These of course were watered by the drainage before it found its way into the storage basin. A succession of such 'Gabar bands' are visible eastward from the road right up to the watershed. One of them crossed about 400 yards above the reservoir stretches right across the defile, here much narrower than below and obviously served for subsidiary storage of water. The whole planning of the main dam and the work executed above it suggests a thoroughly developed system of irrigation, and deserves exact survey and study if possible by a competent irrigation engineer.

The remainder of the day's journey took us through the upper end of the Anpara valley where much 'Khushlaba' land lay untilled. Then across an easy pass well over 6000 feet and across bare plateaus broken by detritus filled nullahs the wide valley of Surab was reached. There at the rest house the long, mired sight of fruit trees in bloom and spring flowers pleasantly greeted us, and there we found ourselves once more on our old track which we had left just over four months before in the bleakness of approaching winter.

### SECTION III.—FROM KALAT TO MASTUNG

The mounds near Rodmji which I examined on my journey on April 10th from Surab to Kalat have already been described in a previous chapter.<sup>1</sup> My stay at the Kalat Residency on April 11 12th enabled me to inspect what old mounds were reported in the vicinity. It also allowed me to gain some acquaintance with the physical conditions of the high valley in which the political centre and chief settlement of Sarawan and the adjacent portions of Baluchistan appears to have been situated all through later Muhammadan times anyhow those of Baluch and Brahui ascendancy if not earlier also. The political importance of Kalat is sufficiently indicated by its name simply meaning the Castle.

<sup>1</sup> See above p. 17

<sup>2</sup> The *Surab Gazetteer* p. 230 refers to the more specific designations of Kalat, Dand and Kalat Surab as known to the natives. The former is derived from Kalat Ghilji in Afghanistan and the latter from its legendary founder.

Importance of Kalat—There is good reason to assume that the importance of the place is due mainly to its central position its situation on a great line of communication from north to south most convenient both for trade and military movements and perhaps also to the climatic advantages secured by the elevation of the valley (about 6100 feet on the average) Irrigation is limited to the narrow belt which stretches down from the foot of the rugged hills south of the Khāns castle to where the small stream fed by the fine spring known simply as Chashma and by Karezes leaves the valley below the village of Malguzar Even including the now abandoned Khushkaba fields about Bazid to the north the total extent of ground capable of cultivation in parts scarcely exceeds five miles in length and a mile in width The actual extent of tilled land is far more limited

Decline of Kalāt—The advent of the railway has deflected most of such trade as there was to Quetta and Mastung and political changes have affected the position of Kalat as an administrative centre Shorn of these advantages derived from human factors Kalat has seen its prosperity steadily dwindle, until now the town nestling below the large grim pile of the Miri is for the most part deserted and the population of the whole valley down to Malguzar reduced to about two thousand according to the Census of 1920-1 Were it not for the Khāns troops and his numerous retainers it would be still smaller It is important to note that at Kalat just as at Mastung by far the greatest part of the cultivated area depends on Karez irrigation and also that in both tracts the main body of the settled cultivators consists of Persian speaking Dehwars These are undoubtedly of Tajik origin<sup>3</sup> and believed probably with good reason to have originally come from Kandahar and other parts of Afghanistan It is very tempting to connect the development of Karez irrigation at Kalat and also at Mastung with this settlement during a comparatively late period of culturally advanced and industrious Tajik immigrants

Absence of large mounds—Attention had to be called to the local conditions just briefly indicated as they help to explain to a great extent why in spite of the important part played by Kalat in the modern history of Baluchistan there are no remains of ancient settlements of any size to be traced in this tract The absence of large mounds with prehistoric pottery of an early type is in any case significant It seems to lend support to the inference that the valley could have been but scantily settled before the introduction of Karēzes, no doubt in historical times rendered close occupation possible at least over a part of it

Damb<sup>4</sup> of Kalat—The *Damb-i Bazid* at which my survey began proved nothing more than a low natural ridge cropping out in the middle of the valley some 3½ miles to the north of the Residency No ancient remains were to be found on it but around could be seen traces of terraced fields long ago abandoned Proceeding across these to the SSW for about 2 miles there was reached the mound of *Bundālū* It is situated about half a mile to the east of Malguzar village near Karez irrigated fields and is entirely artificial It is about

<sup>3</sup> Cf. *Sararfin Gazetteer* pp 68 sq

15 feet high and extends for about 80 yards from east to west. Amidst plenty of coarse plain pottery but few painted pieces could be found on the surface. These too showed only poorly drawn parallel bands in black resembling the late ware found on the mounds near Rodinj.<sup>4</sup> The *Malghori* damb about half a mile to the DSE of the Residency is a small natural hillock of calcareous stone cropping out from the peneplain beneath which pass all the Kalat karizes. The hillock is covered with stone debris from decayed habitations and coarse plain pottery of no old look. But among some chert flakes picked up here a few show signs of having been used as scrapers. Out of the eight karizes which have their heads around the hillock three no longer supply water. Two of these were said to have run dry for the last five or six years and the third a generation ago. The *Khishkaba* fields around are no longer tilled. The same is the case with the area to the south known as *Dasht-i Murad* which before received water from the fine spring the *Chashma* already referred to. Its volume was said to have diminished in recent years and to be no longer sufficient to reach so far.

Another low hillock called *Khwaga Zabar* about 200 yards to the SW of the *Malghori* damb\* is also covered with rubble from decayed dwellings. It measures some 130 yards from east to west and about 100 yards across. Here too the painted pottery showed mostly the same late type as at *Bundakhi*. But a few fragments decorated in black with the hook design familiar from *Suneri* and other *Jhriawan* sites point to occupation having started here in late prehistoric times. About 300 yards to the south there crops out among abandoned fields a low mound partly natural known as *Khad-i Aking* from the hamlet near by. It measures approximately 100 by 40 yards and rises to a height of 10 feet. Here we found besides painted fragments of the late prehistoric type pieces of plain blue and green glazed ware which may belong to early historical times.

Ruined tombs near the *Chashma* —The visit paid from here to the 'Chashma' spring about 2½ miles to the south, proved of interest. It took me past pleasant orchards and homesteads all recalling a small oasis in Persia and clearly bearing the impress of their *Delwar* owners' racial origin. Near the great spring is found a group of half ruined domes under which are buried the *Ahmadzai* Khans of Kalat. They gave to the spot a striking resemblance to one of the 'Sub-shirs' (head of water) of Chinese Turkestan venerated by *Muhammadians* of the present day quite as much as they were in Buddhist times. The fine spring which issues from two karizlike rifts about 30 feet below the valley floor supplied at the time I measured its volume approximately 900 cubic feet of water per second. This volume was declared to have diminished as compared with that of former times. Yet this reduction seems scarcely sufficient to account for the badly neglected look of the arbour and fields of lucerne which cover the ground between the spring and the crumbling town walls. It was a picture of decay illustrating once more how in an arid land

<sup>4</sup> Cf. above p. 1

human factors can within certain limits produce results which centuries hence might easily be mistaken for those of true desiccation<sup>6</sup>

**Mound of Kullu Kalat**—Information collected already on my passage from Quetta in November enabled me to use my journey to Mastung on April 18th for visiting two dams reported in that portion of the Mungachar tract which the road crosses to the north of Kalat. This large and owing to its Karezes comparatively well populated tract drains into the Shinnab river passing to the west of Mastung. The same river receives also the drainage of the Chapar valley to the north west of Kalat which contains near its centre a mound known as *Kullu Kalat*. This I was not able to visit owing to its distance from Kalat and the need of husbanding time for a meeting arranged with Sir John Marshall at Taxila by the third week of April. Specimens of painted pottery brought to me from that mound comprised fragments which are manifestly of late prehistoric type. Some glazed pieces seem to indicate that the locality was occupied also during historical times down to the Muhammadan period.

**Mound of Salu Khan**—From the Levy post of Mungachar which was reached after a twenty miles drive from Kalat a ride of close on five miles to the north west brought us to the dam of *Salu Khan* named after the hamlet built at its foot. The way led first across a long series of Karezes many of them destroyed a couple of years before by a heavy flood from the high range to the south east and then across a wide clayey plain with scattered patches of 'Khushkaba' fields left untilled for years. The hamlet too appeared to have been abandoned. The mound rising above it (marked on the map as a triangulation station with the height of 5880 feet) is about 30 feet high. Its position in a wide trough proves it to be of entirely artificial origin. It measures at its foot about 120 yards from SW to NE and some 80 yards across. Its top is crowned by a low wall of rough stones enclosing a Ziarat. The slopes are covered with plentiful plain potsherds of coarse make and small stones evidently from decayed dwellings built with rubble and clay. Only few painted fragments were found and those of the same late type as at the mounds near Rodiny and Kalat.

**Mound of Sayid Maurez**—Moving due east for three miles past fields still receiving water from Karezes we reached the cluster of hamlets known as Mandehay and half a mile further the mound which after a much frequented Ziarat on its top is called the *Sayid Maurez dam*. The map marks it with the height 5860 feet. An extensive graveyard spreads at its southern foot. The mound appears to be wholly of artificial origin and measures about 300 yards from north to south and some 250 yards where widest. It rises to a height of about 40 feet from the gently sloping ground to the north while its height from the level of the Mujawis hut to the south is over 50 feet. The plentiful potsherds on the slopes are chiefly of plain red buff or greenish grey ware while the painted fragments show mostly hooled scrolls (Maur 12 Pl. XXXII) of the late prehistoric type of Sunan etc. But by the side of these there were picked up low down in an eroded Nullah and at the foot of

<sup>6</sup> Cf. for observations recorded by me *S and A* pp 603 sqq pp 625 sq

the mound some pieces resembling Nil pottery in design and colour as well as a few others with neatly executed geometrical patterns which look distinctly early. The mound obviously marks a settlement of some size. As no glazed ware could be found it is probable that it was not occupied since prehistoric times. A mile beyond the road was regained and the journey continued to Mastung.

Mounds near Mastung.—Already during my stay at Mastung early in December I had used a brief interval in the strenuous labour, which detained me there to pay a visit to the large mounds to the north west of Mastung town. Of these the *Sampur damb* situated at a distance of about 2½ miles in a direct line from the Political Agents Bungalow had been the scene in March 1920 of systematic and fruitful excavations conducted by Mr Hargreaves. The detailed account which he has given of these and which has become accessible to me since my first visit\* makes it unnecessary for me to record the impression then gained. I may however mention that Mr Hargreaves finds of a fine silver cup rightly assigned by him to the 1st century A.D. and of an Indo-Scythian bronze coin completely confirm the conclusion then drawn by me from the potsherds I had picked up on the surface. These comprised plain ribbed ware, fine red pottery decorated with parallel polished lines, the fluted handle Sam I (PLXXXII) and the neck of a large jar Sam 2 decorated with an impressed scroll ornament. All these are methods of ornamentation which observations made in the course of my explorations in Sistan, Upper Sindh and northern Baluchistan had led me to associate with pottery of the early centuries of our era. To this period pointed also a fragment retaining traces of a thick blue glaze. The few pieces of pottery painted in black on red or buff showed too little of their patterns to define their type. All the more interesting it will be to examine the painted potsherds excavated by Mr Hargreaves when reproductions become accessible.

Mound of Spet bulandi.—Mr Hargreaves has already noted and briefly described the conspicuous mound which rises three miles to the north of the Sampur damb and is marked on the map with the elevation of 5246 feet. Fig. 62 shows it, as seen from the south east across bare clayey ground. Its name was given to me in its Baluchi form as *Spet bulandi*, the corresponding Persian form being *Safid bulandi*. At the northern foot of the mound issues a spring filling a tree shaded pool which is visited on certain dates as a Tirtha by local Hindus from Mastung town and neighbouring places. It had in fact on the day preceding my second visit been the scene of such pilgrimage. The plentiful decorated pottery to be found on the surface had attracted my attention already on my first visit in December and as the mound showed no sign of previous exploration I determined to use a day's stay at Mastung, on April 14th, for some rapid trial excavation.

As seen from the sketch plan Pl. 10 the mound is of considerable size its measured perimeter being 77½ yards and its length from east to west approximately 490 yards. Its height as roughly levelled proved to be 78 feet. On the

\* See *Annual Report I.S.I. 1924-25* pp. 50-60, 111-113.

\* The form as indicated on the map into *17½ miles* by a kind of popular estimate.

top some long slabs of stone, undressed and probably dug up from the mound, have been set up by pious hands to mark the spot where a certain holy man, Yak Paṣi by name, burned at Bahram shahī, near Mastung is supposed to have sat and taught. The whole mound shows everywhere on the surface a greyish-white colour, the whole consisting of alluvial soil from the decomposed mud-brick or *pise* walls of dwellings. This accounts for its name, the white hillock'. The softness of the earth, nowhere mixed with stones or other hard debris, obviously facilitates erosion. This explains the great abundance of pottery to be found on the surface.

Decorated pottery.—Besides good plain ware, either red throughout or bearing a whitish or light cream coloured slip on the outside there were found here as the specimens in PI XXXII show, many flat ribbed pieces (S Bul 1,2) both with and without a creamy white slip, fragments of small vessels with a fine terracotta slip and parallel polished lines (S Bul 3,4), and fragments of larger ones with incised or impressed ornament like S Bul 5,6. The relief-decorated bases S Bul 7,9 show a treatment closely corresponding to that on cups excavated by Mr Hargreaves at the Sampur mound\*. Special interest attaches to the application of a whitish slip over red ware, whether plain or decorated, like the handle S Bul 8 or the ribbed piece S Bul 2, for it fully agrees with the same colouring commonly found on the pottery dating from the early centuries of our era at such widely separated sites as Moghul ghundai Tōr dhērai in the north and Jiwanni, Zangān, etc, in the south. This furnishes a valuable chronological indication. Of glazed pottery only a very few small pieces were found, they showed a plain blue or green colour, in each case much effaced. Equally rare were fragments of painted ware, with coarsely executed design in black or dark brown, they are too few and too small to allow the type of pattern to be determined.

Pottery found in trial trenches.—The trenches IIV shown on the sketch plan were cut on different levels of the upper portion of the mound and carried to an average depth of 4.5 feet. The potsherds found (for specimens, see PI XXXII) all corresponded in type to those already described which erosion had exposed on the surface. The fragment of a small cup, S Bul IV 1, is of a shape exactly the same as illustrated among Mr Hargreaves' specimens from the Sampur mound (see his PI XV g). The base here too is disproportionately small as in so many of the cups from early chalcolithic mounds like Periano ghundai and Suktagen dōr, yet the modelling is quite different. The very coarse hand made cup (?), S Bul IV 2, is curious, it is fitted on to a heavy fragment of iron and its purpose obscure. The fragment S Bul I 1 is decorated with a cable ornament in relief, often found on the NW Frontier on pottery of the Buddhist and later periods. Fragments of small iron implements found in trench IV would suffice to establish the fact, if any further proof were still needed, that the deposits of Spūt buland belong to the historical period.

Prolonged occupation of site.—The agreement between the pottery remains at this mound and at the Sampur one is so close that the contemporary occupation

\*See *Annual Report A S I* 1924-25, PI XV L g

of both sites may be considered as certain. That this occupation lasted for a prolonged period may in view of the height of both mounds be safely assumed with Mr Hargreaves also that this occupation ceased before Muhammadan times and was never afterwards resumed. And here it may be pointed out that the close similarity in shapes between a number of the complete vessels excavated by Mr Hargreaves\* and those found by me at sites so distant as the burial grounds of Moghulghundai in Zhob and Jiwan in Zangian etc. in Makran is of special documentary value because it allows us to prove that the same ceramic style prevailed over so wide an area within the identical period.

**Absence of prehistoric mounds.**—In conclusion attention may be called to the curious observation that in a tract which now certainly is the best cultivated and most populous within the whole of the Kalāt State<sup>10</sup> no mounds indicating occupation within prehistoric times appear to exist. Accepting their absence as a fact—and in view of Mr Hargreaves prolonged work at Mastung this can scarcely be doubted—we are naturally induced to look for some explanation. The only one which I can think of at present is suggested by the analogous case of Kalāt. There, too we have noted a locality of importance in historical times where no evidence of prolonged prehistoric settlement can be traced. At both Kalāt and Mastung it is the extensive use of Karizes which permits of close occupation by an agricultural settlement. Would it be right to connect the presence at Mastung of large mounds dating from the early centuries of our era and the absence of others from prehistoric times with the great change which the introduction of Karez irrigation must have brought about in the economic resources of those areas? Under arid climatic conditions cultivation without Karizes would there necessarily be very precarious and insufficient to maintain more than a thin and semi-nomadic population. But here as in so many cases where we are dealing with negative facts and where historical records fail us the critical student will be well advised to refrain from a definite answer.

At Mastung the exploratory work of my tour came to its close. On April 10th I regained Quetta. There under the hospitable roof of the Hon'ble Colonel H. B. St. John the Governor General's Agent and Chief Commissioner I was kept very busy for one day disposing of the manifold practical tasks connected with our 'demobilization'. Then the urgent call of the meeting already referred to obliged me to hurry northward to Taxila. There in the delightful surroundings created by Sir John Marshall's care at a fascinating historical site it seemed strange to recall all the scenes of prehistoric life which those months of happy if trying work had allowed me to see in poor and Gedrosia.

#### FINIS

\* Compare Pl. Nos. 54 and Nos. 37-38-59 in photographs and in press vol. of Mr Hargreaves Pl. XL of 5th report pottery with the specimens from the above named sites reproduced in Pl. Nos. of V. B. St. John's Tour and Pl. VIII in XI below.

<sup>10</sup> The Census returns of 1901 as recorded in H. B. St. John's Pl. I p. 52. (p. 54) show for the Mastung tract a settled population of 6886. Assuming 10 persons to the acre the tract to be about 90 square miles as suggested by the map and the villa estate that would indicate a population of about 90 persons are in the number vastly in excess of that of any tract in the Kalāt State.





## APPENDIX

# REPORT ON A COLLECTION OF BONES MADE BY SIR AUREL STEIN IN MAKRAN

BY

LI Col R B SEYMOUR SEWELL I MS MA Sc D (Cantab) FZS FLS., F A S B.,  
DIRECTOR ZOOLOGICAL SURVEY OF INDIA

AND

B S GUHA A.M., Ph D  
ANTHROPOLOGIST TO THE ZOOLOGICAL SURVEY OF INDIA.

### INTRODUCTORY REMARKS

The collection sent to us by Sir Aurel Stein for examination and report comprises two human skulls and a number of small bones and bone fragments etc that were found during the course of excavation in cinerary pots, funerary vessels, funerary bowls or loose in the earth. A complete list of these fragments is given in Appendix A. Both the skulls were still to a large extent embedded in the earth in which they had been buried. The earth was clearly an alluvial deposit and mixed with it were a number of small stones, fragments of charcoal, broken brcl., etc. Dr G de P. Cotter of the Geological Survey of India has very kindly examined the stones for us and he reports as follows —

The largest rounded stone appears to be a fine grained sandstone. A micro-section was cut from a smaller piece very similar to the large one and proved to be a fine grained sandstone cemented by copious calcareous material. Such rocks are found abundantly in the Tertiary and Pleistocene. The smaller fragments are kankar i.e. concretions of secondary calcium carbonate and this coats the sandstone fragments also.

In addition to these stones, charcoal fragments etc. there was a single sub-fossil shell of the mollusc *Mytiloides tuberculatus* (Müller), a common inhabitant of fresh water and possessing a range of distribution at the present day from Morocco throughout India, Burma and Ceylon to China and Australia. This shell was probably an original ingredient of the alluvium.

During the process of cleaning away the earth from the skulls several interesting objects came to light. Skull A, which appears to have been buried

on its left side had become greatly crushed but near the top of the cranium and in close proximity to the left parietal bone were a number of sub fossil shells 12 in all of a species of mollusc belonging to the genus *Natica*. Dr Srinivasa Rao of the Zoological Survey of India has very kindly examined these shells and he informs us that so far as it is possible to judge they are a variety of the species *Natica osellus* Reeve. Exact specific determination is not possible as in every case the shell was considerably eroded and the lip of the mouth was broken. The genus *Natica* has a wide distribution throughout the great Oceans and the species *N. osellus* Reeve is known to occur throughout Indian seas. The occurrence of a small group of shells of a marine mollusc in the situation in which they were found and their absence in every other part of the earth attached to the skull appears to indicate that they had been placed there deliberately at the time of burial and were not a natural ingredient of the alluvium and it is possible that the number 12 may possess some significance.

Embedded in the earth surrounding skull B was discovered the head of a humerus (arm bone) that was apparently human and in all probability was originally part of the same skeleton and near the right side of the face were the bones of the leg of a sheep (*Ovis* sp.) including the lower part of the Tibia, the Tarsal bones and the upper part of the 3rd Metatarsal bone.

### GENERAL CHARACTER OF THE BONES

The bones were extremely fragile and were of a pale fawn colour. In both appearance and texture they were very similar to bones that have been excavated by the Archaeological Survey of India at Mohenjo-daro in Sind and at Nal in Baluchistan and regarding which we have already submitted our reports<sup>1</sup> and

There was no trace of any blackening or charring of the bones and we are of opinion that the bodies had not been burnt. The presence of small fragments of charcoal in the earth surrounding the bones might be thought to be evidence in favour of cremation, but such fragments would very easily be washed up and deposited in an alluvial mud and as we have already pointed out, the earth surrounding the bones was clearly of an alluvial character. In both cases the body appears to have been buried on the left side with the head strongly flexed on the chest so that the posterior region of the mandible and especially the angle was in close relationship to the cervical vertebrae and as a result of this position the lower jaw had been retained in position relative to the upper jaw the upper and lower teeth being in apposition.

### SKULL A

The whole of the skull has been crushed flat the parietal bones being distorted and flattened so as to abolish almost entirely their natural curvature.

<sup>1</sup> Sewell and Gaha. Report on the bones excavated at Nal. Excavations in Baluchistan App. n. ix. v. pp. 50-80.

<sup>2</sup> Sewell and Gaha. Preliminary report on the bones excavated at Mohenjo-daro. (in the press).

The frontal bone has been broken irregularly into two portions the line of fracture passing very nearly down the median line and a portion in the region of the glabella has been thrust outwards (forwards). The upper part of the coronal suture has been widely forced apart to the extent of 2.5 cm. The right parietal bone has been broken the antero-superior angle being completely detached. The occipital bone has been pushed over to the right side and is considerably distorted. The right mastoid process is completely missing and the posterior two-thirds of the right zygomatic arch is absent. The nasal bones have also disappeared. The right orbit is nearly intact in so far as the margin is concerned, but the three bones of the inner wall including the ethmoid and the lachrymal have been displaced and pushed into the orbit obliterating about one-half of its extent. Both the maxilla and the mandible have been crushed flat the mandible being broken across in the middle line. On the left side the whole of the cranium has been flattened and pushed inwards and the external margin of the orbit has been crushed against the inner wall and the side of the nose. Owing to the skeleton having lain on its left side the bones of this side have undergone considerably more decay than those on the right and in consequence it was a matter of very considerable difficulty to clear this portion of the skull from the earth in which it was embedded.

The face when viewed from the side presents a remarkably prognathic appearance but owing to the distorted and crushed condition of the skull it is very difficult to decide to what degree this prognathism is the normal condition of the skull and how much is due to the flattening and consequent thrusting forward of the 'muzzle' region. We are of opinion however that there must have been a considerable degree of prognathism in life. It is interesting to note that in spite of the distortion and compression of the skull, those incisor teeth that are still *in situ* in the jaws meet in exact apposition and the upper incisors do not overlap in front of the lower. This condition as has been pointed out by Keith, is a characteristic of the skulls of palaeolithic and neolithic times.

The upper part of the vertebral column though much broken and decomposed, is still *in situ* in the neighbourhood of the foramen magnum and from the relative positions of the various parts of the vertebral column and the skull it is clear that at the time of burial the head must have been strongly flexed on the chest the angle of the mandible thus coming into close relationship with the upper vertebrae. As a result of the compression mentioned above the right ramus of the mandible has been forcibly pressed inwards (i.e. downwards) against the bodies of the vertebrae and has been broken. The coronoid process of the ascending ramus is still attached to the body of the mandible but the posterior part of the ascending ramus has been broken across and the condyle has been detached. The remains of the condyle were still in the glenoid fossa but were too decomposed to be preserved.

Judging from the thickness of the cranial vault the individual was in our opinion, probably a male and was undoubtedly adult. There are no indications

of any closure in any of the parts of the sutures that remain intact and capable of examination. Such teeth as are present are in good condition but are markedly eroded the crowns of the molar teeth being worn flat as is the case with the teeth of the skulls from Nal and Mohenjodaro.

Such measurements as we have been able to take on this skull are given below in Tables 1 to 3 together with those of skull B and we have also given those of the Nal skull for comparison.

### SKULL B

This skull is in a great deal better state of preservation than Skull A but it too has undergone a considerable amount of compression and distortion. The right occipitoparietal region has been considerably compressed and flattened and thrust over to the right while the face is pushed over to the left side. Unfortunately during transit from Sir Aurel Stein to the Indian Museum the skull suffered a certain amount of damage the symphysial region of the mandible was broken and the bones of the upper part of the cranium were detached and smashed into small pieces that up to the present time we have been unable to fit together. We have attempted to reconstruct the mandible and in the process we may have somewhat exaggerated the symphysial height, so that such measurements and indices as depend on the correct position of the 'gnathion' must be accepted with reserve. The depth of the horizontal ramus opposite the 2nd Molar tooth is 32 mm but this rapidly increases till opposite the 2nd Premolar tooth it is between 40 and 41 we do not think that the calculated symphysial height of 40 is likely to be far out.

The bones of the upper part of the right orbit and nearly the whole of the frontal region the upper parts of the parietal bones and the supraoccipital portion of the occipital bone are missing and the upper margin of the left orbit was detached. Fortunately the earth with which the skull was filled has remained more or less intact so that the general outline of the skull is still indicated.

The skull has undergone as we have mentioned already some degree of distortion resulting in fracture of some of the bones. The occipital bone has been snapped across near the middle line and in the region of the union has been pushed outwards. The whole of the outer wall of the left orbit including the malar bone and the zygomatic arch of the left side are missing and the greater part of the left mastoid process is also wanting. The left margin of the nasal aperture is broken and the bone displaced inwards to a slight extent. The symphysial region of the mandible is broken and in addition the whole bone has undergone a certain amount of warping.

The muscular attachments are well marked running at first backwards and then backwards and upwards from the posterior end of the zygomatic arch on both sides of the body is a well marked bony ridge that is continued into the line of attachment of the temporal muscle. The right mastoid process is remarkably long the distance between the porion and the lower end of

the mastoid process being as great as 37.25 mm the process is comparatively narrow but the hyoid groove on the internal aspect is deep. The angle of the mandible is everted and forms a distinct crest.

The lower jaw was *in situ* but has undergone a considerable degree of warping. The symphyseal region has been badly broken and the alveolar margin pushed back so that the incisor teeth are displaced and a spurious appearance of prominence given to the right canine tooth. The left canine and 1st premolar are missing as also is the 2nd molar on each side. The depth of the body rapidly increases from 32 mm opposite the 2nd molar tooth to 40 or 41 mm between the 1st and 2nd premolar teeth. The region of the gnathion appears to have been prominent and there is a well marked vertical crest on the inner aspect running from the geniohyoid tubercle to the lower border of the symphysis. All the teeth are considerably worn with the exception of the 3rd molar. As was also the case in skull A this skull appears to have been strongly flexed on the chest at the time of burial so that the chin pressed on the chest and thus retained the lower jaw in position. In this case the upper incisor teeth appear to have overlapped the lower incisors. There is some degree of prognathism present but in the main this seems to have been of the alveolar type the facial angle falling near the line between mesognathism and orthognathism. The teeth are large and are considerably worn though not quite to the same extent as in skull A. Owing to the better state of preservation of this skull it was possible to take many more measurements these are given below in Table I.

The skull appears to have been dolichocephalic though not so long as the *Nal* cranium. The frontal and supraorbital regions are too damaged to permit of any very definite description but the glabella and supraorbital ridges do not appear to have been pronounced and the nasion is not markedly depressed. The forehead judging from the appearance of the skull and the contained mass of earth was of moderate height and probably sloped backwards to a slight extent. A supraorbital foramen was present on the left side.

Owing to the impossibility of obtaining any measurement even approximate of the length or breadth of the cranium it has not been possible to calculate the cranial capacity by means of the Lee Pearson formula. We have however been able to get an approximate estimate of the auricular height namely 119 mm and from this we can calculate the cranial capacity by Wingate Todd's formula —

$$\text{Cubic Capacity} = 14.43 \times \text{auricular height} - 288 \text{ cc}$$

This gives a result of 1428.0 ccs which compares quite favourably with the calculated cranial capacity of the *Nal* skull in which the same formula gives an estimated capacity of 1442.9 ccs.

\* A. C. Lee and Karl Pearson. A first study of the correlation of the Human Skull. *Phil. Mag. Ser. 6*, vol. 106, p. 74, 1908, London.

\* T. Wingate Todd. Mathematical Calculation of Cranial Capacity. *Amer. Journ. Phys. Anthropol.* vol. 11, p. 178, 1922, Washington D.C.

The sex of the skull is in all probability male. The bones of the upper part of the cranium are comparatively thin but the degree of development of the muscular crests seems to us to point towards the skull belonging to the male sex. The individual was adult all the teeth are erupted and closure of the sutures had already commenced especially in the lambdoid suture of the right side near the lambda.

TABLE I

Measurements	Skull A	Skull B	Nat. Cranium
	mm	mm	mm
<i>The Skull</i>			
Maximum horizontal circumference		475*	528*
Nasion Lambda Sagittal length	268	268	271
Auricular height		119	120
Nasion prosthion length		81.5	72
Nasion gnathion length		130*	
Nasion basion length		103*	99.5
Bizygomatic breadth		116*	120*
Orbital breadth	41		40
Orbital height	33		33
Interorbital breadth		21	20
Nasal height		54	49
Nasal breadth		25.5	23
Length of alveolar arch		59	59.5
Breadth of alveolar arch		66	65*
Molar length		45	42
Palatal length		50	53
Palatal breadth		42	42
<i>Mandible</i>			
Bicondylar breadth		108	
Bigonial breadth		95.5	

\* All measurements marked with an asterisk are approximate only and have been obtained by calculation.

TABLE I—contd

Measurements	Skull A.	Skull B P	Nat Cranium
	mm	mm	mm
<i>Mandible—contd</i>			
Mandibular length		74	
Height of Ramus	57	{ R 58 L 60	
Minimum breadth of Ramus	35	{ R 31 L 34.5	
Maximum breadth of Ramus	40	44	
Symphysial height	36	40*	
Height of body		32	
Mandibular angle	117°	121°	
Facial angle (Frankfort)		{ R 85° L 83°	88°

\* All measurements marked with an asterisk are approximate only and have been obtained by calculation.

TABLE II

Indices	Skull A.	Skull B	Nat Cranium
	mm	mm	mm
Total facial Index		91.1	
Superior facial Index		70.3	60
Orbital Index	80-49		82.5
Nasal Index		43.5	46.91
Alveolar Index		111.9	100.3
Palatal Index		80.4	79.25
Dental Index		42.7	42.2
Mandibular Index		60.1	
Ramus Index	63.15	{ R 77.5 L 53.0	



TABLE III

Measurement of the teeth		Skull A	Skull B	No. Cranium
<i>Upper Jaw</i>		mm	mm	mm
<i>Right side</i>				
1st Molar	Length	11 0	11 5	11 0
	Breadth		13 0	13 0
2nd Molar	Length	10 0	11 25	10 0
	Breadth		12 5	11 5
3rd Molar	Length		9 5	9 5
	Breadth		11 5	11 0
<i>Left side</i>				
1st Molar	Length	10 0	11 0	11 5
	Breadth		13 0	13 0
2nd Molar	Length		11 0	11 25
	Breadth		13 0	12 0
3rd Molar	Length		9 5	
	Breadth		12	
<i>Lower Jaw</i>				
<i>Right side</i>				
1st Molar	Length		12 5	
	Breadth		11 5	
3rd Molar	Length		13 0	
	Breadth		11 75	
<i>Left side</i>				
1st Molar	Length		13 0	
	Breadth		11 5	
3rd Molar	Length		13 0	
	Breadth		11 5	

The 2nd Molar tooth on each side was broken

## RELATIONSHIP

Owing to the compression and distortion that both skulls had undergone, as a result of the pressure of the superincumbent earth in which they had been buried, it is impossible to be absolutely certain regarding the true shape of the skulls during life, but so far as can be judged they were both dolichocephalic and the second skull (skull B) appears to have possessed a high vault very similar to that of the 'Nal' cranium. Unfortunately the lower jaw is not present in the "Nal" cranium and in consequence one can only conjecture what the face as a whole was like, the upper facial index, however, shows that this portion of the face was long and narrow (leptene), and this character is even more marked in Skull B of the present collection, in which it is hyperleptene having an upper or superior facial index of only 71.55. Again in the 'Nal' cranium the nose is long and narrow and in skull B this character is even better marked, for whereas the 'Nal' skull possesses an index of 46.94, which just puts it in the leptorrhine group in skull B the index is only 43.5 so that the nose is very leptorrhine. Both the orbital and alveolar indices are of moderate amount, the skull being mesoconch and mesostaphylina. Owing to the distortion that the skull has undergone the facial angle is not quite the same on the two sides of the body on the right side it is  $86^{\circ}$  and on the left  $83^{\circ}$ .

There can be little doubt that skull B was long and had a high vault. The face was long and narrow, and the nose also was long and narrow and in all probability had a high pitch. The teeth which are large, are set in an arch of moderate size (mesostaphylina). The angle of the jaw is pronounced and though there is some slight degree of prognathism present, this is almost entirely alveolar in type, the actual facial angle being between  $83^{\circ}$  and  $86^{\circ}$ , thus falling near the border line between orthognathism and mesognathism.

While agreeing with the "Nal" skull in its general type Skull B would appear to show traces of mixed origin and in certain respects tends to approximate to the Caspian or Nordic Type of skull.

## APPENDIX

*Skull A*.—From a body buried in Shahi tump Makran

*Skull B*.—From a body buried in Shahi tump, Makran

*Parcel 1*.—Suktageñ dor, from a cinerary pot Bone fragments

- (1) Lower end of humerus of a small mammal—? Sheep (*Ovis* sp.)

*Parcel 2*.—Suktageñ dor from a cinerary pot Bone fragments

- (2) A vertebra of a fish
- (3) Teeth of an Ox (*Bos indicus* ?)

*Parcel 3*.—T he dap

- (4) Several spines of a Sea Urchin (*Stomopneustes variolaris* Lamarck)

*Parcel 4*.—Shahi tump bones from funerary vessel

- (5) Portions of a lower jaw with molar teeth of a sheep (*Ovis* sp.).

*Parcel 5*.—Shahi tump bones in funerary bowl

- (6) Small fragments of bone indeterminate

*Parcel 6*.—Mehi bones from burial deposit

- (7) Part of the head and greater tuberosity of the humerus of a small mammal (*Ovis* sp ?) The animal was young and not fully grown for the Epiphysis had not yet joined to the Diaphysis (shaft)
- (8) A fragment of a vertebra of a small mammal The animal was not yet adult for the Epiphysis had not yet joined with the centrum

The bone fragments had become stained a green colour suggestive of the presence of copper

*Parcel 7*.—Nundara, bone fragments from S E corner of cella below stone slab

- (9) Portion of a rib of a large mammal probably an Ox (*Bos indicus* ?)
- (10) Part of the Os innominatum of a large mammal probably an Ox (*Bos indicus* ?)
- (11) Part of the axis vertebra (2nd cervical) of a ruminant (*Ovis* sp ?)
- (12) Lower end of Metacarpal III of fore limb of a small mammal (*Ovis* sp ?)
- (13) Portions of ribs of a small mammal

## B.

Abd i but      te m Wad]	43 1 0
Aldul Chafur Nail    S rveyor and Draftsman	43 156
Bel an end an emp re	43 9 7
Adusta d nl mound in Jhau	43 158
Afgh n stan	43 9 1 0 184
Afr can element in pop lation of Mal r n	43 1
Abmadza family	43 13 182
And i l mb mo m l n Drakalo	43 1 1 8
Al l t r M n r Sapper	43 16
Alfaster cys bo ls etc	43 55 63 65 84 89 93 94 102 108 148 160
Alexander the Great	43 8 11 6 f 1f 6 6° 137
Al al ad l amlt	43 18
Allal dad Kl an Nal of Gayer	43 1 0
Allu l son	43 9 23 94 30 3 31 42 53 58 61 6 67 8 104 105 106 109 116 118 129 133 136 139 140 146 147 1 5 1 4 165 1 188 191
Alu n n m ta h	43 15
Annbas see also Arr a	43 11 notes 1 & 57 note 1
Dr n lersso s explorations	43 5
Andr    Mr F H Nicol U c Po in S t	43 4 note 1
Any ra valley	43 16 181
Arabs—	
Inva on of Ind a by	43 11 16
In populat on of Mahr	43 11
Records	43 170
Arab a interco rse of wtl Mahr n	43 9 46
Arab n Sea	43 9 3 8 1 53 71
Archaeolog cal Tu r    Wa r sta a d No U c Baluch	43 1 note 2 etc
And ty of cl mate n J l shwan etc ce Ra n f al n i Des ceation	
Arne Pa t d Sta    lgr Pot c f f on U c Fru ce of Ho a Cl ra	43    note 9 34 note 4
Arrian	43 11 5 f 82

Arro	Heads of stone see Stone imple-
nents	
Aryan c.	classification 43, 11-11
Ash lino nli n Kol a	43 110
Ashlogun bar tomb	43 29
As hal village	43 56
A aran tract and mo nd	43 81 10 17 18 93 13 127 138 141 144 145
Azul gal	see Zaraf of
Azul Kl n ei cf of Kl ran	43 7 99 102
B lor e	43 90 21 22 94 95 11
B drano lamb group of mo ls	43 7 f
Bagl ani alley	43 171 18 183
Bahr n shah place near Mat ne	43 188
Bal rver	43 7
Ba Kl Sindar help of	43 73
Ba ran dar field above Panjg r	43 41
B. fort & Dugé	43 17 190
B igatt rib en	43 9 7
Balo l Kl n	43 111
B la s o Oil Balor	
Bal ch tribes	43 141 24 95 41 110 183
Bal l Western la guage of	
ll r	43 7 14 17
Makr n	43 11 11 note 7
Hahn i	43 11 note 1
Sar v i	43 14 note
Bal et t n pars . cf	43 1 1 (note) 19 94 98 34 49 50 59 63 69 93 110 11 15 192
B p r .	43 10
Ba l or emulment see Gabar	
lamb and Dams	
Bangle see Clay Shell Copper	
land	
Bar lamb mound	43 180
Barle Makr n	43 9
Parr nes of I haran	43
B l plate n r Cw d r	43 3
B ~ r of Kabot	43 16
B ~ l l n and	43 1 f
Ba l	43 184

## Beads of—

Stone	43 33 44 88 95 96 121
Copper	43 65
Agate	43 96 124
Lapis lazuli	43 96 123
Onyx	43 96
Bone	43 97
Spinel	43 96
Glass	43, 175
Bedi hamlet in Awarin	43 171
Belar valley	43 177f
Beun chah halting place	43 18
Besma tract of Khārān mounds in	43, 29 30 32 35 47 129
Besham damb, debris area near Panjgur	43 45
Bibi Zinat tomb	43 38
Bird painted on pottery	43 51 187
Bird like head	43 37 156 162
Bird like vessel	43 87
Bit village in Buleda valley	43 56 88
Bit damb site in Baghwana	43 179
Branjan Sardars of Nal	43 128 129 136 136 169
Bel la damb mound	43 173
Bones examined	43 192 199
Boulders globular	43 142
Brāhī Khans of Kalat	43 10 note 4
Brahuis part of population of Jhal wan	43 7 11 12-15 12 note 1 20 21 30 35f 37 47 54 129 171 177 183
Bray Su Derays	43 6 note 1 11 note 7
Brendish Mr A F Survey of India Dept	43 16
Brecks—	
Burnt	43 60f 172
Mud	43 67 112 129 140 142 143 163 180 188
Sintered	43 54 96 97 110 117 142 143f 160
Bronze objects	43 75 88 94 158
Buddhist sites	43 121 125 185 188
Buddhist Earth Goddess	43 162
Buleda valley	43 56 88
Bull figure of in terracotta and on painted pottery	43 30, 70 91f, 94 96 97 112 120 122 123 124 125f 136 149 151 153 155 158 160 161 166 169
Burai and place on Bado river	43 27

Bundakli mound	43 184 185
Bunbir valley	43 20
Burial customs and deposits	43 4 20 25 60f 81f 87 93 98 98 103 119 123 127 149f 155f 163 169 175
Byzantine pottery in Egypt	43 28
Cairns funeral	43 34 75 74f 76 77f 80f 86f 119 149f 153 174
Carnelian bead	43 81
Caspian type of skull	43 199
Cities of Khān of Kalat	43 16 17 97 14f
Celadon like pottery	43 51
Central Asian explorations	43 2 5 131
Central Makran Range	43 9 10 48 52 105 128
Ceramics see Pottery	43
Chagai tract	43 6
Chaguls (water bags) of canvas	43 15
Chahi damb mound in Kolwa	43 115
Chalcolithic civilisation <i>passim</i> e.g.	43 4 18 28 33 39 49f 51 60f 63 65 67 81 91 etc
In Transcaspia Persia and Mesopotamia	43 5
Chapar valley	43 189
Clap jags	43 177
Clashma spring	43 181 185f
Cybal monuments for the dead	43 90 177
Cheri Makhr mound in Kolwa	43 115
Chert finds	43, 17 18 89 119 163 164 174 175 176
Chilbaghu valley	43 20
Child's skeleton	43 98 153 156 158
Chumri mound	43 171
China explorations in Central and Western	43 5
China ware fragment	43 108
Chinese porcelain in Kalat valley	43 55
Chori damb site Rakhsan	43 44
Chitkan village of Panjgur	43 42 44f
Chorrul damb ancient site near Panjgur	43, 45
Chronology lack of chronological con trol	43 4 12 15
Chronology of prehistoric mounds	43 70f
Chut river	43, 20
Cinerary pots (cf Burial customs)	43 65 66 87 97
Circumvallation (see also Wall)	43 23 49 54 90 109 129 146 148 163
Clay bangles	43 64 65 68, 92 136
Coastal trade	43 72

- Copper finds 43, 33, 34 64f 68 7, 76 81 89  
92 94 95 96 97 98 108 123 125 136  
141, 150 156 157 158
- Cotter Dr G de P., of Geological  
Survey of India 43, 191
- Crouching skeleton 43, 92
- Cultivation in—  
Daski valley 43 9 18  
Jhalawan 43, 13 170 175  
Bado valley 43 24 27  
Dasem 43, 30  
Rakhshan 43 36 43  
Parom basin 43 48 52  
Kej valley 43, 53 54 104  
on Makran Coast 43 74 83  
Kolwa 43, 106, 113f 118 128  
Awaran 43 131  
Nundara 43 132  
Lanjar 43 137  
Mashkan 43, 110, 117, 150 166  
Baghwana 43, 179  
' Culture stratum ' 43, 139 140  
Ourzon Lord 43 5  
Orrus his attempt to cross Gedrosia 43, 11  
Dabur-lof site of 43 33 65 112 126 146  
161  
Dakhma 43 82  
Dorman Kaur or Dumbani Kaur for  
rent 43 88 note 2  
Damb designation of mounds in Kalat  
state *qashm*  
Damb-i-shk (or Damba Kuli) site in  
Makran 43, 75 79 81 note 5  
Damb-i-Baid mound 43 131f  
Damb-i-dambi ridge above Panjgur 43 41f  
Dams (see also G. barlands) 43 20 21 58  
61 62 73 100 113 119 131 146 168 182  
Dandir fields in Kolwa 43, 111  
Darach kaur river 43, 131  
Darbar hall of Kharan kalat 43 27  
Dorman ban (Kuh-i-Kashu) site in  
Makran 43 7, 7  
Daski river and valley 43, 9 42 61 73 76 71  
70 82  
Daski river territory 43, 77 81 note 5  
Daski-Gorin plateau 43 17  
Daski-Murad area in Kalat 43 185  
Dye trees—  
in Kharan 43, 7  
in Makran 43 8
- Dedari saddle above Mashkan valley 43 115  
Defence 43, 24 62f 117 129 136 176  
Delwa in Persian dialect 43 11 note 7  
Delware tribe of 43 184 185  
Desecration problem of 43 2 41 132 186  
Dhul-ri river 43, 75  
Dhrum massif of 43 10  
Dilek site 43 8,  
Dil-Murad mound 43 11,  
Diodorus 43 82  
Diz Parom fort 43 48 52  
Dog figure 43 101  
Dolichocephalic skulls 43, 199  
Dorasha kaur tributary of Mashkan  
river 43, 1 8 129  
Draklo hamlet and basin 43, 173 176 177  
Drangana province of ancient Iran 43 7  
Dravidian language of Brahuis 43 13  
Drug spring 43 70  
Drums of stone 43, 67  
Egyptian lotus motif 43 124  
Elhot Sir H. V. 43 10 note 4 16 note 4  
Embanli ruins see dams Galur  
banks  
Emigration from Kharan 43 7  
Ekap on Kej river 43 101 10  
Excavation of hill slope 43 8  
Ethnic relations (see also Population) 43 1 11  
18f  
Extent of—  
Kharan Makran Jhalawan 43 5  
Kalat 43 1  
Makran 43 7  
Female figure see Goddess  
Firoz Khan-dani mound near Wala  
7 43 130f 131  
Fish mended figure of 43 17  
Fishing 43 8 9 71 72 76f  
Flints see Stone implements  
Floods 43 9 22f 27 30 37 177 71 74  
106 107 111 125 130 17 140 14 154  
152 173 161  
Fort see Defence Diz Parom  
Fort House of 43 96  
Funerary pits see Cinerary pits  
Galur finds stone dams 43 7 24 45 115f  
117 118 125 141 150 164 165 170 177,  
183f  
Gallies 43 47  
Galler Mr., information of 43 1

- Gedrosia *Gedrosia* see *Gedrosia*  
 Gajar village in Mashkan 43, 150 152  
 Gandhara 43, 2  
 Ganz village 43, 73 77  
 Gar Levy Post 43, 47 50  
 Garro-Ioh coastal range 43 72  
 Garuk river and valley 43, 26 28f 29  
 Gat pass 43, 109 132f  
 Gat haat gorge near Gat pass 43, 132 140  
 Gate well 43 108  
 Gate dap mound in Kohwa 43 108f  
 Gutti hamlet near Gwadar 43, 71f 119  
 Gedrosia ancient name of part of Ka  
   lat Site 43, 1f 11 34 37f 82 183  
 Gen damh 43 173  
 Geographical observations 43 2 15 34  
 Ghaznak mound in Kej 43 101  
 Ghaz kaur river 43 21  
 Ghazni town in Afghanistan 43 14  
 Gichki families 43 11 53 54 84  
 Gidar Dhor or Dor river 43 18 160 169  
 Glass bangle 43 34 55 63 93 94 108 111  
   123 125  
 Glazed ware see Pottery  
 Gubur hamlet 43, 83  
 Goldsee terracotta figurine or 43 37 70 120  
   123f 151 153 155 156 158 160 161f 166  
 Golprosh hill cl a n 43, 9 83 88 89  
 Gold finds 43 126 131  
 Gramkan village 43 45  
 Grownak fort 43 10 15f  
 Greshuk villey 43, 13 note 4 163f 178  
 Gunking stone 43, 121 123 124 160  
 Gumbaz damh site in Jhalawan 43 170  
 Gumbaz domed tomb 43 26 28 73 172 177  
 Gupta Mr R A 43 173  
   Gurich (north gate) 43, 75 82 112 117 165  
 Gushanak village in Kohwa 43, 111 113 117f  
   120  
 Gushatung village 43 53  
 Gwadar port 43 9 56 71 77 132 180  
 Gwani valley 43 165  
 Gwani kalat mound in Gwani 43 165  
 Gwargo river 43, 47  
 Gwarjak hamlet in Mashkan 43 148 149f  
 Gwattar or Gwatar bay 43, 9 71 75 77 81  
   note 5 82  
 Gwetank place on Jal river 43, 21  
 Hab river in Jhalawan 43, 12
- Habibullah Khan Nawab Chief of Kharan 43 3 27  
 Hadiri plateau on Dado river 43, 27  
 Half-brick site in Dasht 43, 58  
 Hair pin copper 43 157 158  
 Haj Abdullah damh 43 177  
 Haj Muhammad damh mound in  
   Bafur 43 177f  
 H b d. m. mound in Nal 43 169  
 Hamal damh mound in Nal 43 169  
   Hamun (terminal depression) 43 6 179  
 Haappa prehistoric site 43, 1 1f 14  
 Hargreaves Mr H 43 1 4 40, 70 123 163  
   166f 171 187 188f  
 Hassan damh mound 43 177  
 Hellensie—  
   Motis 43 81  
   Earth Goddess 43 102  
 Helmand valley 43, 7 11 31 69  
 Herat town 43 89  
 Hindu Tirtha 43 187  
 Hingol river in Jhalawan 43, 12 36 52 106  
   127 130  
 Hobson Mr R D of British Museum 43 131  
 Hor lalet mound 43 111f  
 Hor Nighwor hamlet in Dasht 43 60  
 Horse—  
   Terracotta figurine or 43 34  
   Figure of on painted ware 43 31  
   Head of in earus 43 83  
 Hoshab place in Kej valley 43, 52 104 105f  
   107  
 Hughes Buller R 43 6 note 1 10 11 note  
   7 45 note 4 48 note 1 56 note 7 114 172  
 Human body—  
   Buried 43, 93 95 121 149  
   Cre mated 43 155  
 Hats of palm matting 43, 9  
 Hea on painted pottery 43, 27, 160 165 122,  
   124 143  
 Ikthyophagor 43, 3 71 76 82  
 Inavat Shah damh 43, 179  
 Indo Iraman border lands 43, 1 16 69  
 Indo-Scythian bronze coin 43, 187  
 Indus valley see Sind, and Prehistoric  
   Civilisation  
 Inlay 43, 44

- Inner most Asia* 43 4 note 1 16 28 note 7  
 32 note 2 50 note 2 55 note 4 64 note 5  
 67 note 6 91 note 3 131 note 1  
*Inscription Arabic* 42, 178  
*Intercourse of Makran and Arabia* 43 9  
  
*Iran—*  
     *Prehistoric sites of* 43 1 5  
     *Connexion with Kharan* 43 7 27  
*Iranian languages* 43 14  
*Iron objects* 43, 81 56 88 111 188  
*Irrigation (see also Gabarbands Ka-  
 rezes and Rainfall)* 43 6 8 9 10 19f 17  
 24 27 29 77 49f 53 106 111 139 137  
 115f 150 152 171 173 181 183 184 189  
*Isai Kalat village* 43 43  
*Jabal-i-Mahdi hill* 43 74  
*Jadgals part of population of Makran* 43 11  
 15 112  
*Jai-damb mound in Kharan* 43 49f 50  
*Jal river and pass* 43 40 41  
*Jalkand pass* 43 41  
*James Colonel E H S help of* 43 15  
*Jamut Ru R B Diwan* 43 6 not la 189  
 note 10  
*Jangal rest house* 43 39  
*Jaren hamlet in Kolwa* 43 112  
*Jat see Jadgal*  
*Jaur pass and spring* 43 161 162  
*Jawarji hamlet* 43 160  
*Jawarji-damb mound in Gushak* 43 162  
*Jehr village in Washkan* 43 148 153 163f  
*Jhalawan part of Kalat state* 43 2 3 4f 7  
 12 15 17 19 25 35 40 87 101 10 113  
 127 132 135 141 160 170 189  
*Jhalawan ranges* 43 12  
*Jhau tract* 43 110 127 132 135 138 141  
 161 170  
*Jiwanra* 43 9 56 71f 75 77 82 85 87f 135  
 150 153 164 169 188 189  
*Jungle trees* 43 136  
*Jur hills* 43, 30  
*Kabul* 43 14  
*Kachhi tract below Sarawa* 43 13  
  
*Kahwal —*  
     *river* 43 150 172  
     *Site* 43 171  
*Kalwa damb mound at Gajar* 43 159  
*Kalat capital of Kalat* 43, 12 16 18 40 183f  
*Kalat State pass*
- Kalouk village near Turbat* 43 56 85 86  
*Kalat-i-damb mound near Nag* 43 37f  
*Kahmullah Khan Deputy Wazir of S  
 Jhalawan* 43 178  
*Kallag mound in Kolwa* 43 111f 117  
*Kalka dry flood bed* 43 8  
*Kamar band mound in Kolwa* 43 115  
*Karabar damb mound* 43 1 9f 131 137  
*Kamlaro damb in Awaran* 43 141  
*Kambar-sher portion of Sordaur*  
     *also name for Zingun damb q* 43 86  
*Kanarpur Arab name for Panjgur?* 43 46  
*Kanazbi Arab name for Panjgur?* 43 46  
*Kand hamlet* 43 171  
*Kandahar* 43 13 14 180 187  
*Kan valley* 43 75  
*Kap salt marsh* 43 48 1 5 106 110 149  
*Kapran pass* 43 12  
*Kar depression in Baluchistan valley* 43 178f  
*Karachi* 43 17 1 9  
*Karagi ste* 43 84  
*Karam Shah damb* 43 131  
*Karezes subterraneous canals* 43 8 10 1 14  
 18 27 30 31 32 12f 43 4 5 63 4  
 80 84 104 146 151 152 163 166 175  
 176 181 184 185 186  
*Kargishk damb site in Rakhsan  
 valley* 43 36 37 186 1 107  
*Karimdad gait hill* 43 177  
*Karol flooded* 43 102  
*Karano-damb site* 43 85  
*Kashmala ib mound in Basra* 43 1  
*Kashmala ib mound in Wadh* 43 176  
*Katagias* 43 5  
*Katash pass in Zayak* 43 6 1  
*Kaulam prehistoric site of* 43 126  
*Kind h chiefs* 43 111  
*Kauli (Kat-Khudi) Baluch head  
 man* 43 1  
*Kaurjo canal for irrigation* 43 8 1  
*Keith Sir A on paleolithic and ne  
 lithic skulls* 43 16  
*Koj river and valley* 43 7 8f 9 10 1  
 11 13 71 87 86 105 11 17  
*Koj Makran river given to Makran* 43 8 4  
*Komaror Maran Iolo son of  
 Koj Makran* 43 8 1  
*Koya Colonel T H Field of 14 15 16  
 17  
 18  
 19  
 20  
 21  
 22  
 23  
 24  
 25  
 26  
 27  
 28  
 29  
 30  
 31  
 32  
 33  
 34  
 35  
 36  
 37  
 38  
 39  
 40  
 41  
 42  
 43  
 44  
 45  
 46  
 47  
 48  
 49  
 50  
 51  
 52  
 53  
 54  
 55  
 56  
 57  
 58  
 59  
 60  
 61  
 62  
 63  
 64  
 65  
 66  
 67  
 68  
 69  
 70  
 71  
 72  
 73  
 74  
 75  
 76  
 77  
 78  
 79  
 80  
 81  
 82  
 83  
 84  
 85  
 86  
 87  
 88  
 89  
 90  
 91  
 92  
 93  
 94  
 95  
 96  
 97  
 98  
 99  
 100  
 101  
 102  
 103  
 104  
 105  
 106  
 107  
 108  
 109  
 110  
 111  
 112  
 113  
 114  
 115  
 116  
 117  
 118  
 119  
 120  
 121  
 122  
 123  
 124  
 125  
 126  
 127  
 128  
 129  
 130  
 131  
 132  
 133  
 134  
 135  
 136  
 137  
 138  
 139  
 140  
 141  
 142  
 143  
 144  
 145  
 146  
 147  
 148  
 149  
 150  
 151  
 152  
 153  
 154  
 155  
 156  
 157  
 158  
 159  
 160  
 161  
 162  
 163  
 164  
 165  
 166  
 167  
 168  
 169  
 170  
 171  
 172  
 173  
 174  
 175  
 176  
 177  
 178  
 179  
 180  
 181  
 182  
 183  
 184  
 185  
 186  
 187  
 188  
 189  
 190  
 191  
 192  
 193  
 194  
 195  
 196  
 197  
 198  
 199  
 200  
 201  
 202  
 203  
 204  
 205  
 206  
 207  
 208  
 209  
 210  
 211  
 212  
 213  
 214  
 215  
 216  
 217  
 218  
 219  
 220  
 221  
 222  
 223  
 224  
 225  
 226  
 227  
 228  
 229  
 230  
 231  
 232  
 233  
 234  
 235  
 236  
 237  
 238  
 239  
 240  
 241  
 242  
 243  
 244  
 245  
 246  
 247  
 248  
 249  
 250  
 251  
 252  
 253  
 254  
 255  
 256  
 257  
 258  
 259  
 260  
 261  
 262  
 263  
 264  
 265  
 266  
 267  
 268  
 269  
 270  
 271  
 272  
 273  
 274  
 275  
 276  
 277  
 278  
 279  
 280  
 281  
 282  
 283  
 284  
 285  
 286  
 287  
 288  
 289  
 290  
 291  
 292  
 293  
 294  
 295  
 296  
 297  
 298  
 299  
 300  
 301  
 302  
 303  
 304  
 305  
 306  
 307  
 308  
 309  
 310  
 311  
 312  
 313  
 314  
 315  
 316  
 317  
 318  
 319  
 320  
 321  
 322  
 323  
 324  
 325  
 326  
 327  
 328  
 329  
 330  
 331  
 332  
 333  
 334  
 335  
 336  
 337  
 338  
 339  
 340  
 341  
 342  
 343  
 344  
 345  
 346  
 347  
 348  
 349  
 350  
 351  
 352  
 353  
 354  
 355  
 356  
 357  
 358  
 359  
 360  
 361  
 362  
 363  
 364  
 365  
 366  
 367  
 368  
 369  
 370  
 371  
 372  
 373  
 374  
 375  
 376  
 377  
 378  
 379  
 380  
 381  
 382  
 383  
 384  
 385  
 386  
 387  
 388  
 389  
 390  
 391  
 392  
 393  
 394  
 395  
 396  
 397  
 398  
 399  
 400  
 401  
 402  
 403  
 404  
 405  
 406  
 407  
 408  
 409  
 410  
 411  
 412  
 413  
 414  
 415  
 416  
 417  
 418  
 419  
 420  
 421  
 422  
 423  
 424  
 425  
 426  
 427  
 428  
 429  
 430  
 431  
 432  
 433  
 434  
 435  
 436  
 437  
 438  
 439  
 440  
 441  
 442  
 443  
 444  
 445  
 446  
 447  
 448  
 449  
 450  
 451  
 452  
 453  
 454  
 455  
 456  
 457  
 458  
 459  
 460  
 461  
 462  
 463  
 464  
 465  
 466  
 467  
 468  
 469  
 470  
 471  
 472  
 473  
 474  
 475  
 476  
 477  
 478  
 479  
 480  
 481  
 482  
 483  
 484  
 485  
 486  
 487  
 488  
 489  
 490  
 491  
 492  
 493  
 494  
 495  
 496  
 497  
 498  
 499  
 500  
 501  
 502  
 503  
 504  
 505  
 506  
 507  
 508  
 509  
 510  
 511  
 512  
 513  
 514  
 515  
 516  
 517  
 518  
 519  
 520  
 521  
 522  
 523  
 524  
 525  
 526  
 527  
 528  
 529  
 530  
 531  
 532  
 533  
 534  
 535  
 536  
 537  
 538  
 539  
 540  
 541  
 542  
 543  
 544  
 545  
 546  
 547  
 548  
 549  
 550  
 551  
 552  
 553  
 554  
 555  
 556  
 557  
 558  
 559  
 560  
 561  
 562  
 563  
 564  
 565  
 566  
 567  
 568  
 569  
 570  
 571  
 572  
 573  
 574  
 575  
 576  
 577  
 578  
 579  
 580  
 581  
 582  
 583  
 584  
 585  
 586  
 587  
 588  
 589  
 590  
 591  
 592  
 593  
 594  
 595  
 596  
 597  
 598  
 599  
 600  
 601  
 602  
 603  
 604  
 605  
 606  
 607  
 608  
 609  
 610  
 611  
 612  
 613  
 614  
 615  
 616  
 617  
 618  
 619  
 620  
 621  
 622  
 623  
 624  
 625  
 626  
 627  
 628  
 629  
 630  
 631  
 632  
 633  
 634  
 635  
 636  
 637  
 638  
 639  
 640  
 641  
 642  
 643  
 644  
 645  
 646  
 647  
 648  
 649  
 650  
 651  
 652  
 653  
 654  
 655  
 656  
 657  
 658  
 659  
 660  
 661  
 662  
 663  
 664  
 665  
 666  
 667  
 668  
 669  
 670  
 671  
 672  
 673  
 674  
 675  
 676  
 677  
 678  
 679  
 680  
 681  
 682  
 683  
 684  
 685  
 686  
 687  
 688  
 689  
 690  
 691  
 692  
 693  
 694  
 695  
 696  
 697  
 698  
 699  
 700  
 701  
 702  
 703  
 704  
 705  
 706  
 707  
 708  
 709  
 710  
 711  
 712  
 713  
 714  
 715  
 716  
 717  
 718  
 719  
 720  
 721  
 722  
 723  
 724  
 725  
 726  
 727  
 728  
 729  
 730  
 731  
 732  
 733  
 734  
 735  
 736  
 737  
 738  
 739  
 740  
 741  
 742  
 743  
 744  
 745  
 746  
 747  
 748  
 749  
 750  
 751  
 752  
 753  
 754  
 755  
 756  
 757  
 758  
 759  
 760  
 761  
 762  
 763  
 764  
 765  
 766  
 767  
 768  
 769  
 770  
 771  
 772  
 773  
 774  
 775  
 776  
 777  
 778  
 779  
 780  
 781  
 782  
 783  
 784  
 785  
 786  
 787  
 788  
 789  
 790  
 791  
 792  
 793  
 794  
 795  
 796  
 797  
 798  
 799  
 800  
 801  
 802  
 803  
 804  
 805  
 806  
 807  
 808  
 809  
 810  
 811  
 812  
 813  
 814  
 815  
 816  
 817  
 818  
 819  
 820  
 821  
 822  
 823  
 824  
 825  
 826  
 827  
 828  
 829  
 830  
 831  
 832  
 833  
 834  
 835  
 836  
 837  
 838  
 839  
 840  
 841  
 842  
 843  
 844  
 845  
 846  
 847  
 848  
 849  
 850  
 851  
 852  
 853  
 854  
 855  
 856  
 857  
 858  
 859  
 860  
 861  
 862  
 863  
 864  
 865  
 866  
 867  
 868  
 869  
 870  
 871  
 872  
 873  
 874  
 875  
 876  
 877  
 878  
 879  
 880  
 881  
 882  
 883  
 884  
 885  
 886  
 887  
 888  
 889  
 890  
 891  
 892  
 893  
 894  
 895  
 896  
 897  
 898  
 899  
 900  
 901  
 902  
 903  
 904  
 905  
 906  
 907  
 908  
 909  
 910  
 911  
 912  
 913  
 914  
 915  
 916  
 917  
 918  
 919  
 920  
 921  
 922  
 923  
 924  
 925  
 926  
 927  
 928  
 929  
 930  
 931  
 932  
 933  
 934  
 935  
 936  
 937  
 938  
 939  
 940  
 941  
 942  
 943  
 944  
 945  
 946  
 947  
 948  
 949  
 950  
 951  
 952  
 953  
 954  
 955  
 956  
 957  
 958  
 959  
 960  
 961  
 962  
 963  
 964  
 965  
 966  
 967  
 968  
 969  
 970  
 971  
 972  
 973  
 974  
 975  
 976  
 977  
 978  
 979  
 980  
 981  
 982  
 983  
 984  
 985  
 986  
 987  
 988  
 989  
 990  
 991  
 992  
 993  
 994  
 995  
 996  
 997  
 998  
 999  
 1000*



- Kharan part of Kalat State 43 2 3 5 7 10  
     14 15 20 25 35 37 etc etc  
     remains in Kharan 43 15 34 141  
 Kharan kalat chief village of Khara 43 7 97f  
 Khotan 43 21  
 Khozdar tract of Jhalavan 43 13 17 114  
     169 170 1 8 179  
 Khudabadan mound 43 45f  
 Khushkaba (dry water) cutaya  
     on 43 19 30 32 35 36 38 42 18 51  
     58 61 83 105 150 151 153 164 168  
     175 176 178 181 183 186  
 Khwaja Zabarh lock 43 183  
 Kinshpagnate 43 15  
 Kuman province of Persia and pass  
     of 43 10 123  
 Kiss darab site in Baghiana 43 179  
 Korhabut site 43 17  
 Kohak fort in Dasht 43 38  
 Kohak kalat 43 83  
 Koh Pidak hill chain in Kharan 43 20  
 Kohna kalat mound in Panjgur 43 46  
     5 84  
 Kowabasan 43 8 9 25 70 99 100 10  
     102 104 107 108 129 132 170  
 Korakan river 43 90 23  
 Koshekalat, village 43 88  
 Kuddian village in Dasht 43 33  
 Kufic inscription 43 178  
 Kuhak tract 43 46  
 Kuh Kashu 43 5  
 Kuki damb mound 43 1 f  
 Kuchik river 43 170  
 Kulanch valley 43 8  
 Kull mound 43 92 105 118 128 131 136  
     41 114 150 151 153 156 160 162  
     165 166 1 4  
 Kullalat mound 43 186  
 Kunda terrace near Jal river 43 90  
 Kununange 43 21  
 Kurragi damb mound in Kharan 43 30f  
 Kurram river 43 1  
 Kuuzkol mound in Parom 43 50  
 Labach hamlet 43 129  
 Ladder probably used for entrance to  
     dwelling 43 124f  
 Lagherzard site in Nul 43 169  
 Lak plateau 43 77 82  
 Lak hill above Mashka valley 43 152  
 Lakman pass 43 181 183  
 Lalas bones of 43 96  
 Lanidamb mound 43 180  
 Langage and race 43 14 note 6 and 7 15  
 Lannar portion of Jhau 43 137 139  
 Lash State 43 10 11 12 132 1 3 136  
     137 165 173 1 6 179  
 Lee Pearson formula 43 195  
 Lefmound in Nal 43 169  
 Leopards on painted pottery 43 114  
 Lowlwood Captain R. G. 43 1 note 2  
 Londo Yamet 43 1 9 181  
 Lep desert in Central Asia 43 18 113 130  
 Lorpelutomic mounds of 43 23 31 35f  
     37 41 59 65 1 92 100 108 109 190  
     12 155 1 9 180  
 McCrindle Mr 43 82 note 6  
 Macgregor Wundengs Balochistan 43 71  
     note 17  
 Maclean damb mound in Dasht 43 59  
 Mackay Mr E. 43 44 note 3  
 Madak kalat mound and Zaran  
     Kol 43 111  
 Ma Masura Muhammadan tomb 43 180  
 Maibhu valley 43 164  
 Makaur gorge of 43 135  
 Makran  
     part of Baluchistan pass eg 43 2 3 4f  
     10 13 15 16 19 28f 35 3 41 40 52  
     1 etc  
     history of 43 10f  
     remains on Makran Coast 43 1 86  
 Makran Coast Range 43 8 56 106  
 Malabar Coast trade with 43 2  
 Malir area in Kol 43 113f 116 118 145  
     1 4  
 Malasband site in Mashka 43 118 150  
 Malgher damb mound 43 185  
 Milguzer village 43 184  
 Mahls of—  
     Makran 43 43  
     Seton 43 26  
 Mail area near Bennchal 43 18  
 Malta megaliths of 43 174  
 Mamma damb mound in Kharan 43 30  
 Mand fort 43 8 note 3 9 84-84  
 Mandeha group of hamlets 43 186  
 Maps published by the Survey of India 43 6  
     and 6 note 2  
 Maristan 43 107

Marble grinding stone	43 124
Marco Polo o Makran	43 8 note 7
Mar ch basin	43 106 113
Marsha Sr John support of	43 1 2 16 186 189
Mashka river and valley	43 31 50 6 64 9 100 101 106 10 113 114 11 127 128 130 131 13 144-1 0 1 1
Masi kai ver and bas	43 3 10 16
Masso C	43 13 171 1 3 182 note 7
Ma tung cas s	43 16 184 196 187 189
May lchal wal	43 40
Mazen damb mound n Mashka	43 118
Meeredy Colonel H R A	43 15
M ds among population of Gwal ar	43 0 note 1
Meh ste n Mashka	43 92 107 141 144 103 154-16 168 1 4
Men ham et near Gajar	43 101
Men damb mound in Gajar	53 06
Mengal t be m Wadh	43 1 0
Mesopotam a	43 1 14 2
Manar v Nage	43 88
Minch n Major C T Khan an	43 6 note 1a
Mir east e near Turbat	43 4f 83
Mir but s te of Khozdar	43 1 1f
Mi or of copper	43 10 1 8
Mir Shams Shah Nawab Sr War	43 3
Arum of Kalat	43 3
Mirra r family	43 112 117 120 129 101 149 160 180 189
Mocker Major D	43 56 60-71 4f 8 81 note 3
Mog also eragaty	43 10
Mogh lghunda in Zhob valley	43 34 3 66 67 C M 4f 81f 86 8 f 101 110 130 149 160 180 189
Mol enjo daro prel ust or s te in Sund	43 1 4f 11 1 0 19 194
Mother goddess see Godde s	43
Motor tracks	43 3 10 16 1 29 32 46 0 106 11 140 16 1 0 1 6 150

## Mounds p e g —

n Kalat	43 1 f 19
n Kl r n	43 30 34
n Rak h	43 3 40
P om	43 10
u I j	43 33 36 86 103
in Da ht	43 36 1

Mounds p e g —	
on M kra Co t	43 1 86
n Ho a	43 104 1
n Nund r and Jha	43 12 144
n M lka	43 141 1 0
n Central Jha awan and So w	43 1 0 189
Mud pas e	43 1
M lah j l ee Ba kwana	43 181
Muhammad Hasan West f of M kr	43 3
Muhammad K la G hl	43 0
Mulamma l Khan Mengal R all	43 f
Mul m m d Khan S rdar of B jo	43 1 0 80
Muh n nadan and Muh an m lan re	
mans	43 2 32 4 16 170 1 8 15 189
Muhammudan gra es	43 26f 28 20 38 11 61 f 101 120 101 1 1 6 18
Mu gach r tract	43 16 186
M ga chauk atch post n Ma h	43 11 f
Mungah alat h mlet in Ma h a	43 11
Mun r lge	43 1
Mu ad Khan V b of Be ma an l	
Rakl han	43
M ca Khan Miranr	43 134 134
Musl at state of	43 0
Muskat Sultans of	43
Nag village and r er	43 3 36f 1 10
Nal p chs or s te n	43 1 13 note 1 4 40f 0 9 102 143 63 166 1 0 100 194 19 199
Nu r a d n er	43 131 1 3 1 8 16 160 160 1 0 1 8
Nal t pe of p nted potte	43 0 0 102 103 108f 110 111 110 110 118 1 0 1 128 129 130 131 131 13 36 110 141 143 144 148 1 1 160 163 164 16 1 1 1 4 1 6 1 18
Nu r ba l	43 0 8 f
Netw n ham l t	43 1

## Nauroz lal t —

o s s n Kl ran	43 191f 21f
in t el	43 0
Nu r o Kl n	43 0
Nu l r o r l ing f m l in h n	43 0 3 111 1 0
Nazan d d lla	43 8 8 11
Ne lo gen r l of N x n l	43 11 1
N klace of on x	43 6 1 1 0

## See also of—

copper	43, 65 68 108
bone	43 123
Neghar village	43 19
Nabat of Turbat	43, 8
Nking tributary of Kej river	43 8 9 82f
Nokjo Gazarai village near Gajar	43, 152
Nokjo Shahdunzar village near Gajar	43 152f
Nordic type of skull	43, 199
Nulani hamlet	43, 179
Nundara valley	43, 132 131 137 145
Nundara site see Siakh damb	
Nuruddin Mengal Sirdar	43 175 176
Nushli locality	43, 12 18 22 25
Oases of Panjgur (cf Panjgur)	43, 10
Old Balor mound in Kolwa	43, 110 135
Oman coast	43, 123
Onyx head	43, 63 96 124 125
Oritai tribe custom and territory of	43 82 137
Ormara harbour	43, 111
Pak mound	43, 107 108 109
Panjgur oases in Makran	43, 16 17 29 32 41 46 52 53 56 60 104 111 128
Panju damb site in Wadh	43 175
Panodi hamlet and mound in Dasht	43 59
Panthers on painted pottery	43, 144
Pardan damb remains of old embankment	43, 45
Parom basin	43 9 35 46 52 55 64 80 108
Parthian coin	43 81
Pasao kaur flood bed	43 75
Pashto language	43, 14 note 7
Pasni roadstead	43, 8 72 75 86f 104
Pasu bandar	43 71
Patakin well	43, 30f
Pathans	43 14 15
Pax Britannica	43 35
Pelar place in Jhau	43, 138
Periano ghundai site in Zhob	43 31, 37 50 64 66 67 69f 84 91, 93 96 101 102 126 144 156 159 188
Persia	43 10 11 16 35 46 51 52 55 131 170 185
Persian Gulf	43, 11 60 71
Peshwar valley	43, 121 125
Pier like wall	43 139f
Pigs snout in terracotta	43 110
Pillar	43, 142
Pipil Lalat mound near Panjgur	43 47

Pipish hill chain	43, 48
Pir Ahzu prehistoric mound of	43, 36 note 4
Pirandar hamlet	43, 131
Pir, resting place of a	43, 21 26 27 37 47
Pish valley	43 132
Pishul water hole in Makran	43, 72
Pishin tract	43, 12, 36 59 83 109, 170 172 180
Pishukan hamlet	43, 75
Pistachio trees	43, 20
Plants on painted pottery	43, 122 128 141 155 159

## Population of—

Kharan Makran and Jhalawan	43, 5
Kharan	43, 7 30
Makran	43, 7f 9 11
Rakhshan valley	43 10
Jhalawan	43, 12 14
Jhau and Nundara	43, 137
Nal valley	43, 166
Mastung	43, 189 note 10
Porali river in Jhalawan	43 12 82 173 175 176f
Portuguese construction	43, 74

## Pottery—

Plain	43, 17 18 19 22ff 28 29 30f 33f 33f 37f 42 43 45 17 49f 51 53f 59, 61 64ff 67f 74f 76 78ff 84f 86 87f 89ff 93ff 98 103 104 105 107f 110 115 119 122 123 125 128 129 131 132 133f 136 137 140 145 147 148f 150ff 154ff 163f 167ff 170ff 179 etc
Painted	43, 17 23f 28 29 31f 33 33f 37f 39f 44 45 49f 51 55f 59 64ff 79f 83 84f 87 91 93ff 98-103 105, 107f 109 112 115 117 118 120 122 123 124f 128-131 133f 135 138 140 143 144 146 147 148f 150ff 154ff 163f 165 167ff 170ff 174 etc
Mark-marked	43, 24 28 45 59 100 101 115 169
Pottenger Lieutenant (later Sir Henry) on remains in Kharan	43, 18 21ff 23f
Pozhoi damb mound in Besema	43 32
Pre Aryan civilisation	43, 11 14 92 161
Prehistoric civilisation of Indus valley	43 1 14 192
Pumpelly expedition in Transcaspiia	43 5
Punjab	43, 14
Quetta	43, 12 15f 184 186 189
Quetta Museum pottery in	43 4

- Radhan damh mound 43 180  
 Rainfall 43, 8 9 10 12 17 18 19 25 30  
     30 36 38 57 58 59 71 73f 84 106 109  
     114 119 128 145 148 160 162 164 168  
     170 178  
 Raja Gira's Castle in Swat 43 116  
 Rakhshan river and valley 43, 3 9f 17 29  
     35 52  
 Ram Chand Bah Pandit help of 43 16  
 Ram's head in terracotta 43, 110, 137, 161  
 Rana ghundai ancient site 43, 36  
 Rao Dr Srivasa of Zoological  
     Survey of India 43, 192  
 Raskoh range 43, 6 9f 27  
 Reghai tract 43 35  
 Rukm place on Mashkar river 43 128  
 Rukh basin 43 176  
 Rul tribe 43 179 180  
 Rodhap village 43 17 18 183 185 186  
 Rodhan mound 43 169f  
 Roman pottery in Egypt 43 28  
 Ross Sir Demson 43 178  
 Rubble-built walls 43 23 27 30 33 36  
     135 181  
 Ruby bead 43 96  
 Rudhan see Rodhan  
 Runjan site above Jebri 43 164  
 Rustam Khan Sirdar of Jebri 43, 161 151  
 Safed bulandi (Spet bulandi q v)  
 Sakar kahit mound in Kolwa 43 111  
 Sayid Maur z damh mound 43 186  
 Sapid damh mound in Beema 43 31  
 Sapid range 43, 53 59 72  
 Sapilaur drainage bed in Beema 43 32  
 Saka kalat mound in Greshah 43 165f  
 Silt marshes 43, 9 42 179  
 Sindh n mound 43, 186  
 Sindh valley 43 173  
 Samarkand pottery 43 171  
 Sam Hurok oases of 43 8 note 3 59  
     105  
 Samir land mound 43 187 188  
 Sangar type of towers 43 61  
 Sangar damh mound 43 180  
 Sarawin portion of Kalat State 43 1<sup>st</sup> note 1  
     13 16 170 183  
 Sarbaz river 43 10  
 Sarhad site in Central Asia 43 131 137  
 Sarhad province in Persia 43 6  
 Sar damh mound in Rakhshan 43, 44  
 Sar Parom W part of Parom basin 43, 48  
     note 1 49 50f 52  
 Schmidt H *Prähistorisches aus Or-*  
     *assen* 43 f note 5  
 Script—  
     of Harappa and Mohenjo-daro seals 43 1 14  
     Sumerian 43 1  
 Seals of—  
     copper 43 48  
     bone 43 159  
 Seals prehistoric from Indus sites 43 1 14  
 Segak mound on S Kolwa route 43 109  
 Semiramis attempt of to cross Gedrosia 43 11  
 Serloran village of Panjgur 43 17f 44  
 Shadinza village 43, 150 159 161 162  
 Shal tumh mound in Kej 43, 54 63 69f  
     85 88 103 105 107f 112 116 120 122  
     123 126f 130 141 143 144 153 166  
     167f 168  
 Shal rug village in Turbat 43 52  
 Shakar Khan Mengal leader 43 175  
 Shakar Khan damh mound near Nal  
     village 43 168  
 Sham damh mound in Khan a 43 51 55  
 Shank branch of Nal river 43 130 137  
 Shan damh mound in Nal 43 166f  
 Sheep's or goats jaw bone 43 93  
 Sheep's leg 43 192  
 Shell handle 43 63 65 66 68 72  
 Shell —  
     *Melanoidea t. bore latas* (Müller) 43 191  
     *Valva* genus 43 192  
     *Natica a. M.* (Reeve) 43 192  
 Shinnal river 43 186  
 Shiroza district 43 9  
 Shal range 43 6 10 46  
 Shal-dun site in Nundara 43 136f 138 144  
     161f  
 Shah damh site in Thau 43 13 f 1 17f  
     163 161 162  
 Shikand valley 43 20  
 Shikand ornament on pottery 43 54 55 1  
     104 120  
 Silt deposit 43 67  
 Silver objects 43 81 15  
     Sindh and Nal The Lament of 43 11  
     1 17  
 Sind river and valley (cf. also prehistoric  
     and modern) 43 7 10 11 12 14 15 17 71,  
     82 105 17 181 1 2

- Sing kulit ridge 43 37f 116f
- Sino damh see Bft-damh
- Sistan 43 4 6 7 10 18 26 2 28 37 34  
44 49f 51 55 64 67 69 91 93 103 190  
192 120 101 1 9 187
- Sivas bull 43 92 161
- Skeleton see Human body and Skull
- Skills (see also Human body) 43 106 153  
191 199
- Smith Captain D R Makran etc 43 41f
- Sohr damh mound in Mashkan above  
Tan' river 43 146
- Sohr amb 'al burial ground 43 70 143  
166f
- Sohron damh mound near Awaran 43 131  
13 160 1 2
- Sohron damh mound in Mashkan 43 149
- Sorab river 43 86f
- Sorak karot 43 176
- Sorgar village 43 171
- Spate see Flood
- Spet buland mound 43 187f
- Spet-damh two mounds of same name  
both in Jhan 43 110 135f 164 168  
177 180
- Spindle whorl 43 120
- Sraduk date grove at Panjgur 43 45
- St John Hon ble Colonel H B 43 189
- Stone cups vessels 43 50 63
- Stone—  
implements 43 63 6 68 69 92 96  
104 163 165  
absence of 43 197 167
- Stone structures remains of ancient in—  
Kelva 43 5 105 107 108 110 112 115  
116 119 190f 126 130
- Besema 43 31
- Zay'd 43 32 31
- Rakhshan 43 36 33 45
- Kuj 43 54f
- Suktagen dor 43 65 67
- Jw nri 43 77
- Sh hi tump 43 88 96
- Nandara 43 133 139 141 144
- Jlail 43 135
- Mahla 43 146 148 101 107 154 160  
164
- Jhalawan 43 144
- Walth 43 176 177
- Kalat 43 186
- Stratigraphic evidence 43 4 39 70 141  
144 154
- Stronghold see Castle
- Su bashus of Chinese Turkestan 43 185
- Siltagan dor site near Santsar 43 56 59  
60 71 82 85 89 93 95 101 102 105  
108 129f 125 130 141 144 150 155 163  
188
- Sultan Khan Naib 43 29
- Sumerian script 43 1
- Sunari damh site in Mashkan 43 31 164 165  
168 169 177 180 185 186
- Suntsar Levy post 43 56 60 71 32f
- Sirab locality 43 16f 18f 21 92 37 183
- Surjungal 43 31 37 69 125
- Surkh village 43 19
- Surkh damh mound 43 19
- Susa—  
explorations at 43 5  
pottery of 43 99
- Svastika 43 100 101 103
- Swat valley 43 116 121 125 187
- Sykes Sir Percy 43 11 note 7
- Taghan damh mound in Besma 43 31f
- Tale dap valley 43 76f
- Tal lamakan desert in Central Asia 43 113
- Taj k or gin of Dehriwara 43 184
- Taj Muhammad Naib, help of 43 104 107  
113 123
- Tal valley 43 20f
- Tamarsisks 43 21 22 47 109 110 153 185  
169
- Tal river 43 116
- Tarim basin 43 39 47
- Tasp village of Panjgur 43 41
- Tats of Turkestan 43 31 44 170
- Taxila 43 18 189
- Tepe Musi n site 43 34
- Terracotta—  
Figures 43 30 34 37 44 70 91f 96 120  
123 120f 125 136 149 151 153 153f  
158 160 161f 166
- Rechts 43 110
- Absence of figures 43 141
- Thale damh mound near Hoshal 43 114 10
- Thale knur torrent bed 43 100
- Thok valley 43 1 18



















SPECIMENS OF POTTERY FROM SITES IN EAST MALAY





SECTION OF POTTERY FROM SITES IN KUPANI FAULT VALLEY - MALIYAN






THE UNIVERSITY OF CHICAGO LIBRARY












SPECIMENS OF OBJECTS IN CLAY, STONE AND METAL FROM SULEYMANLI AND HANCI DASHI





SPECIMENS OF TOTTERYAL SITS FROM TUTTAL CAVEN. HUANET
























Specimens of pottery and objects in tone and color from Hahltum Mount  
Iluvaity Markan












Sh T v p a




8 2 u



Sh T v 2 b



Sh T v 3 b



Sh T v 3 o




Sh T v f f



8 T 4




Sh T



Sh T v 5 d



Sh T v 8 b




Sh T




















FUNERAL POTTERY FROM BASHITIME MINE AREA, VALLEY MARIAN




















SPECIMENS OF POTTERY FROM KULI AND OTHER SITES IN KOLWA MARIAN








SPECIMEN OF LITHIC AND OBJECT IN CLAY AND CORNELL MUSEUM AND CHANAL L. C. A. MALBAY






FIGURES OF LOTTERY. ALSO OBJECT IN STONE AND CLAY. THE WHITE LINE IS THE MATERIAL.









SPECIMENS OF POTTERY FROM SITES OF KOLWA, HAU AND NUNDALA








SECTIONS OF POTTERY FROM SITES OF HRAI AND NUNDAFA, HETAUWAN






SPECIMENS OF TOLTEC AND OBJECTS IN CLAY FROM SITES OF NUNDALA AND MASHKAT TULATWAY






SPECIMENS OF POTTERY FROM MEHU-DAMP IN MASRAH, HAWAII












SPECIMENS OF POTTERY FROM MEHĀ DĀTĀ, NEAR AL HALĀFĀ





31. FACETTA FIGURINES AND OTHER SMALL OBJECTS IN CLAY, STONE, ETC. FROM MARI FAME MASBE AT  
HATAYAN





OBJECTS IN CLAY FROM NEH DAW MASHKAT AND SPECIMENS OF POTTERY FROM MASHKAT  
SITES SARAWAK














SKETCH PLAN OF SITES AT  
NĀG RAKHSHĀN



SKETCH PLAN OF  
P R SHA HASAN MOUND  
KHĀRĀN








SKETCH PLAN OF  
KARGUSHKI-DAMB  
RAKSHAN

SCALE  
Yards 0 10 20 30 40 50 60 70 80 90 100

Approximate contours at 5 foot intervals






PLAN AND SECTION OF  
EXCAVATED PORTION OF  
RUINED STRUCTURE A  
KARGUSHKI-DAMB

SCALE  
Yards 0 10 20 30 40 50 60 70 80 90 100




SKETCH PLAN OF  
SUKHTAGĒN-DÖR  
DASHT

SCALE



PLAN OF  
SUKHTAGĒN-DÖR  
DASHT

SCALE











SKETCH PLAN OF  
RUINED MOUND  
GATE DAP

SCALE




SKETCH PLAN OF  
SEGAK MOUND

SCALE



SKETCH PLAN OF  
ZIK KALĀT

SCALE



SKETCH PLAN OF  
SINGI KĀ AṬ  
MALĀR


SCALE






SKETCH PLAN OF  
KULLI SITE  
KOLWA

SCALE




ZIK KALI


SKETCH OF ELEVATION  
SHOWING MASONRY OF  
WALL F1 V  
DWELLING I  
BOX E



SKETCH PLAN AND SECTIONS OF  
CURVED DWELLING I




SKETCH PLAN OF DWELLING  
V2





SKETCH PLAN OF  
KULLI SITE  
KOLWA

SCALE  
0 10 20 Yards





SIK-KAL




SKETCH OF ELEVATION  
SHOWING MASONRY ON  
WALL F.A. V  
DWELLING I

SCALE




SKETCH PLAN AND SECTIONS OF  
DWELLING I

SCALE  
0 10 20 Yards



SKETCH PLAN OF DWELLING

SCALE  
0 10 20 Yards





SKETCH PLAN OF  
KULLI SITE  
KOLWA

SCALE

100' 0" 50' 0" 25' 0"

5  
ZIK KAL

SKETCH OF ELEVATION  
SHOWING MASONRY ON  
WALL F/ V  
DWELLING I  
SCALE




SCALE

SKETCH PLAN AND SECTIONS C  
RUINED DWELL

SCALE  
1" = 10' 0"

SKETCH PLAN OF RUINED DWELL

SCALE  
1" = 10' 0"








SKETCH PLAN OF  
MEHĪ-DAMB  
JEBRĪ

SCALE

Yards 0 1 2 3 4 5 6 7 8 9 10


Cultivation





SKETCH PLAN OF  
GABAR BAND  
LAKORIAN

SCALE



ROUGH SKETCH OF  
GABAR BANDS NEAR

UGHAR  
MASHKAI

SCALE










# SKETCH PLAN OF RUINED MOUND GATE-DAP

SCALE


Ya 0. 20 40 60 80 100 Ya d



# SKETCH PLAN OF SEGAK MOUND

SCALE


0 20 40 60 80 100



# SKETCH PLAN OF ZIK-KALĀT

SCALE

Ya 0. 20 40 60 80 100 Ya d



# SKETCH PLAN OF SINGI-KA'ĀT MĀLĀR

SCALE

0 20 40 60 80 100








# SKETCH PLAN OF SHĀHĪ-TUMP TURBAT

SCALE


Yards 0 10 20 30 40 50  
Gordon's of 1 foot reference



## PLAN OF EXCAVATED AREA ON LINE A B

SCALE


Feet 0 10 20 30 40 50



## PLAN OF EXCAVATED AREA SHĀHĪ-TUMP

SCALE


Feet 0 10 20 30 40 50





SKETCH PLAN OF  
BURIAL CAIRNS AT  
ZANGIAN  
TUEBAT



SCf LE





SKETCH PLAN OF  
SUKHTAGĒN-DŌR  
DASHT


SCALE





SKETCH PLAN OF  
SUKHTAGĒN-DŌR  
DASHT

SCALE



CULTIVATION

CULTIVATED

PLAN OF  
FIXED DWELLINGS &  
SUKHTAGĒN-DŌR

SCALE

